INITIAL ENVIRONMENTAL EXAMINATION (IEE)

FOR

CLAY SOIL PRODUCTION PROJECT

MALKARO VILLAGE TRACT, KYAIKMARAW TOWNSHIP, MAWLAMYINE, MON STATE, MYANMAR





December, 2019

Disclaimer

This report has been prepared by 3rd party, E Guard Environmental Services Co., Ltd. for June Cement Industry Limited for the project of Clay Soil Production located at Near Kaw Pa Naw Village, Kyaikmaraw Township, Mon State. The report preparation was done inside the framework of Myanmar EIA Procedure 2015.

The analysis works had been done based on the provided data of the proposed plan of project Government Environmental Authority, Environmental Conservation Department, hereinafter ECD.

The impact assessment and mitigation measure are prepared based on the facts and figures of detail plan/process of the project obtained from the client.

Moreover, this report has been prepared in line with the prevailing active Laws, Rules, Procedure, Guidelines, and Standards etc. of Myanmar Legal System on (Month/Year).

The drawings, sketches, maps and other illustrative figures in this report are for the demonstrative/descriptive purposes only and not to be considered as approved boundary nor accepted territory nor recognized properties extend of any kind.

In case of dual or multiple meanings of the wordings, those wordings should be interpreted as relevant meaning to the concerned areas of discussed in this report.

The individual/personal, organizational and commercial data and information found in this report are included based on the concerned authority's requirement. The privacy and trade secrets concerned are to be addressed to the concerned authority ECD.



<u>Commitment to follow Environmental Conservation Law, Rules and</u> <u>Regulation, Environmental Standards and Mitigation Measures Stated in the</u> <u>Environmental Management Plan (EMP) of IEE Reports</u>

With regard to the above matter, we, June Cement Industry Limited has established for related projects (Jetty construction, channel construction, clay soil production and laterite production) needed for Cement plant. Our company strongly commits that all our operations will be performed in an environmentally friendly manner by following Environmental Conservation Law 2012, Environmental Conservation Rules 2014, Environmental Impact Assessment Procedure and National Environmental Quality (emission) Guidelines (2015) and relevant environmental standards through successful implementation of mitigation measures stated in the Environmental Management Plan (EMP), EMOP, CSR Plan and Grievance Redress Mechanism of IEE Reports.

1802

Myint Soe Managing Director June Cement Industry Ltd;



No. (11), Airport Avenue Road, (@codőőőősoscoða) Yangon Airport Road, Saw Bwar Gyi Gone Quarter, Insein Township, Yangon 11011, Myanmar. Tel: (95) 1 666512 Fax: (95) 19667757 H.P (95) 9 44801676



Commitment to follow and compliance with Environmental Conservation Law, Rules, Environmental Impact Assessment Procedure, National Environmental (Quality) Emission Guidelines, Standards and Mitigation Measures Stated in the Environmental Management Plan (EMP) of IEE reports

With regard to the above matter, we, E Guard Environmental Services has prepared the Initial Environmental Examination (IEE) Reports for related projects (Jetty construction, channel construction, clay soil production and laterite production) needed for Cement plant. Our company strongly commits that this IEE report has been prepared by following Environmental Conservation Law (2012), Environmental Conservation Rules (2014), Environmental Impact Assessment Procedure (2015), National Environmental (Quality) Emission Guidelines (2015) and relevant environmental standards through successful implementation of mitigation measures and monitoring plan stated in the Environmental Management Plan (EMP) of IEE Reports.

E guard Environmental Services

it into a

ם צים

<u>Report Review Form</u>

٦

Report Title: Initial Environmental Examination (IEE) Report For Clay Soil Production Project		
Report Version: Version-00		
Proponent:	Prepared by;	
June Cement Industry Limited No.80, Sayar San Street, Bahan Township, Yangon. Tel: +9592005445/ +9519010660 Fax: +9519010080 tinoo.june@gmail.com	E Guard Environmental Services Co., Ltd. No. (145-A2-3), Thiri Mingalar Street, Ward No. (4), Mayangone Township, Yangon 11062, Myanmar. Tel: 01 667953, Fax: 01 6667953, info@eguardservices.com Mobile: +959 797005199	
Prepared by: U Kyaw Soe Moe	Position: Project Associate	
Submitted Date: 25 /11/2019	Signature:	
Checked by: U Aung Myint Myat	Position: Associate Consultant	
Checked Date: 28/11/2019	Signature:	
Summary: IEE Report This document presents Initial Environmental Examination (IEE) report as required for clay soil production project.	Approved by:	

Distribution:

Г



Internal

Public

Confidential



Contents

List of 7	Гables	VI
Executiv	ve Summary	1
CHAPT	ER 1	11
INTRO	DUCTION	11
1.1	BACKGROUND OF THE STUDY	11
1.2	SCOPE OF THE STUDY	12
1.3	MATERIALS AND METHODS	13
CHAPT	TER 2	16
PROJE	CT DESCRIPTION	16
2.1	BASIC PROJECT INFORMATION	16
2.2	INVESTMENT PLAN	17
2.3	LOCATION OF PROJECT, OVERVIEW MAP AND SITE LAYOU	T PLAN17
2.3	.1 Location of Project and Overview Map	17
2.4	PRODUCTION PROCESS	18
2.5	HUMAN RESOURCE REQUIREMENT	20
2.6	REQUIREMENT OF MACHINERY AND EQUIPMENT	20
2.7	AMOUNT OF PRODUCTION	21
2.8	WATER REQUIREMENT AND CONSUMPTION	21
2.9	SOURCE OF POWER SUPPLY AND DIESEL CONSUMPTION	22
2.10	PRODUCTION PROCESS AMOUNT OF WASTES/SOLID, LIQU 22	JID AND GAS
2.1	0.1 Solid Waste	22
2.1	0.2 Liquid Waste	22
2.1	0.3 Gas Emission	22
2.11	PROJECT ALTERNATIVES	24
CHAPT	TER 3	25
IDENTI	IFICATION OF THE PROJECT PROPONENT	25
3.1	PROJECT PROPONENT INFORMATION	25
CHAPT	TER 4	26
IDENTI	IFICATION OF THE IEE EXPERTS	26
4.1	STUDY TEAM FOR INITIAL ENVIRONMENTAL EXAMINATION	DN26



CHAPTER 5	29
POLICY, LEGAL AND INSTITUTIONAL FRAMEWORK	29
5.1 INSTITUTIONAL FRAMEWORK FOR ENVIRONMENTAL CONSERV 29	VATION
5.2 NATIONAL LAWS AND REGULATIONS	29
Employment and Skill Development Law (2013)	31
CHAPTER 6	
DESCRIPTION OF THE SURROUNDING ENVIRONMENTAL AND CONDITIONS	SOCIAL
6.1 METHODOLOGY	
6.2 PHYSICAL ENVIRONMENT	
6.2.1 Climate and Rainfall	
6.2.2 Topography	
6.2.3 Hydrology	
6.2.4 Access and Transportation	
6.3 ENVIRONMENTAL QUALITY MEASURING	
6.3.1 Ambient Air Quality	40
6.3.2 Ambient Noise	40
6.3.3 Water Quality	40
6.3.4 Environmental Quality Measuring and Sampling Locations	41
6.4 ENVIRONMENTAL QUALITY ANALYSIS	42
6.4.1 Ambient Air Quality	42
6.4.2 Ambient Noise	46
6.4.3 Wind Speed and Direction	48
6.4.4 Water Quality	48
6.4.5 Soil Quality	50
6.5 ECOSYSTEM	51
6.6 SOCIAL ENVIRONMENT	56
6.7 SOCIAL-ECONOMIC SURVEY RESULTS	59
CHAPTER 7	60
IDENTIFICATION AND ASSESSMENT OF POTENTIAL ENVIRONMIMPACTS	1ENTAL 60
7.1 IDENTIFICATION AND ASSESSMENT OF POTENTIAL ENVIRONM IMPACTS	1ENTAL 60



7.2 O	BJECTIVE	60
7.3 PH	ASES OF CLAY SOIL PRODUCTION PROJECT	61
7.4 M	ETHODOLOGY & APPROACH FOR IMPACT ASSESSMENT	61
7.5 PC	DTENTIAL ENVIRONMENTAL IMPACTS IDENTIFICATION	AND
ASSESS	MENT	62
7.5.1	Impact on Aesthetics resources	63
7.5.2	Impacts on Air Quality	63
7.5.3	Odor	64
7.5.4	Impacts on Noise and Vibration	64
7.5.5	Impacts on Soil Quality and Terrestrial Ecosystem	65
7.5.6	Impacts on Water Quality and Aquatic Ecosystem	65
7.5.7	Waste Generation	66
7.5.8	Fire Hazards	67
7.5.9	Impacts on Occupational and Community Health and Safety	67
7.5.10	Socio-economic Resources during All Stages of the Mine Cycle	67
7.6 EI	NVIRONMENTAL IMPACT AND SIGNIFICANCE	68
7.7 SU	JMMARY OF IMPACTS SIGNIFICANCE	74
7.8 M	ITIGATING ADVERSE IMPACTS OF THE PROPOSED PROJECT	75
7.8.1	Mitigation Measures on Aesthetics	75
7.8.2	Mitigation Measures of Air Quality	76
7.8.3	Mitigation Measures of Odor	76
7.8.4	Mitigation Measures of Noise and Vibration	76
7.8.5	Mitigation Measures of Soil Quality and Terrestrial Ecosystem	77
7.8.6	Mitigation Measures of Water Quality and Aquatic Ecosystem	77
7.8.7	Mitigation Measures of Waste Generation	78
7.8.8	Mitigation Measures of Fire Hazards	79
7.8.9	Mitigation Measures of Occupational Health and Safety	80
7.8.10	Mitigation Measures of Community Health and Safety	81
CHAPTER	8	82
PUBLIC C	ONSULTATION AND INFORMATION DISCLOSURE	82
8.1 M	EETING PURPOSE OF THE PUBLIC CONSULTATION	AND
INFORM	IATION DISCLOSURE	82
8.2 M	ETHODOLOGY AND APPROACH	82
CHAPTER	9	89



INSTIT	UTIONAL REQUIREMENT AND ENVIRONMENTAL MANAGEM	ENT PLAN 	
9.1	RESPONSIBLE PERSON FOR EMP	90	
9.2	ENVIRONMENTAL MANAGEMENT PLAN	91	
9.3	ENVIRONMENTAL MONITORING PLAN	103	
9.4	COST ESTIMATION FOR EMP	106	
9.5	OCCUPATIONAL HEALTH AND SAFETY PLAN	107	
9.6	COMMUNITY HEALTH AND SAFETY PLAN	108	
9.7	EMERGENCY PREPAREDNESS AND RESPONSE PROCEDURES.	108	
9.7	.1 Fire Prevention, Preparedness and Response	108	
9.7	.2 Landslide Prevention, Preparedness and Response	111	
9.7	.3 Emergency Communications (Kyaikmaraw Township)	113	
9.8	TOPSOIL MANAGEMENT PLAN	113	
9.8	.1 Vegetation and Topsoil Management	114	
9.9	MINE CLOSURE PLAN	114	
9.10	CORPORATE SOCIAL RESPONSIBILITY (CSR) PLAN	117	
9.11	COMMUNITY GRIEVANCE REDRESS MECHANISM	117	
СНАРТ	ER 10	119	
CONCI	LUSIONS AND RECOMMENDATIONS	119	
10.1	CONCLUSION	119	
10.2	RECOMMENDATIONS FOR FUTURE WORKS		
10.3 Proje	Disclosing of Initial Environmental Examination (IEE) for Clay Soil	Production	
Referen	ces		
APPEN	DIX 1- Surface Water Quality Laboratory Result (1)		
APPEN	DIX 2- Surface Water Quality Laboratory Result (2)	126	
APPEN	DIX 3 – Soil Quality Laboratory Result	129	
APPEN	DIX 4 – Presentation File	130	
APPEN	DIX 5 - Public Consultation (Original Attendants' Sheets with Signatures)143	
APPEN	DIX 6 - Company Registration	150	
APPEN	DIX 7 - Using farmland by other means permit	151	
APPENDIX 8 – Plot numbers for Clay soil production			
APPEN	DIX 9 - Corporate Social Responsibility		
APPEN	DIX 10 - Consultant Registration Certificate	165	



List of figures

Figure 1. 1 Schematic Processes of Environmental Approval	2
Figure 2. 1 Location Map of the Proposed Project Site17	7
Figure 2.2 Layout Plan of the Proposed Project Site	8
Figure 2.3 Production Process Flow Chart of proposed project	C
Figure 2.4 Bulldozer	1
Figure 2.5 Dump Trucks	1
Figure 2.6 Excavator	1
Figure 2.7 Wheel loader	1
Figure 6. 1 Project Location	9
Figure 6. 2 Environmental Quality Monitoring Locations	2
Figure 6.3 PM Monitoring Results at Project Site	4
Figure 6.4 Fluctuation of Air Pollutants dial cycle at Project Site4	5
Figure 6.5 Air quality measure	5
Figure 6.6 Air and Wind Measurement40	5
Figure 6.7 Noise Level at Clay soil	5
Figure 6.8 Noise quality measure	7
Figure 6.9 Noise quality measure47	7
Figure 6.10 Wind Speed and Wind Direction (Blowing From) at Clay soil48	8
Figure 6.11 Wind Class Frequency Distribution at Clay soil	8
Figure 6.12 Surface Water quality measure	0
Figure 6. 13 Soil quality measured	1
Figure 7. 1 Potential Impact of the Proposed Project	C
Figure 7.2 Summary of Impact Significance Level due to Project Activities75	5
Figure 8. 1 Public Consultation of Initial Environmental Examination for related projects in	n
Cement Plant by June Cement Industry Ltd	8
Figure 9. 1 Environmental Management in Project Cycle	9
Figure 9.2 Components of a Fire Extinguisher	9
Figure 9.3 Types of Fire Extinguishers	C
Figure 9.4 Examples of low-cost retaining walls112	2
Figure 9.5 Tree roots help holding the different soil layers together and hinder landslide 112	2
Figure 9.6 Steps of Grievance Redress Mechanism of June Cement Industry Limited118	8



List of Tables

Table 1. 1 Describes the devices used to collect baseline environmental data for the propos	sed
project	.14
Table 2. 1 Project Information	.16
Table 2. 2 Human Resources Requirement	.20
Table 2. 3 Machine and Equipment List of the Project Site	.21
Table 2. 4 Quantity of CO2 Emissions from the Generator	.23
Table 2. 5 EBRD Standard of CO2 Emission	.23
Table 3. 1 Project Proponent Information	.25
Table 4. 1 IEE Study Team and their Responsibility	.26
Table 5. 1 Relevant National Laws and Regulations of Myanmar	.29
Table 6. 1 Ambient Air Quality Parameters	.40
Table 6.2 Noise level monitoring	.40
Table 6.3 Environmental Quality Parameters for Water Quality	.41
Table 6.4 Equipment for water sampling	.41
Table 6.5 Location of Sampling Points	.42
Table 6.6 The result of Particulate Matter (PM10 and PM2.5) compared with NEQ Guidel	ine
(24hrs. continuous)	.43
Table 6.7 The result of Nitrogen Dioxide compared with NEQ Guideline (24hrs continuo	us)
	.44
Table 6.8 The result of Sulphur Dioxide compared with NEQ Guideline (24 hrs continuo	us)
	.44
Table 6.9 The result of Ozone compared with NEQ Guideline (8 hrs continuous)	.45
Table 6.10 National Environmental Quality (Emission) Guideline Value for Noise Level	.47
Table 6. 11 Noise Level Measured within the Proposed Project	.47
Table 6. 12 Surface Water Quality Results	.49
Table 6. 13 Soil Quality Result	.50
Table 6. 14 Flora Species Found in Kyaikmaraw Township	.51
Table 6. 15 Fauna Species Found in Kyaikmaraw Township	.53
Table 6.16 Ethnic Groups Living in Kyaikmaraw Township	.57
Table 6.17 Total Households/ Families of Kyaikmaraw Township	.57
Table 6.18 Total Populations of Kyaikmaraw Township	.58
Table 6.19 Forests in Kyaikmaraw Township	.58
Table 6.20 Forest Products of Kyaikmaraw Township	.58
Table 6.21 Mineral Production of Kyaikmaraw Township	.58
Table 6. 22Types of Land Use in Kyaikmaraw Township	.59
Table 7. 1 Tentative Schedule for clay soil Mining Operation Activities	.61
Table 7.2 Impact Assessment Parameters and Its Scale	.62
Table 7. 3 Impact Significance	.62
Table 7. 4 Analysis Potential Impacts during Preparation Phase	.68
Table 7.5 Analysis Potential Impacts during Operation Phase	.70
Table 7.6 Analysis Potential Impacts during Decommissioning/Closure Phase	
Table 7.6 Analysis I otential impacts during Decommissioning/Closure I hase	.73



Table 7. 8 Personal Protective Equipment (PPE) and Their Functions	80
Table 7. 9 Safety Signage and Their Descriptions during the Operation Phase	80
Table 8. 1 Meeting Records	83
Table 9. 1 Responsible Person for EMP	90
Table 9.2 Environmental Management Plan for Preparation Phase	92
Table 9. 3 Environmental Management Plan for Operation Phase	95
Table 9.4 Environmental Management Plan for Decommission Phase	99
Table 9.5 Environmental Monitoring Plan	103
Table 9.6 Cost Estimation for EMP Implementation	106
Table 9.7 Tentative Schedule for OHSE plan	107
Table 9.8 Types of Fires	109
Table 9.9 Uses of a Fire Extinguisher Properly	110
Table 9.10 Safety Tips on Fire	111
Table 9. 11Safety Tips on Landslide	112
Table 9.12 During Landslide and After a Landslide	112
Table 9.13 Emergency Contacts	113
Table 9. 14 Corporate Social Responsibility Plan	117



Executive Summary

June Cement Industry Limited proposed to conduct the Initial Environmental Examination (IEE) report for proposed clay soil production, near Malkaro Village, Kyaikmaraw Township, Mon State. The investor submitted a project investment proposal on August 19, 2015 to the Myanmar Investment Commission (MIC) and then, for the environmental approval and comments of the Ministry of the Natural Resources and Environmental Conservation (MONREC). As per the comments of ECD, the proposed project needs to submit IEE report. Therefore, June Cement Industry Limited commissioned E Guard Environmental Services for IEE report study. The specific objectives of this study are to;

1) Identify the major impacts that may arise from the activities of the proposed project on natural environment and socio-economic environment of the project area,

2) Describe the mitigation measures to minimize these impacts,

3) Prepare and implement Environmental Management Plan for the project and

4) Make sure that IEE is developed sufficiently and soundly for the proposed project.

5) Implement Corporate Social Responsibility Plan (CSR Plan) which plays an essential part for the improvement of the social welfare of the community as well as the development of the region.

E Guard Environmental Services prepared this IEE report in accordance with EIA procedure (2015) and National Environmental Quality (Emissions) Guidelines (2015). This IEE report identifies all possible potential impacts to be caused by the construction, operation and decommissioning for the clay soil production. The proposed project background and scope of the study are described in **Chapter 1**.

The elevation of project area is 18 ft above the sea level. The intended project period will be 30 years. The purpose of the project is to provide clay soil for June Cement Production during the operational phase, to provide employment opportunities for local residents and to have good access along the road for those villagers living close to Kaw Pa Naw Village. Open cast mining method will be used for clay soil production and there will be no drilling and blasting operations due to the soft nature of clay soil. It will excavate directly from its in situ position by excavator and so no over burden dumps and no waste stockpile will be generated from the clay soil production. Major use of utilities such as water, electricity and fuel requirement, human resources, use of vehicles, amount of production and generated wastes, are also mentioned in **Chapter 2.**

The proposed project proponent is June Group Company Limited, which is a 100 % local investment. Detailed information of the project proponent and IEE experts are described in **Chapter 3 and 4**.

The brief summary of relevant national environmental legislations such as Environmental Impact Assessment Procedure (2015) and National Environmental Quality (emission) Guidelines, established by the Ministry of Natural Resources and Environmental Conservation (MONREC) and overview of current local and international environmental and social policies including related international or regional convention for the proposed project were also described in **Chapter 5**.



For environmental baseline data were collected by onsite measurements analysis for air quality and noise level at proposed project site. Surface water and soil samples were also collected and sent to respective laboratories and then the analyzed lab results can be seen in **Appendix 1 and Appendix 3**. Moreover, secondary data collection of proposed project site area such as physical/biological environment, and weather data and land use were collected from the township data of Kyaikmaraw Township, Mon State. Environmental quality baseline data collection conducted on 14th to 15th March, 2019 and detail analysis results of air quality, noise level and water quality results are described in **Chapter 6**.

The project activities during the whole project period (construction, operation and decommissioning) could have negative and positive impacts on the existing environment. The following methodology has been applied to assess the environmental impacts of the clay soil production mainly on air, water, land, biodiversity including human beings. Qualitative assessment is used and each source of impact has been assessed in the following method.

Accessment	Scale				
Assessment	1	2	3	4	5
Magnitude (M)	Insignificant	Small and have no effect on environment	Moderate and will result in minor changes on environment	High and will result in minor changes on environment	Very High and will result in permanent change on environment
Duration (D)	0-1 year	2-5 year	6-15 year	Life of operation	Post closure
Extent(E)	Limited to the site	Limited to local area	Limited to region	National	International
Probability (P)	Very improbable	Improbable	Probable	Highly probable	Definite

Then, the Significant Point (SP) is calculated by following formula.

Significant Point (SP) = (Magnitude+ Duration+ Extent) * Probability

Impact Significance: Based on calculated significant point, impact significance can be categorized as follows:

Explanation

Significant Point (SP) = (Magnitude+ Duration+ Extent) * Probability Impact Significance

Significant Point (SP)	Impact Significance
<15	Very low
15-29	Low
30-44	Moderate
45-59	High
<60	Very High





Figure-Summary of Significance of impact

According to the analysis of these results, most of the project activities are low significance and some are moderate and high significance which need to improve for environmental performance. Social and economic developments are positive impacts of the proposed project. Potential negative impacts and mitigation measures of the proposed project are described in **Chapter 7**.

Public consultation meeting was held on 15th June, 2019 at Malkaro Village, Kyaikmaraw Township, Mon State. U Tin Oo (Project manager) explained about the proposed project, type of investment and also their future plan. And then, U Tin Aung Moe (Director) also explained about the objective of IEE study, baseline data collection and prediction of environmental impact and effective impact mitigation measure and preparation of EMP plan including with Environmental Monitoring Pan and CSR plan etc. Detail comments, suggestions, questions and answers are described in **Chapter 8**.

The Environmental Management Plan (EMP) identifies potential environmental impacts, source of impacts, how to mitigate these impacts and residual impacts after mitigation and responsible persons for all three phases. Due to the activities of the proposed project for all phases, the environmental qualities like air, water, soil and noise, fire hazards, occupational health and safety, waste disposal can have negative impacts but for the socioeconomic, it can be positive impact. And also, the mitigation measures for these negative impacts are fully mentioned in this EMP section. The Environmental Monitoring Plan (EMOP) identifies parameters, frequency and responsible party to monitor for air, water and noise level for all phases. The cost estimation for EMP plan will be cost about 433,850 USD. The Corporate Social Responsibility (CSR) Plan aims to secure social well-being of the employees and their family members, better community living and transparent and friendly relationship with neighboring communities. The Grievance Redress Mechanism (GRM) identifies the steps to solve complaints related with the proposed project. The **Emergency** Preparedness and Response Plan identifies how to overcome emergency cases and effectively. This EMP has, in brief, systematically explored all possible positive and negative environmental impacts of the proposed project and identified mitigation and monitoring



measures on negative impacts which can occur in all three phases. The detail information for the plans is described in **Chapter 9.**

In Conclusion, the environmental management practices, procedures and responsibilities are defined here in to get full compliance with the existing environmental policy, laws, rules and instructions of the Republic of the Union of Myanmar. All the feedbacks, desires and needs of local public recorded in public consultation meetings are also well addressed and incorporated in formulation of EMP.



အစီရင်ခံစာအကျဉ်းချုပ်

ဤကနဦးပတ်ဝန်းကျင်ဆန်းစစ်ခြင်းအစီရင်ခံစာသည် မွန်ပြည်နယ်၊ ကျိုက်မရောမြို့နယ်၊ မယ်ကရိ ကျေးရွာအနီးတွင်ဆောင်ရွက်မည့် ရွံစေးမြေတူးဖော်ရေးလုပ်ငန်းအတွက် ဇွန်ဘိလပ်မြေစက်ရံ လီမိတက်မှ အဆိုပြုတင်ပြသော အစီရင်ခံစာဖြစ်ပါသည်။ စီမံကိန်းအဆိုပြုသူသည် ၂၀၁၅ ခုနှစ်၊ ဩဂုတ်လ (၁၉) ရက်နေ့တွင် မြန်မာနိုင်ငံရင်းနှီးမြှုပ်နှံမှုကော်မရှင် (MIC) သို့ စီမံကိန်းရင်းနှီးမြှုပ်နှံမှု အဆိုပြုလွှာကို လျှောက်ထားခဲ့ပါသည်။ ထို့နောက်အဆိုပြုစီမံကိန်းဆိုင်ရာ လျှောက်လွှာအပေါ် ပတ်ဝန်းကျင်ထိန်းသိမ်းရေး ဆိုင်ရာသဘောထားမှတ်ချက်ရယူရန်အတွက် သယံဧာတနှင့်သဘာဝ ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဝန်ကြီး ဌာနသို့ ဆက်လက်တင်ပြခဲ့ပြီး လမ်းညွှန်ချက်တောင်းခံခဲ့ ပါသည်။ ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဦးစီးဌာန၏ သဘောထားမှတ်ချက်အရ အဆိုပြုစီမံကိန်းသည် ကနဦးပတ်ဝန်းကျင်ဆန်းစစ်ခြင်း အစီရင်ခံစာတင်သွင်းရန် ညွှန်ကြားလာပါသည်။ ထို့ကြောင့် ဇွန်ဘိလပ်မြေစက်ရုံလီမိတက်သည် ရွံစေးမြေတူးဖော်ခြင်းလုပ်ငန်း လုပ်ဆောင်နိုင်ရန်အတွက် ကနဦးပတ်ဝန်းကျင်ဆန်းစစ်ခြင်း အစီရင်ခံစာရေးဆွဲရန် အီးဂတ်ပတ်ဝန်းကျင် ဆိုင်ရာဝန်ဆောင်မှုလုပ်ငန်းကို ငှားရမ်းခဲ့ပါသည်။ ဤလေ့လာဆန်းစစ်ခြင်း၏ အဓိကရည်ရွယ်ချက်များမှာ-

- သဘာဝပတ်ဝန်းကျင်နှင့်လှုမှုစီးပွားပတ်ဝန်းကျင် တို့အပေါ် စီမံကိန်းဆောင်ရွက်ချက်များ ကြောင့် ထိခိုက်မှုများကိုလေ့လာရန်။
- ထိခိုက်မှုများကို လျှော့ချနိုင်ရန် လျော့နည်းစေမည့်နည်းလမ်းများကို ဖော်ပြရန်။
- စီမံကိန်းအတွက် ပတ်ဝန်းကျင်စီမံခန့်ခွဲမှုအစီအစဉ်ကို ပြင်ဆင်ရန်နှင့် အကောင်အထည် ဖော်ရန်။
- စီမံကိန်းအတွက် လုံလောက်တိကျသော ကနဦးပတ်ဝန်းကျင်ဆန်းစစ်ခြင်းလုပ်ဆောင်မှု ရှိစေရန်။
- ဒေသခံများ၏လူမှုရေးရာ သက်သာချောင်ချိမှုများ တိုးတက်ရန်နှင့် ဖွံ့ဖြိုးတိုးတက်မှုများ အတွက် မရှိမဖြစ်အရေးပါသော လူမှုစီးပွားတာဝန်ယူမှုအစီအစဉ်အား အကောင်အထည်ဖော် ဆောင်ရွက်ရန်တို့ဖြစ်ပါသည်။

အီးဂတ်ပတ်ဝန်းကျင်ဆိုင်ရာဝန်ဆောင်မှုလုပ်ငန်းသည် ဤအစီရင်ခံစာကို ပတ်ဝန်းကျင်ထိန်းသိမ်း ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းဆိုင်ရာ ရေးဦးစီးဌာနမု ထုတ်ပြန်ခဲ့သော လုပ်ထုံးလုပ်နည်း၊ အမျိုးသားပတ်ဝန်းကျင်ဆိုင်ရာ အရည်အသွေး လမ်းညွှန်ချက်များနှင့်အညီ (ထုတ်လွှတ်မှု) ဆောင်ရွက်ခဲ့ပါသည်။ ဤအစီရင်ခံစာတွင် ရွံ့စေးမြေတူးဖော်ခြင်းလုပ်ကွက် ပြင်ဆင်ခြင်းကာလ၊ လုပ်ငန်းဆောင်ရွက်လည်ပတ်ခြင်းကာလ နှင့် လုပ်ငန်းဖျက်သိမ်းရေးကာလတို့တွင် ဖြစ်ပေါ်နိုင်ခြေ ရှိသော သက်ရောက်နိုင်မှုများအားလုံးကို ဖော်ပြထားပါသည်။ အဆိုပြုစီမံကိန်း၏ နောက်ခံသမိုင်း အကြောင်းအရာနှင့် လေ့လာမည့်နယ်ပယ် တို့ကိုလည်း အခန်း (၁) တွင်ဖော်ပြထားပါသည်။

စီမံကိန်းတည်နေရာသည် ပင်လယ်ရေမျက်နှာပြင်အထက် (၁၈) ပေ တွင်တည်ရှိပြီး ခန့်မှန်းလုပ်ငန်း ဆောင်ရွက်မှုကာလမှာ နှစ် (၃၀) ဖြစ်ပါသည်။ လုပ်ငန်းဆောင်ရွက်ခြင်းရည်ရွယ်ချက်များမှာ လုပ်ငန်းလည်ပတ်စဉ်ကာလရွံ့စေးမြေထောက်ပံ့မှုပေးနိုင်ရန်၊ ဒေသခံတို့အလုပ်အကိုင်အခွင့်အလမ်း များ ရရှိစေရန်နှင့် ကျေးရွာတွင်းလမ်းပန်းဆက်သွယ်ရေး ဖွံ့ဖြိုးလာစေရန်တို့ဖြစ်သည်။ ရွံ့စေးမြေ ထုတ်လုပ်ခြင်းကို ဟင်းလင်းဖွင့်နည်းစဉ်ကိုအသုံးပြုဆောင်ရွက်သွားမည်ဖြစ်ကာ ရွံ့စေးမြေ၏ ပျော့ပြောင်းမှု သဘောသဘာဝကြောင့်လွန်တူးခြင်းနှင့်ယမ်းခွဲခြင်းတို့မပါဝင်ပါ။



ရွံ့စေးမြေတူးဖော်ခြင်းကိုစက်ယန္တရားများဖြင့်သာ တိုက်ရိုက်တူးဖော် ပို့ဆောင်သွားမည်ဖြစ်သော ကြောင့် စွန့်ပစ်မြေစာနှင့်မြေစာပုံထားရှိခြင်းမရှိပါ။ လုပ်ငန်းဆိုင်ရာအချက်အလက် များဖြစ်သည့် စက်ယန္တရားအသုံးပြုမှု၊ လူအင်အားပမာဏ၊ လျှပ်စစ်နှင့်လောင်စာဆီအသုံးပြုမှု၊ ရေလိုအပ်ချက်၊ ထုတ်လုပ်မှုပမာဏနှင့် ထွက်ရှိမည့် စွန့်ပစ်ပစ္စည်းတို့ကို အခန်း (၂) တွင်ဖော်ပြထားပါသည်။

စီမံကိန်းအဆိုပြုသူသည် ဇွန်အုပ်စုကုမ္ပဏီလီမိတက်ဖြစ်ပြီး ရာနှုန်းပြည့်ပြည်တွင်းရင်းနှီးမြှုပ်နှံမှု ဖြစ်သည်။ စီမံကိန်းအဆိုပြုသူနှင့် ပတ်ဝန်းကျင်ဆိုင်ရာလေ့လာမှုဆောင်ရွက်သည့်အဖွဲ့အစည်းဆိုင်ရာ အချက်အလက် တို့ကို အခန်း (၃) နှင့် (၄) တွင်အသေးစိတ်ဖော်ပြထားပါသည်။

အဆိုပြုစီမံကိန်းနှင့်ပတ်သက်ဆက်စပ်ပြီး လိုက်နာရမည့် ဥပဒေနှင့်နည်းဥပဒေများ၊ သယံဇာတ နှင့် သဘာဝပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဝန်ကြီးဌာန (MONREC) မှ ထုတ်ပြန်ထားသော ပတ်ဝန်းကျင် ထိခိုက်မှုဆန်းစစ်ခြင်းဆိုင်ရာလုပ်ထုံးလုပ်နည်းများ၊ အမျိုးသားပတ်ဝန်းကျင်ဆိုင်ရာ အရည်အသွေး (ထုတ်လွှတ်မှု) လမ်းညွှန်ချက်များ၊ စီမံကိန်းနှင့်သက်ဆိုင်သည့်ဒေသတွင်း (သို့) အပြည်ပြည်ဆိုင်ရာ သဘာဝပတ်ဝန်းကျင်နှင့် လူမှုပတ်ဝန်းကျင်ဆိုင်ရာမူဝါဒ၊ ဆက်စပ်နေသောသဘောတူညီချက်များကို အခန်း (၅) တွင် အသေးစိတ် ဖော်ပြထားပါသည်။

စီမံကိန်းလုပ်ငန်းဆောင်ရွက်နေစဉ်ကာလအတွင်း စီမံကိန်းနေရာ၏ လက်ရှိသဘာဝပတ်ဝန်းကျင် ဆိုင်ရာ အခြေခံအချက်အလက်များဖြစ်သည့် ဆူညံမှုတိုင်းတာခြင်း၊ လေထုအရည်အသွေးတိုင်း တာခြင်းတို့ကို ကွင်းဆင်းတိုင်းတာခဲ့ပါသည်။ မြေပေါ်ရေအရည်အသွေးနှင့် မြေအရည်အသွေးနမူနာ ကောက်ယူပြီး သက်ဆိုင်ရာဓာတ်ခွဲခန်းများသို့ပို့ကာ စစ်ဆေးမူများပြုလုပ်ပြီးရလဒ်များအား နောက်တွင်ပါရှိသည့် နောက်ဆက်တွဲ (၁၊ ၂၊ ၃) တွင်ဖော်ပြထားပါသည်။ ထို့အပြင်အဆိုပြုစီမံကိန်း တည်နေရာနှင့်သက်ဆိုင်သည့် အခြေခံအချက်လက်များ ဖြစ်သည့်လူမှုစီးပွားအခြေအနေ၊ ရူပဆိုင်ရာ အချက်အလက်၊ ဇီဝပတ်ဝန်းကျင် ဆိုင်ရာအချက်အလက်၊ ရာသီဥတုဆိုင်ရာသတင်းအချက်အလက်များစသည်တို့ကို မွန်ပြည်နယ်၊ ကျိုက်မရော မြို့နယ်မှပြဋ္ဌာန်းထားသော မြို့နယ်ဆိုင်ရာအချက်အလက်များမှစုဆောင်းထားပါသည်။ ပတ်ဝန်းကျင် အရည်အသွေးဆိုင်ရာ အချက်အလက်များကွင်းဆင်းတိုင်းတာမှုအား ၂၀၁၉ခုနှစ်၊ မတ်လ (၁၄)ရက် နှင့် (၁၅) ရက်နေ့များတွင်လုပ်ဆောင်ခဲ့ပြီး ရရှိလာသောလေအရည်အသွေးရလဒ်၊ ဆူညံမှုအတိုင်းတာမူရလဒ်၊ မြေပေါ်ရေ အရည်အသွေး တို့၏ အသေးစိတ်အချက်အလက်များကို အခန်း (၆) တွင်ဖော်ပြထားပါသည်။

စီမံကိန်းအကောင်အထည်ဖော်သည့်ကာလများ (တည်ဆောက်ရေးကာလ၊ လုပ်ငန်းများလည်ပတ် ဆောင်ရွက်သည့်ကာလ နှင့် စီမံကိန်းဖျက်သိမ်းရေးကာလများ) တွင်ဆောင်ရွက်သောလုပ်ငန်း များကြောင့် ပတ်ဝန်းကျင်အပေါ်တွင် ကောင်ကျိုး နှင့် ဆိုးကျိုးများဖြစ်ပေါ်စေနိုင်ပါသည်။ အောက်ဖော်ပြပါ ဆန်းစစ်သည့်နည်းလမ်းတွင် လေ၊ ရေ၊ မြေ၊ လူအပါအဝင် ဇီဝမျိုးစုံမျိုးကွဲများအပေါ် ထိခိုက်မှုများကိုလေ့လာဆန်းစစ်ခြင်းဖြစ်ပါသည်။ စီမံကိန်းလုပ်ဆောင်ရာ လုပ်ငန်းစဉ်အလိုက် ပတ်ဝန်းကျင် အပေါ်သက်ရောက်နိုင်မှုများကို အောက်တွင်ဖော်ပြထားပါသည်။



ကန်းစစ်ခြင်း	သတ်မှတ်ချက်				
ဆရးဖဖခြင်း	Э	J	2	9	ງ
ပြင်းအား	မသိသာ	သိသာမှု အနည်းငယ်ရှိပြီး လုပ်ငန်းခွင်တွင် သက်ရောက်မှု မရှိ	သိသာမှု အလည် အလတ်ရှိပြီး လုပ်ငန်းခွင်တွင် သက်ရောက်မှု အနည်းငယ်ရှိ။	သိသာမှုများပြီး လုပ်ငန်းခွင်တွင် သက်ရောက်မှု ထင်ရှား။	သိသာမှု အလွန် များပြီး လုပ်ငန်းခွင်တွင် ပြောင်းလဲမှု ထင်ရှား။
ကြာချိန်	၀– ၁ နှစ်	၂– ၅ နှစ်	၆– ၁၅ နှစ်	လုပ်ငန်း လည်ပတ်ချိန် တစ်လျှောက်	လုပ်ငန်း ဖျက်သိမ်းသည် အထိ
ပျံ့နှံ့နိုင်မှု	လုပ်ငန်းခွင် အတွင်းသာ	အနီးအနား ပတ်ဝန်းကျင်ထိ	ဒေသတွင်း	နိုင်ငံတွင်း	နိုင်ငံတကာထိ
ဖြစ်နိုင်စွမ်း	လုံးဝ မဖြစ်နိုင်	မဖြစ်နိုင်	ဖြစ်နိုင်သည်	အလွန်ဖြစ်နိုင် သည်။	ဖြစ်နိုင်မှု သေချာသည်။

ထိခိုက်မှုများကို အောက်ဖော်ပြပါ ပုံသေနည်းအတိုင်းတွက်ချက်သည်။

ထင်ရှားမှု= (ပြင်းအား+ ကြာချိန်+ ပျံ့နှံ့နိုင်မှု) * ဖြစ်နိုင်စွမ်း

ထိခိုက်မှုများ၏ ထင်ရှားမှုများကိုအောက်ပါအတိုင်း အပိုင်းငါးပိုင်းခွဲခြားနိုင်သည်။

ထင်ရှားမှု	ထိခိုက်မှုများ၏ ထင်ရှားမှု
<ാ၅	အရမ်းနည်းသည်။
၁၅−၂၉	နည်းသည်။
2 0-66	အလယ်အလတ်ဖြစ်သည်။
୨೨−୭୧	မြင့်သည်။
>ଓ୦	အလွန်မြင့်သည်။





ထိခိုက်နိုင်မှုများကို လေ့လာဆန်းစစ်ချက်အရ စီမံကိန်းဆောင်ရွက်ချက်များမှာ ထိခိုက်နိုင်မှု နည်းပါးပြီး အခြားလုပ်ဆောင်ရွက်ချက်များမှာ ထိခိုက်နိုင်မှု အလယ်အလတ် နှင့် မြင့်မားသည့် အခြေအနေတို့တွင် တည်ရှိနေပါသည်။ ထိုသက်ရောက်မှုများကိုလည်း သင့်တော်သော လျော့ချ နိုင်မည့်နည်းလမ်းများကိုလည်း ထည့်သွင်းဖော်ပြထားပါသည်။ လူမှုစီးပွားဖွံ့ဖြိုးတိုးတက်လာခြင်း သည်စီမံကိန်း၏ကောင်းကျိုးသက်ရောက်မှု ဖြစ်သည်။ အသေးစိတ်ကို အခန်း (၇) တွင်ဖော်ပြထား ပါသည်။

အများပြည်သူသဘောထားရယူခြင်းအခမ်းအနားကို ၂၀၁၉ ခုနှစ်၊ ဇွန်လ (၁၅) ရက်နေ့တွင် မယ်ကရိ ကျေးရွာ၊ ကျိုက်မရောမြို့နယ်၊ မွန်ပြည်နယ်တွင်ကျင်းပပြုလုပ်ခဲ့သည်။ စီမံကိန်းမန်နေဂျာ ဦးတင်ဦးမှ အဆိုပြုစီမံကိန်း၏အကြောင်း၊ ရင်းနှီးမြှုပ်နှံမှုပမာဏနှင့် ၄င်းတို့၏ အနာဂတ်အစီအစဉ် ကိုရှင်းလင်းတင်ပြခဲ့သည်။ ထို့နောက် အီးဂတ်ပတ်ဝန်းကျင်ဆိုင်ရာဝန်ဆောင်မှုလုပ်ငန်းမှ ဒါရိုက်တာ ဦးတင်အောင်မိုးမှ ကနဦးပတ်ဝန်းကျင်ဆန်းစစ်ခြင်း၏ ရည်ရွယ်ချက်၊ စီမံကိန်းဆိုင်ရာအချက် အလက်များစုဆောင်းပေးခြင်း၊ ပတ်ဝန်းကျင်ဆိုင်ရာ ထိခိုက်မှုများကို တွက်ချက်ခန့်မှန်းခြင်း နှင့် လျော့နည်းအောင်ပြုလုပ်ရမည့်နည်းလမ်းများကို အကြုံပြုတင်ပြခြင်း၊ လူမှုစီးပွားတာဝန်ယူမှု အစီအစဉ် (CSR Plan)၊ ပတ်ဝန်းကျင်ဆိုင်ရာ စောင့်ကြပ်ကြည့်ရှူ့မှု အစီအစဉ်များ ပါဝင်သည့် ပတ်ဝန်းကျင်ဆိုင်ရာ စီမံခန့်ခွဲမှုအစီအစဉ် (EMP) ပြင်ဆင်ချက်များကို ရှင်းလင်းတင်ပြခဲ့သည်။ အသေးစိတ် အကြံပြုချက်များ၊ အမေးအဖြေများကို အခန်း (၈) တွင်ဖော်ပြထားပါသည်။

ပတ်ဝန်းကျင်စီမံခန့်ခွဲမှုအစီအစဉ်တွင် ဖြစ်ပေါ်နိုင်သည့် ပတ်ဝန်းကျင်ထိခိုက်မှုများ၊ ထိခိုက်မှု အရင်းအမြစ်များ၊ ထိခိုက်မှုများကိုလျှော့ချပေးနိုင်မည့်ရှောင်လွှဲရန်နည်းလမ်းများ၊ ကျန်ရှိမည့် ထိခိုက်မှုများနှင့် ဆောက်လုပ်ရေးကာလ၊ လုပ်ငန်းလည်ပတ်ခြင်းကာလနှင့် ဖျက်သိမ်းခြင်းကာလ အစီအစဉ်တွင် လေ နှင့် ရေ အရည်အသွေး၊ ဆူညံသံပမာဏ၊ မီးဘေးအန္တရာယ်၊ လုပ်ငန်းခွင် ဘေးအန္တရာယ်၊ စွန့်ပစ်ပစ္စည်းများ စသည်တို့သည်ပတ်ဝန်းကျင် အပေါ်တွင်သက်ရောက်မှုရှိနိုင်ပြီး လူမှုစီးပွားအခြေအနေ ပေါ်တွင်ကောင်းကျိုး ဖြစ်စေမည်။ ထိုသက်ရောက်မှုများကိုလျော့ချရန် နည်းလမ်းများကိုလည်း EMP အပိုင်းတွင် အသေးစိတ် ဖော်ပြထားသည်။ စောင့်ကြပ်ကြည့်ရှူမှု အစီအစဉ်တွင် စီမံကိန်းဆောင်ရွက်နေစဉ် ကာလအတွင်း လေ၊ ရေ၊



မြေအရည်အသွေးနှင့် ဆူညံသံပမာဏတို့အတွက် စောင့်ကြပ်ကြည့်ရှူ့ရန် တာဝန်ရှိသောပုဂ္ဂိုလ်များ၊ တိုင်းတာရန်အကြိမ် အရေအတွက်များစသည်တို့ပါဝင်သည်။ ပတ်ဝန်းကျင်ဆိုင်ရာစီမံခန့်ခွဲမှုအစီအစဉ်ကို အကောင် အထည် ဖော်ဆောင်ရွက်ရန် ခန့်မှန်းကုန်ကျစရိတ်မှာ အမေရိကန်ဒေါ်လာ (၄၃၃၈၅ဂ) ခန့် လျာထားပါသည်။ လူမှုစီးပွားတာဝန်ယူမှုအစီအစဉ်တွင် ဝန်ထမ်းများနှင့် မိသားစုများ၏လူနေမှုဘဝ လုံခြုံစေရန်၊ အနီးအနားရှိ အဖွဲ့ အစည်းများနှင့် ပိုမိုကောင်းမွန်သောနေထိုင်မှုစနစ်နှင့် ပွင့်လင်းရင်းနီးသော ဆက်ဆံမှုရရှိရန်အတွက် လည်းရည်ရွယ်ထားပါသည်။ အနီးပတ်ဝန်းကျင်ရှိ ဒေသခံများအတွက် လူမှုစီးပွားဖွံ့ဖြိုးရေးရန်ပုံငွေကို ပေးဆောင်ရန်လည်းတာဝန်ရှိပါသည်။ မကျေလည်မှုများကိုဖြေရှင်း ပေးမည့်အစီအစဉ်တွင် စီမံကိန်းနှင့် ပတ်သက်၍ မကျေလည်မှုများ ပေါ်ပေါက်လာပါက ဖြေရှင်း နိုင်မည့်နည်းလမ်းများကို ဖော်ပြထားသည်။ အရေးပေါ်ကိစ္စရပ်များအတွက် ကာကွယ်မှုနှင့် တုံ့ပြန်မှု အစီအစဉ်တွင် အရေးပေါ်ကိစ္စရပ်များကို ကြိုတင် ကာကွယ်ရန်နှင့် ဖြစ်ပေါ်လာပါကတုံ့ပြန်ရန် နည်းလမ်းများပါဝင်သည်။ အချုပ်အားဖြင့် ပတ်ဝန်းကျင်ဆိုင်ရာ စီမံခန့်ခွဲမှုအစီအစဉ်တွင် စီမံကိန်းကြောင့် ဖြစ်ပေါ်လာနိုင်သော ပတ်ဝန်းကျင်အပေါ်ကောင်းကျိုး၊ ဆိုးကျိုးများ ကိုစနစ်တကျလေ့လာပြီး ဆိုးကျိုးများကို စောင့်ကြပ်ကြည့်ရှုရန်နှင့် လျှော့ချရန်နည်းလမ်းများကို ကာလအားလုံးအတွက် သတ်မှတ်ထားပါသည်။ အစီအစဉ်အသေးစိတ်များကို အခန်း (၉) တွင်ဖော်ပြထားပါသည်။

အကျဉ်းချူပ်အားဖြင့် ပြည်ထောင်စုသမ္မတမြန်မာနိုင်၏ လမ်းညွှန်မူများ၊ ပတ်ဝန်းကျင်ဆိုင်ရာဥပဒေ၊ နည်းဥပဒေစည်းမျဉ်းစည်းကမ်းများနှင့် ချမှတ်ထားသော မူဝါဒလမ်းညွှန်ချက်များအတိုင်း ပတ်ဝန်းကျင် ဆိုင်ရာစီမံခန့်ခွဲမူအလေ့အကျင့်များ၊ လုပ်ငန်းစဉ်များနှင့် လိုက်နာဆောင်ရွက်ကျင့် သုံးရန်တာဝန်များကို ဤကနဦးပတ်ဝန်းကျင်ဆန်းစစ်ခြင်းအစီရင်ခံစာတွင် ဖော်ပြတင်ပြထားပါသည်။ စီမံကိန်းနှင့်သက်ဆိုင်သူများ အား စီမံကိန်းဆိုင်ရာအကြောင်းရာများရှင်းလင်းတင်ပြခြင်း၊ အကြုံပြုချက်များနှင့် ဆွေနွေးတင်ပြလာသော သဘောထား အကြံဉာဏ်များကိုရယူပြီး အဆိုပါကနဦးပတ်ဝန်းကျင်ဆန်းစစ်ခြင်းအစီရင်ခံစာ၏ ပတ်ဝန်းကျင် ဆိုင်ရာစီမံခန့်ခွဲမူအစီစဉ်တွင် ထည့်သွင်းရေးသားခဲ့ပါသည်။





CHAPTER 1 INTRODUCTION

1.1 BACKGROUND OF THE STUDY

This Initial Environmental Examination (IEE) was developed based on site assessment of the proposed Clay soil production project. The proposed project is intended to perform clay soil production operation for June cement factory that existing near Malkaro Village, Kyaikmaraw Township, Mawlamyine, Mon State for 30 years period. The land area of the proposed project for clay soil production operation is approximately 100 acres.

June Cement Industry Ltd. has submitted a proposal for cement production plant with a kiln capacity of 5000 t/d with an annual production of approximately 2.1 to 2.3 million tons of Portland cement manufactured by dry processing method in Myanmar, to Myanmar Investment Commission (MIC) in August 2015. In September 2016, Environmental Impact Assessment (EIA) Report for the whole project has been prepared and submitted to Environmental Conservation Department (ECD). ECD gives some comments on EIA report to carry out the separate Initial Environmental Examinations (IEEs) for main project activities such as mining. In this context, with an advice of E Guard Environmental Services the project proponent decides to prepare the separate IEE report of clay soil production of raw materials for cement factory.

In compliance with laws, rules and regulations of MONREC, the Initial Environmental Examination (IEE) is conducted for the proposed clay soil production operation, in order to identify the immediate and potential impacts of the project activities on physical, biological, socioeconomic and cultural environment of the proposed project site. The specific objectives of this study include:

- Identify the major issues that may arise as a result of the proposed activities on biophysical, socioeconomic and cultural environment of the project area.
- Recommend practical and site-specific measures for environmental impact mitigation and environmental enhancement.
- Prepare and implement an environmental management plan for the project, and
- Make sure that the IEE is done sufficiently for the proposed project

As per the comments of (ECD), the proposed project requires an IEE to meet the environmental assessment requirements of Environmental Impacts Assessment Procedures (2015). Therefore, June Cement Industry Limited appoints E Guard Environmental Services for conducting IEE studies and preparing the report. E Guard Environmental Services has prepared this Initial Environmental Examination (IEE) according to the Environmental Impact Assessment (EIA) procedure (2015).

This IEE report is prepared (1) to initially assess the potential impacts of the proposed clay soil production project on environmental components and communities nearby, (2) to develop adequate and feasible mitigation measures and monitoring programs, and (3) to keep residual impacts of the project within acceptable limits in order to ensure successful implementation of the proposed project. The schematic processes of Environmental approval in the IEE procedures are shown in **Figure 1.1**.







1.2 SCOPE OF THE STUDY

The study on existing environmental resources in the project area focused on two main resources: the primary data and the secondary data. The primary data collection of current physical environment such as air, water and soil qualities inside the project area was carried out during the site visit period to obtain existing information of the project's physical environment. The secondary data on physical and socioeconomic conditions of the project area were collected as reference materials from relevant ministries and research institutes for the preparation and formulation of IEE report. The data collection process is done by direct observation, surveying and sampling. Moreover, the IEE report comprises baseline data on



existing conditions, together with the anticipated environmental impacts and proposed mitigation measures. The study is done by considering the potential impacts of the activities in all these phases of the project: site preparation, operation and decommissioning/closure phases.

1.3 MATERIALS AND METHODS

The method adopted for this project site consists of field work in which water and soil samples were collected, air quality and noise level were measured, field observations to determine the physical, environmental impact of mining and the laboratory work in which representative samples collected from the field were analyzed for their physical and chemical properties contents.

i) Field Work

The field work was carried out within the designated place of the study area. The representative surface water samples were collected near irrigation scheme and Ataran River which are near project site. These samples were carefully put in plastic bottles and labeled.

The representative soil sample was randomly collected from the surface using a shovel from the areas within the clay soil project site. The sample collected was described based on their color, texture and carefully put in plastic bags and labeled.

The representative air qualities (PM_{10} , $PM_{2.5}$, NO_2 , SO_2 and O_3) were measured from the surface using an EPAS, with sensors and casing from the operation site. Noise level measuring was also carried out within the project site. The field studies were carried out by members of E Guard Environmental Services. The team studied the field survey with the following professional experts and the survey period was from March 10, 2019 to March 12, 2019.

The IEE study survey team members are listed below:

- 1) U Tin Aung Moe (Director)
- 2) U Aung Myint Myat
- 3) U Thaw Tar Htun
- 4) U Kyaw Soe Moe
- 5) U Aung Moe Oo
- 6) Daw May Thu Win
- 7) Daw Thet Shwe Yee Aung
- 8) U Khin Zaw Min



Table 1. 1 Describes the devices used to collect baseline environmental data for the proposed project





iii) Field Observations

During the field work, observation of the whole project site was done so as to evaluate the physical impact of the clay soil production operation area. The current land use of the proposed project area is agricultural land so the project proponent will conduct the necessary clearance work in environmentally sound manner for the clay soil production.

iv) Laboratory Work

The water samples were analyzed in the ISO Tech Laboratory and SGS. The soil sample was analyzed at the United Analyst and Engineering Consultant Co., Ltd.

E Guard Environmental Services had prepared and submitted an Initial Environmental Examination report to explain the environmental impacts of the project and other existing and planned activities in the operation area, in combination with the project. The IEE report and application had been prepared in accordance with the requirements prescribed under the Ministry of Natural Resource and Environmental Conservation (MONREC).



CHAPTER 2 PROJECT DESCRIPTION

2.1 **BASIC PROJECT INFORMATION**

The purpose of the project is to extract clay soil as raw material for cement production during the operational phase, to provide employment opportunities for local residents. June Cement Industry Limited needs raw material such as clay soil, laterite, and limestone for cement production. According to the cement composition ratio, clay soil will be needed to extract daily 10% (500 ton per day) of total production amount of cement 5000 tons/day. However, only 6% (300 ton per day) will be extracted from the proposed clay mine site because clay content in laterite sample from laterite mine (June Cement Industry Limited) is 4% as a laboratory analysis result. As the proposed project site is located adjacent to the Ataran River, project proponent will extract clay soil 150 meters away from the boundary of Ataran River to ensure that there is no disturbance the waterway and pollution the water quality. Operation process will break during raining season because flooding may occur around the project area.

The facilities of the proposed project include one-storey office building and dormitory, workshop, machine garage, water storage tank, toilet and etc. According to the MIC permit, preparation will start within 2 years for clay soil production. During the operational phase, it is intended to extract clay soil for the period of 30 years. After the operation phase, the proponent will rehabilitate the project area during decommissioning phase and close out phases of the project. The project proponent had got using farmland by other means permit approximately (100 acres) from Department of Agricultural Land Management and Statistics that is described in Appendix 7.

Table 2. 1 Project Information			
Project Name	: Clay Soil Production Project		
Project Location	: Malkaro Village, Kyaikmaraw Township, Mawlamyine, Mon State		
Project Owner	: Daw Nu Nu Win		
Designation	: Managing Director		
Type of Business	: June Cement Industry Ltd.		
Principle Company's Address	: No. 80, Sayar San Street, Bahan Township, Yangon, Myanmar		
Contact Number	: +95 92005445, +95 19010660		



2.2 INVESTMENT PLAN

The total investment of June Cement Industry Limited for cement production will be around USD 47 million. Clay soil Production is the branch of it so that 20% of the total investment will be used for developing the clay soil production including machineries, equipment and equity.

2.3 LOCATION OF PROJECT, OVERVIEW MAP AND SITE LAYOUT PLAN

2.3.1 Location of Project and Overview Map

June Cement Industry Ltd. had made 30 years land lease contract according to the permission of Myanmar Investment Commission (MIC), for clay soil mine operation near Malkaro Village, Kyaikmaraw Township, Mawlamyine, Mon State and it is located only 0.17 miles away from the Cement Industry which is just across from the operation site. It is connected by road to Kyaikmaraw which links with Phar Auk and Mawlamyine. The land area of the proposed project for clay soil mining operation is approximately 100 acres. The elevation is from 12 ft above sea level. The location map of the proposed project site is shown in **Figure 2.1**.



Figure 2. 1 Location Map of the Proposed Project Site

Clay soil production operates within an area of approximately 100 acres. Total project area which will include related buildings and facilities, topsoil dumping yard and clay soil production area. In the project area, there are four buildings which will use as machine



garage, workshop, one-story office, staff dormitory and toilets. Moreover, a sedimentation pond must be constructed to utilize as wastewater collection pond for site runoff water and dewatering. In addition, one generator (3 kVA) will use as lighting mining operation on the project site. The layout plan of the proposed project site is shown in **Figure 2.2**.



Figure 2.2 Layout Plan of the Proposed Project Site

2.4 PRODUCTION PROCESS

(1) Site Clearing

Quarrying is an "Open Cut" process which requires clearing someway in front of working surfaces. Vegetation, topsoil and small amount of overburden will be progressively removed by bulldozers and excavators to expose the hard rock resource. Topsoil and overburden, where available, will be stockpiled separately for later use in rehabilitation. In some instances, topsoil and overburden will be applied directly to area undergoing rehabilitation or where overburden is required for the stabilization of landscape.

(2) Topsoil Removing

Before clay mining operation will take place, topsoil removing and stockpiling process will be carried out by using hydraulic excavators, bulldozers and dump trucks.

(3) Clay Soil Production



In the project area, clay soil will be extracted from the surface of the ground or beneath the surface. There are several techniques and process by which clay soil may be extracted from the earth. Open cast mining method will mainly use in the project site. Open cast mining is a type of strip mining in which the clay deposit extends deep in the ground, necessitating the removal of layer upon layer of topsoil. The removal of topsoil is 3ft depth and the clay soil is soft in nature, therefore drilling and blasting is not required, it will excavated directly from its in situ position by excavator, so no overburden dumps and no waste stockpile will be generated from the clay soil production.

(4) Clay soil Handling and Transportation

Clay soil will be excavated by hydraulic excavator and then loaded by dump trucks to store temporarily in clay soil stockpile. It will be transported by dump trucks to cement plant.

(5) Mine Dewatering

Mine dewatering is the process of controlling and managing surface water and groundwater to allow mining in relatively dry conditions, to improve geotechnical stability and to improve the efficiency of mining methods. According to the site survey observations in Malkaro Village, water level of water table well in unconfined aquifer is 12 feet from the ground level. Therefore, the project proponent must consider implementing a planned dewatering system to be more efficient working conditions such as trafficking, diggability and reducing downtime due to pit flooding.

(6) Sedimentation Pond

A sedimentation pond is a temporary settling pond designed to slowly release runoff, detaining it long enough to allow sediment to settle out. Moreover, it intercepts stormwater before it reaches the waterway, and slows it down to allow the coarse sediment to fall to the bottom. In the preparation and operation phases, ground water can be discharged due to the excavation activities. Therefore, dewatering process must be conducted. Water from the dewatering process must be discharged to the surrounding environment after passing through the sedimentation pond.





Figure 2.3 Production Process Flow Chart of proposed project

2.5 HUMAN RESOURCE REQUIREMENT

A total 12 workers from local are employed to work for the clay soil mining operation. During operation, the management of the process will be operated on one shift during day time starting from 8:00 AM to 5:00 PM including lunch time. The working week is start from Monday morning till Saturday noon. Adequate housings are supplied for accommodation services of all workers at staff housings of June cement plant. The requirement of workers during operation in the project is shown in **Table 2.2**.

No.	Designation	Number of Employees
1.	Supervisor	1
2.	Office Staff	1
3.	Operators	5
4.	Drivers	5
Total		12

Table 2. 2 Human Resources Requirement

2.6 REQUIREMENT OF MACHINERY AND EQUIPMENT

During the operation phase, required machines are to be purchased locally. The proposed project site has also utilized hydraulic excavator, bulldozer, wheel loader, generator and etc. for clay soil production operation. Detailed machines and equipment are shown in **Table 2.3**.



		0
Sr No.	Particular	Machinery (Quantity)
1.	Hydraulic excavator	1
2.	Generator	1
3.	Bulldozer	1
4.	Wheel loader	1
5.	Dump truck	4
	Total	8

 Table 2. 3 Machine and Equipment List of the Project Site



2.7 AMOUNT OF PRODUCTION

June Cement Industry Limited will produce 5000 cement tons per day. Clay soil will be used in only production of cement (June Cement Industry Limited) so clay production amount is based on the cement production amount. According to the raw mix calculation, 10% clay soil will be needed to produce cement so that the total amount of clay soil extraction for production of 5000 tons of cement will be around 500 tons of clay soil will be needed to extract per day.

2.8 WATER REQUIREMENT AND CONSUMPTION

There is no water usage for extraction of clay soil. Requirement of domestic usage will be supplied by tube well. In addition, for domestic water, the water from the tube well will be



pumped to an elevated water tank in the project site. Staffs domestic water will be used about 70 gals per person per day so the storage water tank will be constructed at project site and the water storage tank volume is 1000 gals. Purified drinking water will be supplied all time for every staffs.

2.9 SOURCE OF POWER SUPPLY AND DIESEL CONSUMPTION

The proposed development would result in increased fuel consumption. The main source of electricity supply will be obtained from one generator with a capacity of 3 KVA will be used as lighting. Approximately 100 gallons of diesel are required daily for generators, trippers and heavy machines, about 3000 gallons diesel per month purchases from the local market (Mawlamyine) and transport to the project area by car. The daily fuel requirement for the generator and machines is stored in the oil barrel in the project site.

2.10 PRODUCTION PROCESS AMOUNT OF WASTES/SOLID, LIQUID AND GAS

2.10.1 Solid Waste

The clay soil will be excavated directly from its in situ position by excavator, so no overburden dumps and no waste stockpile will be generated from the clay soil production. General domestic solid wastes are also generated from the staffs. Estimated solid waste generation rate will be 0.6 kg per person per day. Since there are total 12 staffs in the project site, total solid waste amount produced per day is 7.2 kg and 216 kg of waste will be generated per month. These domestic solid wastes will be collected at designated waste dump within the project site and then destroyed by fire.

2.10.2 Liquid Waste

Wastewater may be generated from dewatering process during the clay soil production process. Sedimentation pond will be provided in the project site to retain the wastewater and settle down the suspended solids containing in the discharged wastewater. This water will be used for plantation and spraying on haul road. There is no beneficiation mineral within the project area hence, no wastewater generation. However, domestic liquid waste will be generated by staffs. Non-hazardous liquid waste is staff personal discharge amount is 60 gals per person and there are total 12 staffs, total amount of water discharged from the project is 720 gals. Approximately 70% of this water is domestic waste water, 504 gals are discharged into septic tank. Remaining 30% of produced water (216 gals) is discharged outside the project site. They flow into the near project area. Hazardous liquid waste will generate by machine workshop and diesel oil storage tank.

2.10.3 Gas Emission

Air emission impact is Carbon-dioxide emission from the electric generator, heavy machine and tripper. In the project area, one generator will be used for electricity source for lighting staffs. Those generators diesel consumption is average 100 gallons per day. Carbon


dioxide amount emission from heavy machine and tripper can't be determined. Thus, the total amount of CO_2 emissions from the generator can be calculated as shown in below **Table 2.4**

Description	Metric Tons of CO ₂ emission factor	Resource Consumption per day	Kilo Tons of CO ₂ e/ per day	Kilo Tons of CO ₂ per Month	Kilo Tons of CO2e per year
Diesel	0.010	100 gallons	0.001	0.03	0.36

Table 2. 4 Quantity of CO₂ Emissions from the Generator

Source: World Resources Institute GHG Calculation for Stationary and Mobile Sources (2006)

The average amount of CO_2 emission from the generator is 0.36 kilotons CO_2 per year. According to EBRD Greenhouse Assessment Methodology, minimum CO_2 emission from the operation of facilities is <20 ktons CO_2 e per year. Therefore, the amount of GHG emissions is low when considered on the EBRD standard of CO_2 emission and there will be only a minor impact in the surrounding area.

In order to find out the air pollution due to GHG emissions, EBRD has developed a standard that will assess CO_2 emissions due to operation of project sectors. (See CO_2 Emission standards in **Table 2.5**.

Category	Range
Negligible	No GHG assessment necessary
Low	< 20kt/y CO ₂ - equivalence (CO ₂ –e)
Medium – Low	20 - 100 kt CO ₂ - equivalence (CO ₂ - e)
Medium- high	100 kt- 1 Mt CO ₂ - equivalence (CO ₂ –e)
High	$> 1 \text{ Mt CO}_2 - e$

Table 2. 5 EBRD Standard of CO₂ Emission



2.11 PROJECT ALTERNATIVES

This section considers the selected alternative to 'no project alternative'. There were no other alternative site locations considered for the project because clay soil can be extracted and supported sufficiently for cement production of June Cement Industry Limited which is located adjacent to the project site.

No Action Alternative

The following positive impacts are anticipated by choosing this alternative:

- There will have no impact (even minimal) from any construction and extraction activities
- No light pollution, emissions, noise and any other (even minimal) impacts on the surrounding environment will be expected so natural resources and biodiversity will be impacted by the activities of the project
- > No additional human presence (Staffs) will be expected
- > There will be less traffic movement around the project site

In the meantime, the following negative impacts are anticipated:

- Lack of job opportunity
- Cement production cost will be higher due to the lack of clay soil demand for cement production plant which is located near the proposed clay soil extraction site.
- > Traffic load will be raised definitely in surrounding environment due to the raw material transportation activities.



CHAPTER 3

IDENTIFICATION OF THE PROJECT PROPONENT

3.1 PROJECT PROPONENT INFORMATION

The project proponent of the clay soil production project is June Cement Industry Limited, which is a 100 % local investment. June Cement Industry Limited's company registration certificate had attached in **Appendix 6**. The proposed duration of the investment is 30 years. Detailed information of the project proponent is shown in **Table 3.1**.

No.	Name	NRC Number	Designation	Address		
1.	Daw Nu Nu Win	10/Ma La Ma (C) 143240	Managing Director	No.80, Sayar San Street, Bahan Township, Yangon.		
2.	U Aung Moe	12/Ah La Na (C) 033634	Director	No.11/13, Thayaphe Street, Ahlone Township, Yangon.		
3.	U Myint Khaing	12/Ka Ta Ta (AC) 000291	Director	No.80, Sayar San Street, Bahan Township, Yangon.		
4.	U Myint Soe	12/BaHaNa (C) 048684	Director	No.27, Shwe Taung Gone Yeik Thar, Inlyar Myaing Street, Bahan Township, Yangon.		

Table 3. 1 Project Proponent Information



CHAPTER 4

IDENTIFICATION OF THE IEE EXPERTS

4.1 STUDY TEAM FOR INITIAL ENVIRONMENTAL EXAMINATION

The Initial Environmental Examination (IEE) with the Environmental Management Plan (EMP) for the proposed project is prepared by E Guard Environmental Services. E Guard Environmental Services started this IEE report preparation on July 2019 in line with Myanmar Environmental Conservation Law and Regulation for clay soil production project of June Cement Industry Limited. Consultant Registration Certificates had attached in **Appendix 10.** Initial Environmental Examination members of the E Guard Environmental Services for the proposed project are as follows:

No.	Name	Position	Transitional Consultant Registration Numbers	Role
	E Guard Environmental Services	EIA Organization	0028	
1	U Tin Aung Moe	Project Leader	10103	Overall responsibility for IEE Project Report Preparation
2	U Aung Myint Myat	Team Leader	10099	Project Management and Review
3	U Thaw Tar Htun	Team Member	-	Project Management
4	Daw Thein Mwe Khin	Team Member	10104	Socio-Economist
5	U Kyaw Soe Moe	Team Member	-	Report Writing, SocialSurvey,PublicConsultation,EnvironmentalAssessment,ImpactIdentificationandAnalysis
6	U Aung Moe Oo	Team Member	-	Environmental Quality Measuring and Analysis
7	Daw May Thu Win	Team Member	-	Laws and Legislation
8	Daw Thet Shwe Yee Aung	Team Member	-	Social Survey data entry, Assist for Database requirements
9	U Khin Zaw Min	Team Member	-	Field Surveyor for Environmental Quality

Table 4. 1 IEE Study Team and their Responsibility



				Data
--	--	--	--	------

U Tin Aung Moe (Director)

U Tin Aung Moe is a Consultant who holds Transitional Consultant Certificate No 0103; described expertise is Facilitation of meeting, Land use, Risk Assessment and Hazard Management, RS and GIS. He is one of the founding members of E Guard. He has been working for Environmental Assessment and Environmental Technologies development and capacity building for the Developing countries in Asia and Pacific Region. He is responsible for the policy and institutional linkages and harmonization of E Guard.

U Aung Myint Myat (Associate consultant)

U Aung Myint Myat is an Associate Consultant, who holds Transitional Consultant Certificate No. 0099, described expertise is Forestry. He has Bachelor Degree in Forestry from the University of Forestry in 2014. He has four years experiences on environmental site surveys and also socio-economic surveys. Another experience is to cooperate with clients, government authorities and local people to conduct stakeholder engagement and public consultation meeting. He also participates in the activities of social survey, biodiversity survey, and reviewing the reports.

U Thaw Tar Htun (Associate Consultant)

U Thaw Tar Htun is an Associate Consultant working on EIA project reporting in E Guard Environmental Services Co., Ltd. since 2018. He received Bachelor of Civil Engineering from Taunggyi Technological University in 2011 and Master of Engineering in (International Graduate Program in Environmental and Water Resources Engineering) from Mahidol University, Thailand in 2016. He had experiences in environmental fields for 4 years including his master degree research, "Mathematical Modelling Wastewater Collection System in Cha-Am Municipality using PCSWMM". His master thesis paper was presented in 3rd International Conference on Civil, Biological and Environmental Engineering Conference, Phukhet, Bangkok. He had worked as a Sub Assistant Engineer at Engineering Department (Water and Sanitation) at Naypyitaw Development Committee, Naypyitaw, Naypyitaw Union Terrority from August 2012 to October 2017.

Daw Thein Mwe Khin (Associate Consultant)

Daw Thein Mwe Khin is an Associate Consultant, who received her Master Degree in Regional and Rural Development Planning from Asian Institute of Technology and Bachelor Degree in Forestry from the University of Forestry. She has more than 4-year experience in communication with clients, regulators such as analytical laboratories. She is also familiar with conducting socio-economic survey for development projects and RAP as a team leader. Her contributions on preparation of this project are socio- economic questionnaire preparation and data analysis as a socio-economist.



U Kyaw Soe Moe (Project Associate)

U Kyaw Soe Moe is a Project Associate who received Bachelor of Civil Engineering from Taunggyi Technological University in 2016. He has nearly 2 years experiences in conduction stakeholder engagement, public consultation, social survey and site visit. His contributions on preparation of this project are report writing, social survey, public consultation, potential impact identification and analysis.

U Aung Moe Oo (Project Associate)

U Aung Moe Oo is a Project Assistant, who received his Bachelor Degree in Chemical Engineering from Technological University (Thanlyin) in 2016 and working in E Guard Environmental Services Co., Ltd. He has experience on environmental site survey and socio-economic surveys. He also specializes in environmental quality such as water quality, air quality and noise etc. He is also responsible for data analysis and interpretation of environmental baseline data.

Daw May Thu Win (Project Assistant)

Daw May Thu Win is working as project assistant in E-Guard Environmental Services Co., Ltd. She obtained her Bachelor Degree in Law from East Yangon University (Tarwa) in 2018. She is currently assisting in preparing Laws, Rules, Regulations, Policies, Directions and Notifications use for environmental reports, public consultations and information gathering process.

Daw Thet Shwe Yee Aung (Project Assistant)

Daw Thet Shwe Yee Aung is working as Project Assistant in E Guard Environmental Services. She completed her Bachelor Degree in Geology from University of Yangon in 2018. She went to Chauk, Popa, Kyauk Se Township and Southern Shan State to study the geological structure of those areas and also participated in writing geological reports. She has more than one experience in conduction stakeholder engagement and public consultation, site visit. She is currently assisting in preparing environmental reports, public consultation and information gathering processes.

U Khin Zaw Min (Surveyor)

U Khin Zaw Min specializes in instrumentation and field data collection of environmental condition of the site and measuring of environmental baseline data.



CHAPTER 5

POLICY, LEGAL AND INSTITUTIONAL FRAMEWORK

5.1 INSTITUTIONAL FRAMEWORK FOR ENVIRONMENTAL CONSERVATION

The Ministry of Environmental Conservation and Forestry (MOECAF) was reorganized as the Ministry of Natural Resources and Environmental Conservation (MONREC) on 30th March 2016 in order to undertake both environmental and natural resources conservation and management more effectively. Under Section 3 of the Environmental Impact Assessment Procedure (2015), pursuant to section 21 of the law and Articles 52, 53 and 55 of the Environmental Conservation Rules, all projects and project expansions undertaken by any organization, which may cause an impact on environmental quality, are required to obtain Prior Permission. This is to be in accordance with section 21 of the Environmental Conservation Law, and Article 62 of the Environmental Conservation Rules, having the potential to cause Adverse Impacts, are required to undertake IEE or EIA or to develop an EMP, and to obtain an Environmental Compliance Certificate (ECC) in accordance with this Procedure.

5.2 NATIONAL LAWS AND REGULATIONS

National laws and regulations for environmental protection applicable to the proposed project are compiled and presented in **Table 5.1**.

Laws and Regulations	Description		
Constitution of the	Constitution of the Republic of the Union of Myanmar (2008)		
The Constitution of	the Union of Myanmar is the supreme law of the country and has provisions regarding the		
protection of the en	vironment in Myanmar. Articles in the Constitution relevant to environmental protection		
are Articles 37, 42 at	nd 390. They are quoted below:		
	(a) The Union is the ultimate owner of all lands and all natural resources above and		
Article 37	below the ground, above and beneath the water and in the atmosphere in the Union;		
Article 37	(b) The Union shall enact necessary law to supervise extraction and utilization of State		
	owned natural resources by economic forces;		
Article 42	The Union shall protect and conserve the natural environment.		
	Every citizen has the duty to assist the Union in carrying out the following matters:		
	(a) Preservation and safeguarding of cultural heritage;		
Article 390	(b) Environmental conservation;		
Article 370	(c) Striving for development of human resources;		
	(d) Protection and preservation of public property.		
	These three Articles in the Constitution provide a basis for legalizing and		
institutionalizing environmental health impact assessment and social impact			
Myanmar National Environmental Policy (2019)			
Mission	To achieve a clean environment, with healthy and functioning ecosystems, that ensures		
WIISSION	inclusive development and wellbeing for all people in Myanmar.		
Vision	To establish national environmental policy principles for guiding environmental		

Table 5. 1 Relevant National Laws and Regulations of Myanmar



Laws and Regulations	Description	
	protection and sustainable development and for mainstreaming environmental considerations into all policies, laws, regulations, plans, strategies, programs and projects in Myanmar.	
National Land Use	Policy (2016)	
Objectives	 a. To promote sustainable land use management and protection of cultural heritage areas, environment, and natural resources in the interest of all people in the country; b. To strengthen land tenure security for the livelihoods improvement and food security of all people in both urban and rural areas of the country; c. To recognize and protect customary land tenure rights and procedures of the ethnic nationalities; d. To develop transparent, fair, affordable and independent dispute resolution mechanisms in accordance with the rule of law; e. To promote people centered development in land resources and accountable land use administration in order to support the equitable economic development of the country; f. To develop a National Land Law in order to implement the above objectives of the National Land Use Policy. 	
The Environmental Conservation Law (2012)		
The Pyidaungsu Hluttaw enacted this law by Law No. 9 of 2012 on the date of 30 th March, 2012. March, 2012. The legal mechanism for ESHIA has been put in this law. This law was enacted with the objectives of:		

- a. To enable to implement the Myanmar National Environmental Policy;
- b. To enable to lay down the basic principles and give guidance for systematic integration of the matters of environmental conservation in the sustainable development process;
- c. To enable to emerge a healthy and clean environment and to enable to conserve natural and cultural heritage for the benefit of present and future generations;
- d. To reclaim ecosystems as may be possible which are starting to degenerate and disappear;
- e. To enable to manage and implement for a decrease and loss of natural resources and for enabling the sustainable use beneficially;
- f. To enable to implement for promoting public awareness and cooperation in educational for dissemination of environmental perception;
- g. To enable to promote international, regional and bilateral cooperation in the matters of environmental conservation;
- h. To enable to cooperate with Government Departments, Government Organizations, International Organizations, non-government organizations and individuals in matters of environmental conservation.

The following articles are particularly relevant to EIA requirements and this project:

Article 7 of chapter 4 mentions the need for SIA and EIA for any project operated by the government or organizations or individuals.

The duties and powers relating to the environmental conservation of the Ministry are as follows:

- a. Implementing the environmental conservation policies
- b. Laying down, carrying out and monitoring programs for conservation and enhancement of the environment and for conservation, control and abatement not to cause environmental pollution
- c. Specifying categories and classes of hazardous wastes generated from the production and use of chemicals or other hazardous substances in carrying out industry, agriculture, mineral production, sanitation and other activities;
- d. Prescribing categories of hazardous substances that may affect significantly at present or in the long run on the environment;
- e. Promoting and carrying out the establishment of necessary factories and stations for the treatment of solid wastes, effluents and emissions which contain toxic and hazardous substances;
- f. Prescribing the terms and conditions relating to effluent treatment in industrial estates and other necessary places and buildings and emissions of machines, vehicles and mechanisms;



Laws and	Description
Regulations	Description

- g. Laying down and carry out a system of Environmental Impact Assessment (EIA) and Social Impact Assessment (SIA) as to whether or not a project or activity to be undertaken by any Government department, organization or person may cause a significant impact on the environment;
- h. Managing to cause the polluter to compensate for the environmental impact, cause to contribute funds by the organizations which obtain benefit from the natural environment service system, cause to contribute a part of the benefit from the businesses which explore, trade and use the natural resources in environmental conservation works."

Also in this law, Article 14 and Article 15 are related to waste disposal in accordance with environmental standards:

- 14. A person causing a point source of pollution shall treat, emit, drainage and deposit the substances which cause pollution in the environment in accord with stipulated environmental quality standards.
- 15. The owner or occupier of any business, material or place which causes a point source of pollution shall install or use an on-site facility or controlling equipment in order to monitor, control, manage, reduce or eliminate environmental pollution. If it is impracticable, it shall be arranged to dispose the wastes in accord with environmentally sound methods.
- 16. A person or organization operating business in the industrial estate or business in the SEZ or category of business stipulated by the Ministry:
 - a. is responsible to carry out by contributing the stipulated cash or kind in the relevant combined scheme for the environmental conservation including the management and treatment of waste;
 - b. is responsible to carry out by contributing the stipulated cash or kind in the relevant combined scheme for the environmental conservation including the management and treatment of waste;
 - c. shall contribute the stipulated users' charge s or management fees for the environmental conservation according to the relevant industrial estate, SEZ and business organization
 - d. shall comply with the directives issued for environmental conservation according to the relevant industrial estate, SEZ or business.

Employment and Skill Development Law (2013)

Purpose: To ensure the job security and to develop the employee's skill with the fund of project owner:

- a. The project proponent has to appoint employees with the contract in line with the provision of section 5 of said law.
- b. The project proponent has to carry out the training programs with the policy of Skill Development Body to develop the employment skill of employees who is appointed or will be appointed, under section 14 of said law.
- c. The project proponent has to monthly pay to the fund, which is fund for development of skill of employees, not less below 0.5 percentage of the total payment to the level of worker supervisor and the workers below such level, under sub-section (a) of section 30 of said law.
- d. The project proponent has to promise not to deduct from the payment of employees for above mentioned fund, under sub-section (b) of section 30 of said law.

Minimum Wages Law (2013)

Purpose: To ensure the project owner pay the wages not less than prescribed wages and notify obviously this wages in work place, moreover to be inspected.

- a. The project proponent has to pay the wages in line with section 12 of said law.
- b. The project proponent has to notify the prescribed wages obviously in work place under sub-section



Laws and Regulations	Description
(a) of section	13 of said law.
c. The project these to the stipulations u	proponent has to correctly record the lists, schedules, documents and wages and report relevant department and give if these are asked while inspecting, in accord with the inder sub-section $(b)(c)(d)$ of section13 of said law.
d. The project j section 13 ar	proponent has to allow to be inspected by the inspector, under sub-section (d) and (e) of a section 18 of said law.
e. The project j work, under	proponent has to allow holiday for medical treatment if the employee' health is not fit to sub-section (f) of section 13 of said law.
f. The project one of family	proponent has to allow holidays without deducting from the wages if one of parents or y dies, under sub-section (g) of section 13 of said law.
The Environmental	Conservation Rules (2014)
The Ministry of Ensection (a) of section of 5^{th} June, 2014.	vironmental Conservation and Forestry, in the exercise of power conferred under sub- 42 of the Environmental Conservation Law, issues this rule by No. 50 of 2014 on the date
Rule 51	The Ministry shall assign duty to the Department for enabling to adopt and carry out the environmental impact assessment system.
Rule 52	The Ministry shall determine the categories of plan, business or activity which shall carry out environmental impact assessment
Rule 53	The Ministry shall to scrutinize whether or not it is necessary to conduct environmental impact assessment, determine the proposed plans, businesses or activities which do not include in stipulation under rule 52
Rule 56	The person who carries out any project, business or activity shall arrange and carry out for conducting the environmental impact assessment for any project, business or activity of a qualified third person or organization accepted by the Ministry.
Rule 58	The Ministry shall form the Environmental Impact Assessment Report Review Body with the experts from the relevant Government departments, Government organizations.
Rule 61	The Ministry may approve and reply to the EIA report or IEE or EMP with the guidance of the Committee
Rule 69	 i. Any person shall not emit, cause to emit, dispose, cause to dispose, pile and cause to pile, by any means, the pollutants and the hazardous waste or hazardous material stipulated by notification under the Law and any of these rules at any place which may affect the public directly or indirectly. ii. Any person shall not carry out to damage the ecosystem and the natural environment which is changing due to such system, except for carrying out with the permission of the Ministry for the interest of the people.
The Forest Law (19	92)
The State Law and C	Order Restoration Council had enacted the following Law in 3 November, 1992 as Forest
Law.	
Chapter II: Basic Principles	 3. This Law shall be implemented in accordance with the following basic principles: a) to implement the forestry policy of the Government; b) to implement the environmental conservation policy of the Government; c) to promote the sector of public co-operation in implementing the forestry policy and the environmental conservation policy of the Government.
	9. The functions and responsibilities of the Forest Department are as follows:-
ChapterIV:ManagementofForest Land	 a) implementation of the forestry policy of the Government; b) implementation of the plans relating to conservation of water, bio-diversity and environment, sustained yield of forest produce and protection of forest covered land:



Laws and Regulations	Description
	 c) management of forest land in accordance with the provision of this Law; d) submitting proposals to the Minister for the determination, alteration or cancellation of reserved forest, protected public forest and species of reserved trees; Whoever, within a forest land and forest covered land at the disposal of the Government: a) is desirous of carrying out any development work or economic scheme shall obtain the prior approval of the Forestry Ministry.
Chapter XII: Offences and Penalties	 40. Whoever commits any of the following acts shall, on conviction be punished with fine which may extend to Kyat 5,000 or with imprisonment for a term which may extend to 6months or with both: a) trespassing and encroaching in a reserved forest; b) pasturing domestic animals or permitting domestic animals to trespass in a reserved forest; c) breaking up any land, clearing, digging or causing damage to the original condition of the land without a permit in a reserved forest; d) causing damage to a water-course, poisoning in the water, using chemicals or explosives in the water in a reserved forest; e) catching animals, hunting or fishing in a reserved forest; f) kindling, keeping, carrying any fire or leaving any fire burning which may set fire to the forests in a reserved forest; h) violating any provision of the rule, procedure, order, directive or notification issued under this Law.
The Protection of V	Vildlife and Natural Areas Law (1994)
The State Law and C 8 th June, 1994.	Order Restoration Council had enacted the Protection of wildlife and Natural Areas Law on
ObjectivesThe objectives of this Law are as follows:- a) to implement the Government policy for wildlife protection; b) to implement the Government policy for natural areas conservation; c) to carry out in accordance with the International Conventions acceded by State in respect of the protection and conservation of wildlife, ecosystems migratory birds; d) to protect endangered species of wildlife and their natural habitats.	
Protected Wildlife	 15. The Director General shall, with the approval of the Minister: a) determine and declare endangered species of wild animal which are to be protected according to the following categories: i. completely protected species of wild animals; ii. normally protected species of wild animals; iii. seasonally protected species of wild animals; b) determine and declare the endangered species of wild plants and their nature habitats thereof; c) lay down and carry out measures for the preservation of protected wildlife species;
Taking	31. A Forest Officer may pass an administrative order causing a fine that may extend to
Administrative	Kyat 10,000 to be paid, on a person who kills, hunts, wounds or raises a seasonally
Action	protected wild animal without permission during the closed season.
The Forest Law (20	

Purpose: To ensure in carrying out the project with the permission of Ministry of Natural Resources and Environmental Conservation if the project land is forest land or forest covered land. This law focuses as follow:



Laws and Regulations	Description		
a. The project proj Conservation be	ponent has to obtain the permission of Ministry of Natural Resources and Environmental efore starting the work if the project land is forest land or forest covered under sub-		
section (a) of se	section (a) of section 12.		
Protection of Biodi	versity and Protected Area Law (2018)		
Purpose: To ensure	abiding by the prohibitions and stipulations to protect biodiversity and protected area.		
a. The project p permission un	proponent has to avoid entering the prohibited area located in protected area without ider sub-section (a) of section35.		
b. The project p under sub-sec	roponent has to avoid digging on the land or carrying out any activity in protected area tion (c) of section35.		
c. The project	roponent has to avoid extracting, collecting or destroying in any manner, any kind of wild plant in protected area under sub-section (d) of section35		
d. The project provide the description of the descr	roponent has to avoid polluting soil, water and air, damaging a water-course or poisoning fication, using chemical or explosive materials in protected area under sub-section (a) of		
e. The project p protected area	proponent has to avoid possessing or disposing of toxic objectives or mineral wastes in a under sub-section (b) of section39.		
Public Health Law	(1972)		
Purpose: to ensure the	he public health include not only employees but also resident people and cooperation with		
the authorized perso	on or organization of health department. It is concerned with the protection of peoples'		
health by controlling	g the quality and cleanliness of food, drugs, environmental sanitation, epidemic diseases		
and regulation of pr	ivate clinics. The project owner will cooperate with the authorized person or organization		
in line with the section	on 3 and 5 of said law.		
Section 3: The proje	ct owner will abide by any instruction or stipulation for public health.		
Section 5: The proje	ct owner will accept any inspection, anytime, anywhere if it is needed.		
Prevention and con	the healthy work environment and provention the communicable discoses by the		
cooperation with the	relevant health department		
The project owner w of said law.	vill cooperate with the health officer in line with the clause(9) of subsection(a) of section 3		
The project owner w	ill abide by any instruction or stipulation for public health. Section 4		
The project owner	will inform promptly to the nearest health department or hospital if the following are		
occurred; (section 9)			
(a) mass death of	birds or chicken		
(b) mass death of	mouse		
(c) suspense of o	ccurring of communicable disease or occurring of communicable disease		
(d) occurring of c	communicable disease which must be informed		
The project owner w	ill accept any inspection, anytime, anywhere if it is needed.(section 11)		
Mining Law (1994)			
Chapter II:	3. The objectives of this Law are as follows:		
Objectives	a) to implement the wineral Resources Policy of the Government;		
	due to mining operation		
Chapter III.	4 A person or organization desirous of carrying out any of the following operations		
Application and	shall apply to the Ministry in accordance with the stipulations for obtaining permit		
Granting of Permit	8. The Ministry may grant permit for the following operations:		
Standing of Formit	a) large scale production of industrial mineral or stone with local investment		
Chapter IV:	12.The holder of permit shall:		



Laws and Regulations	Description
Duties of the	a) abide by the provisions of this Law, rules, orders and directives made there
Holder of Permit	under;
	b) abide by the conditions contained in the permit;
	c) pay rent for the land related to the permit calculated in accordance with the
	rates prescribed by the rules made under this Law;
	d) pay rent for the land for each permit separately;
	13. The holder of permit shall comply with the rules prescribed under this Law in respect
	of the following matters:-
	c) making provisions for safety and the prevention of accidents in a mine and their implementation;
	e) making provisions for the environmental conservation works that may have
	detrimental effects due to mining operation;
Chapter V.	15. If, in the interest of the State, it is necessary to acquire the land where mineral
Dight of	production could be undertaken on commercial scale, the Ministry shall co-ordinate
Right of with the relevant.	
ord Water for	Ministry for the acquisition of such land in accordance with the existing law.
Mineral	16. If the holder of mineral production permit requires the use of public water for
Production	mineral production he shall first and foremost inform the Department of such
Troduction	requirement in accordance with the prescribed manner.
Chapter VI:	d) for industrial mineral or stone at the rate of 1% to 3%
Royalty	
Chapter VII:	21. The Ministry:-
Designation of	(a) may designate an area where mineral can be produced on commercial scale as
Mineral Reserve	Mineral Reserve Area by notification with the approval of the Government;
Area and	
Gemstone Tract	
	28. If the holder of permit or a person managing on his behalf or any of the worker fails
Chapter IX:	to comply with any of the orders or directives made under this Law, or contravenes
Taking of Action	any of the terms of the permit, the person issuing the permit may pass any of the
by Administrative	following administrative orders:—
Means	a) suspending all or portion of the operations carried out under the permit;
	b) allowing continuation of the operation, after causing the payment of fine;
	c) cancelling the permit;
Social Security Law	v (2012)

Purpose: The project proponent has to create the social security for the employees because the project is the business under the Myanmar Citizen Investment Law. To ensure the social security for employees of the project, the project owner has to register to the social security offices and to pay the prescribed fund.

- a. The project proponent has to register to the respected social security office, under sub-section (a) of section 11 of said law
- b. The project proponent has to pay the social security fund for at least four types of social security included in sub-section (a) of section 15, under section 15 of said law.
- c. The project proponent has to pay the fund which has to be paid myself and together with the fund which has to be paid from their salary by the employees .Moreover the project owner will pay the cost for paying the above mentioned fund only myself under sub-section (b) of section 18 of said law.
- d. The project proponent has to pay the fund for accidence, under sub-section(b) of section 48 of said law.
 (but this fund is not related to workmen compensation so if it is needed compensation must be separately paid by the Workmen compensation Act)
- **e.** The project proponent has to make correctly and submit the list and record provided in section 75 to respected social security office, under section 75 of said law.



Laws and Begulations	Description			
Kegulations Myonmor Fire Ser	vices Law (2015)			
The objectives of M	vanmar Fire Force Law are:			
The objectives of M a) To take pr cultural her b) To organize c) To prevent or any kind d) To educate e) To particip The relevant Gover obtain the approval a) Constructin b) Operating I c) Constructin d) Operating I e) Producing Doing transport bus	yanmar Fire Force Law are: ecautionary and preventive measure and loss of state own property, private property, itage and the lives and property of public due to fire and other natural disasters e fire brigade systemically and to train the fire brigade from fire and to conduct release work when fire disaster, natural disaster, epidemic disease of certain danger occurs , organize an inside extensively so as to achieve public corporation ate if in need for national security, peace for the citizens and law and order ment Department or organization shall, for the purpose of precaution and prevention, of the Fire force Department before granting permission for the following cases: ng three-storied and above buildings market and condominium buildings, notel, guest house enterprise ng factory, workshop, storage facilities and warehouse business expose to fire hazard by using in inflammable materials or explosive materials and selling fire-extinguishing apparatuses iness, public utility vehicles train, airplane, helicopter, vessel, ship, etc.			
The relevant government department or organization shall obtain the opinion of the Fire Services Department for the purpose of fire precaution and prevention, when laying down plans for construction for town, village and downtown or village development plans.				
Underground Wat	er Act (1930)			
The underground was protect underground purpose of obtaining the water officer. To jurisdiction over the of the tube as if it w	ater act enacted on the date of 21 st June in 1930 whereas it is expedient to conserve and a sources of water supply in the Union of Burma. This act prohibits sinking of a tube for the g underground water except under and in accordance with the terms of a license granted by pwnship Officer or sub-divisional officer had power to close a license tube after exercising local area concerned and the expense of such closure shall be recoverable from the owner ere an arrear of land-revenue.			
Farm Land Law (2	012)			
To ensure the right t	o use the farm land and sufficient compensation for acquisition of the farmland.			
a. The project of Central Adm farm land, un	e tollowing matters; owner has to abide by the decision of relevant Ministry with the coordination with the inistrative Body of the Farmland for paying the compensation if it is needed acquisition der section 26 of said law.			
b. The project p the land use c	roponent has to obtain the permission of the Central Administrative Body of Farmland for hange from paddy field land to other land use under sub-section (a) of section 30.			
 c. The project recommendat farm land oth 	proponent has to obtain the permission of the Yangon Region Government with the ion of Yangon Region Administrative Body of Farmland for the land use change from er than paddy field land to other land use under sub-section (b) of section 30.			
Vacant, Fallow and	l Virgin Land Management Law (2012)			
Purpose: To ensure	the project land is clearly get as the project land.			

- a. The project proponent will ensure to get permitted areas for the project land by the Central Administrative Body on Vacant, Virgin and Fallow Land, under sub-section (d) of section 10 of said law.
- b. The project proponent will promise to return the land if any antique object is found in the project area,



Laws and Deculations	Description				
under sub see	tion (a) of social and the social law				
c The project proponent will promise to return the land if any resource is found in the project under sub-					
section (d) of section 10 of said law					
The Settlement of I	cohor Dispute Low (2012)				
The Drideungen Hu	Labor Dispute Law (2012)				
relationship between	n employer and workers and making peaceful workplace or obtaining the rights fairly				
rightfully and quick	why settling the dispute of employer and worker justly				
Chapter II: Forma	tion of the Workplace Coordinating Committee				
3 In any trade in w	high more than 30 workers are amployed the amployer, with the view to perotisting and				
5. In any trade in w	nich more man 50 workers are employed, me employer, with the view to negotiating and				
(a) if there is an	whether organization form the Workplace Coordinating Committee with the view to make a				
(a) If there is any	gaining as follows:				
(i) two rop	gaming as follows.				
(i) two tep	instant number of representatives of employer:				
(h) if there is no	labor organization form the Workplace Coordinating Committee as follows:				
(i) two repre	abor organization, form the workprace coordinating commutee as follows.				
5 The Coordinating	Committee shall promote the good relationship between the employer and worker or labor				
organization neg	retiation and coordination on the conditions of employment terms and conditions and				
occupational safe	ty health welfare and productivity				
6 (a) If the worker	or labor organization or the employer by themselves or by representative request and				
complain	their grievances to the Coordinating Committee it shall be negotiated and settled by the				
Coordinati	ing Committee within five days, not including the official holidays, from the day of the				
receipt of	the request.				
(b) The Coordinating Committee shall keep the record of settlement and shall send report on the situation					
of perform	ance in accord with the stipulation to the relevant Conciliation Body.				
Chapter III: Forma	ation of the Conciliation Body				
10. The Region or S	tate Government shall form the Conciliation Body in the townships.				
Chapter IV: Forma	ation of the Dispute Settlement Arbitration Body				
16 (a) The Minis	extry shall with the approval of the Union Government, form the Dispute Settlement				
Arbitration	Body in the Regions or States				
Chapter V: Format	tion of Dispute Settlement Arbitration Council				
19 The Ministry sh	all with the approval of the Union Government form the Dispute Settlement				
Arbitration Cou	ncil with 15 qualified persons of good standing from legal experts and experts in				
labour affairs	Aron anon Council with 15 quantieu persons of good standing from legal experts and experts in				
Chapter VI: Settler	ment of Dispute				
23 A party employ	er or worker may complain individual dispute relating to his grievance to the Conciliation				
Body and if he	is not satisfied with the conciliation of such body in accord with stipulated manners, may				
apply to the competent court in person or by the legal representative					
International Guid	elines				
In the following Gu	idelines and standards are referred for Environmental Management Plan of the proposed				
clav soil mining ope	ration.				
a. World Health	Organization Standards.				
b. National Envi	ronmental Quality (Emission) Guidelines (2015).				
The National Environmental Quality (Emission) Guidelines provide the basis for regulation and control					
of air emissions and liquid discharges from various sources in order to prevent pollution for the					
protection of human and ecosystem health.					

c. IFC Guidelines for Waste Management Facilities, 2007.



CHAPTER 6 DESCRIPTION OF THE SURROUNDING ENVIRONMENTAL AND SOCIAL CONDITIONS METHODOLOGY

The following are the methodologies used for the IEE report preparation;

- i) On-site Measurements and Analysis During the preparation phase, baseline parameters such as air quality, noise level, soil and water quality of the existing project site are measured and collected on site, while some water and soil samples were collected and tested in respective laboratories, and results are mentioned in this Chapter.
- ii) Secondary Data Collection and Analysis Some data, such as socioeconomic condition, the physical/biological environment and weather data are collected from official township data received from the Township Administrative Office.

6.2 PHYSICAL ENVIRONMENT

6.2.1 Climate and Rainfall

6.1

The climate is tropical as it is located in the low latitude zone and near the sea, therefore it experiences the typical wet and dry seasons, and rain is especially heavy in July and August. In 2016, total precipitation days was 115 days with average annual rainfall of 147.22 inches and the minimum temperature of 17°C and the maximum temperature of 37.5°C were recorded in winter and summer respectively. In 2017, total precipitation days was 116 days with average annual rainfall of 144.87 inches and the minimum temperature in winter was 17°C and the maximum temperature in summer was 37.5°C respectively. The project site also has tropical climate and therefore it experiences the typical wet and dry seasons.

6.2.2 Topography

Kyaikmaraw Township is one of the townships in Mon State located at the south-east part of Myanmar, adjacent to Mawlamyine, but it is largely rural. Its location is between 16° 7' and 16° 34' north latitudes and between 97° 9' and 97° 50' east longitudes, bordering Kawkareik Township in the east, Hpa-An township in the north and Kyarin Seikkyi township in the south, Kawkareik township and Mudon township in the west. The township is having an area of approximately 516.04 square mile with east- west extends of about 18 miles and a north-south extends of about 40 miles.

Kyaikmaraw Township is only 18 feet above sea level as it is in the low lying plains. The town looks like an oval shape frying pan situated between Jaing river basin on the north of the town, Taung Nyo mountain range on the west and Attaran river basin at middle-west. Attran is one of the famous rivers flowing from south to north across the town.

The project site is located in Mon State area, about 40km South-East from Mawlamyine and 8km South from Kyeikmaraw. It is located in Kyaikmaraw Township and Malkaro Village is situated near the project site. In its surrounding, Kaw Panaw, Kaw Dun and We Nge Villages are located respectively. The project location map is shown in Figure 6.1.





Figure 6. 1 Project Location

6.2.3 Hydrology

Kyaikmaraw Township is 18 ft above the sea level and is located adjacent to the Ataran River. The main rivers and streams in the area are Ataran River, Jaing River, Za Mi stream and Win Yaw stream. Ataran is one of the famous rivers in the region and is flowing from south to north across the town. Ataran and Jyine rivers are accessible by ships and boats. Most of the rivers and streams provide freshwater and can therefore be used both for agricultures and domestic uses.

6.2.4 Access and Transportation

The project site is always accessible by boat navigating the Ataran River from Kyaikmaraw, from which project site can be accessed by means of cars or motorcycles. It can also be accessed by car from Mawlamyine during the dry season by the car.

6.3 ENVIRONMENTAL QUALITY MEASURING

Baseline environmental parameters and sampling locations for air, noise, water, and soil quality measuring were defined according to the objectives of the environmental measuring purposes. Locations for sampling and analysis of ambient air, water, noise, and soil quality of the project site were identified by E Guard Environmental Services.



6.3.1 Ambient Air Quality

The emissions of dust particles and gases were measured for 24hrs continuously at the selected site within the project area by using the Environmental Perimeter Air Station (EPAS), AeroquaL S500 and EPAS provides direct readings in real time with data-logging capabilities. The measuring results were compared with National Environmental Quality (Emission) Guideline (NEQG), World Health Organization (WHO) and American Conference of Governmental Industrial Hygienists (ACGIH) guidelines.

Ambient Air Quality	
Gas Emission	SO ₂ , NO ₂ , O ₃
Dust Emission	PM ₁₀ , PM _{2.5}

Table 6. 1 Ambient Air Quality Parameters

6.3.2 Ambient Noise

Noise level LAeq (dBA) will be measured at the selected location within the project area that can reflect the exposure of the nearest local community and sensitive locations. Duration and frequency were measured for 24hrs continuously at the selected site using the Noise Level Meter. The monitoring procedures, data analysis and interpretation were carried out in accordance with the instrument's manufacture and National Environmental Quality (Emission) Guidelines in order to be in line with Environmental Conservation Department, Ministry of Natural Resources and Environment Conservation (MONREC). "National Environmental Quality (Emission) Guidelines" for Myanmar was also presented the value of noise level as LAeq (dBA).

Table 6.2 Noise level monitoring

Noise monitoring	
Noise Emission	LAeq (dBA) (1hrs, 24 hrs.)

6.3.3 Water Quality

Surface water samples were collected at selected locations which are near irrigation scheme near project site and at Atran River with appropriate sampling equipment and procedures. The sampling team has pre-arranged with the labs in Yangon for analysis and logistic arrangement made to reach the preserved samples with unique IDs to the designated labs within 48hrs.

The sampling and survey team has a list of local laboratories providing analytical services for water quality analysis. Up to this date, there is no laboratory having accredited certification for water quality testing (environmental analysis) in Myanmar.

The following laboratories were used for analysis of water and parameters shown in **Table 6.3.**

1. ISO Lab, No-18, Lanthit Road, Insein Township, Yangon. Tel; 01 540 955, 732251575



2. SGS Minerals and Environmental Services, No. 79D, Bo Chain Street, 6-1/2Miles, Hlaing Township, Yangon. Tel; 01 654 795, 654 796

Water Quality Parameter			
Chemical Parameter	BOD, COD		
Physical Parameter	pH, Total Suspended Solid		
Nutrients	Total Nitrogen, Total Phosphorous		
Compounds	Oils & Grease		
Biological	Total Coliform Bacteria		

Table 6.3 Environmental Quality Parameters for Water Quality

On-site water quality measurements, water samplings are conducted using the following equipment as shown in **Table 6.4**.

Water Sampling Bottle	
water Sampling Bottle	

Table 6.4 Equipment for water sampling

6.3.4 Environmental Quality Measuring and Sampling Locations

Locations of sampling sites were discussed briefly by E Guard Environmental Services. Air quality and noise level monitoring were conducted at the selected locations within Clay soil production area. Surface water samples were collected near irrigation scheme near project site and at Atran River. Soil sampling was also conducted at the selected location within Clay soil Production Area.





Figure 6. 2 Environmental Quality Monitoring Locations

Locations No.	Points	Coordinate	Locations		
		Ambient Air Quality Monitoring	Location		
1	Air	Lat- 16°22'59.21"N, Long-	Within project site		
_		97°46'58.16"E	········ F···J····		
		Noise Level Measuring Loc	ation		
1	Noise	Lat- 16°22'59.21"N, Long-	Within project site		
1		97°46'58.16"E	within project site		
Surface Water Quality Location					
1	Surface	Lat- 16°22'54.43"N, Long-	Irrigation Sahama near project site		
1	Water	97°47'12.62"E	inigation scheme hear project she		
2	Surface	Lat- 16°21'34.275"N, Long-	Atron Diver neer project site		
Z	Water	97°47'38.319"E	Atran River hear project site		
Soil Quality Sampling Location					
1	Soil	Lat- 16°23'27.579"N,	Within project site		
		Long- 97°49'14.670"E	within project site		

Table 6.5 Location of Sampling Points

6.4 ENVIRONMENTAL QUALITY ANALYSIS

6.4.1 Ambient Air Quality

Air quality monitoring was done 24 hours at the selected location from 11 March 2019 to 12 March 2019. The measured results are compared with National Emission Guidelines.

There are many things, which are produced by humans and nature, those can pollute air quality. In general, they can be divided into two: Primary pollutants and Secondary pollutants. Primary pollutants are those that are produced directly into the air. The main



primary pollutants are particulate matters such as ash and smoke and gases such as SO_2 , NO_2 , and Ozone organic gases. Secondary pollutants are those that are produced from the chemical combination of primary pollutants and the chemicals contained in the normal air. They are NO_2 , SO_2 and O_3 , etc.

Emission Sources

Site clearing, topsoil removal, mine site preparation, mine production operation and closure may lead to the air quality degradation. Machinery operation, handling and transportation are the primary source of air pollutants and is the main factor that may cause impact on the environment and humans. Particulate matters and gases are produced from machinery operation and mine operations. Particulate matters (PM_{10} , $PM_{2.5}$), NO_2 , SO_2 are measured at specific time interval for 24 hours by EPAS Haz-Scanner and O_3 is measured 8 hours by Aeroqua S500. The measured results are compared with the National Environmental Quality (Emission) Guidelines.

(a) Particulate Matters (PM₁₀, PM_{2.5})

Clay soil extraction and transportation may produce a lot of particulate matters into the surrounding air. Generated particulate matters are measured at the project site and the results are compared with NEQEG guideline in the following **Table 6.6**.

Table 6.6 The result of Particulate Matter (PM10 and PM2.5) compared with NEQ Guideline (24hrs. continuous)

Date	Time	Substance (µg/m ³)	Result (µg/m ³)	NEQ (Emission) Guidelines (µg/m ³)
11.March.2019 12.March.2019	StartTime11:00 End Time10:59	PM10 µg/m ³	37.20	50
		PM2.5µg/m ³	29.61	25

(b) Nitrogen Dioxide (NO₂)

Nitrogen dioxide is one of the main air pollutants and is generally produced from combustion. Machinery operation and generator usually produce the gas. In machinery operation case, although they are the source of air pollution, the produced gas type may differ based on the type of the engines such as diesel engine or petrol engine. Inhalation of nitrogen dioxide may lead to lung diseases. The result of nitrogen dioxide is shown in below **Table 6.7.**



 Table 6.7 The result of Nitrogen Dioxide compared with NEQ Guideline (24hrs continuous)

Date	Time(1hr)	Substance (µg/m ³)	Result (µg/m ³)	NEQ Guidelines (µg/m ³)
11.March.2019 12.March.2019	StartTime11:00 End Time10:59	$NO_2(\mu g/m^3)$	5.86 (µg/m ³)	200 μg/m ³

(c) Sulphur Dioxide (SO₂)

Sulphur dioxide is the most important gas among the air pollutants. It is colorless and has significant odor. Heavy machinery used in operation is the source of Sulphur dioxide. It may cause eye and throat irritation and respiratory tract problems when inhaled. Continuous amount may lead to lung diseases. The result is shown in below **Table 6.8**.

Table 6.8 The result of Sulphur Dioxide compared with NEQ Guideline (24 hrs continuous)

Date	Time(24hrs)	Substance (µg/m ³)	Result (µg/m ³)	NEQ (Emission) Guidelines (µg/m ³)
11.March.2019 12.March.2019	StartTime11:00 End Time10:59	$SO_2(\mu g/m^3)$	2.62 (µg/m ³)	$20 \ \mu g/m^3$



Figure 6.3 PM Monitoring Results at Project Site





Figure 6.4 Fluctuation of Air Pollutants dial cycle at Project Site

(d) Ozone

Ozone is the most important gas among the air pollutants. It is a pale blue gas with a distinctively pungent smell. Pollution from cars comes from by-products of this combustion process (exhaust) and from evaporation of the fuel itself. It may cause shortness of breath, and pain when taking a deep breath. Cause coughing and sore or scratchy throat. Inflame and damage the airways. Aggravate lung diseases such as asthma, emphysema, and chronic bronchitis. The result is shown in below **Table 6.9**.

Table 6.9 The result of Ozone compared with	h NEQ Guideline (8 hrs continuous)
---	------------------------------------

Date	Time(24hrs)	Substance (µg/m³)	Result (µg/m³)	NEQ (Emission) Guidelines (µg/m ³)
11.March.2019 12.March.2019	StartTime11:00 End Time10:59	$O_3(\mu g/m^3)$	110.319 (μg/m ³)	21 g/m ³

As per above tables, it can be seen that $PM_{2.5}$ parameters measured are upper the National Environmental Quality (Emission) Guideline (NEQG) because dust concentration is high during dry season. Ozone is upper the National Environmental Quality (Emission) Guideline (NEQG) because ozone level may be high during summer month. NO₂ and SO₂ are within the National Environmental Quality (Emission) Guideline (NEQG).





6.4.2 Ambient Noise

Ambient noise level for the proposed project was measured with Digital Sound Level Meter at the project site. The noise level measurement is conducted at one point near the air monitoring points on 11 March to 12 March 2019. Measuring period is 24 hours continuously. The following figures are noise level measurement at the proposed project.



Figure 6.7 Noise Level at Clay soil



Table 6.10 National Environmental Quality (Emission) Guideline Value for Noise Level

Decentor	One Hour LAeq (dBA)			
Keceptor	Day Time 07:00 – 22:00	Night time22:00 – 07:00		
Residential, institutional, educational	55	45		
Industrial, commercial	70	70		

^a Equivalent continuous sound level in decibels

Source: National Environmental Quality (Emission) Guidelines, 2015

Table 6. 11 Noise Level Measured within the Proposed Project

No.	Sources	Location	Date and Time	Day Time Average Noise Level (dB)A	Night Time Average Noise Level (dB)A	
1.	Noise Source	Perimeter of the clay soil soil production area	11.3.2019 Day time (7:00 AM - 22:00 PM) Night time (22:00PM - 7:00 AM)	41.78	42.13	
Weat	Weather was Fine (^a Average; ^b Min; ^c Max)					

The observed values are compared with the National Environmental Quality (Emission) Guidelines as shown in **Table 6.10** which indicates the separate level for residential points.

The proposed project is located adjacent to the residential area. All the observed daytime and night time values are lower than the National Environmental Quality (Emission) Guidelines.



Figure 6.8 Noise quality measure



Figure 6.9 Noise quality measure



6.4.3 Wind Speed and Direction

The following figure describes the wind speed and wind direction of the proposed project site on, 11 March to 12 March 2019 respectively. According to the data, the wind is blowing from North to South direction expressed in the following figure.



Figure 6.10 Wind Speed and Wind Direction (Blowing From) at Clay soil



Figure 6.11 Wind Class Frequency Distribution at Clay soil

6.4.4 Water Quality

The project proponent is responsible for ensuring the drainage or runoff from the project or its related activities do not deteriorate the existing water quality. Baseline quality



of water quality was recorded by on site sampling and laboratory analysis at the selected location systematically. The field surveys for environmental quality sampling were done during 17 March 2019.

Objectives of the sampling and analysis of water quality is to understand the existing water quality at the selected locations and to monitor the impacts before the operation.

Water quality sampling results are shown in **Table 6.12** and compared with National Environmental Quality (Emission) Guidelines (NEQEG). According to the laboratory results, results of all parameters are within the NEQEG. Laboratory results of water quality can be seen in **Appendix 1 and 2**.

Parameters	National Environmental Quality (Emission) Guidelines for General	Results
Agricultural drain near project sit	e	
Biochemical Oxygen Demand (BOD) (5 days at 20 .C)	30 mg/l	8 mg/l
Chemical Oxygen Demand (COD)	125 mg/l	32 mg/l
Oil & Grease	10 mg/l	<5 mg/l
pH (Lab Results)	6-9 S.U.	7.2
Total Suspended Solids	50 mg/l	46 mg/l
Total Nitrogen	10 mg/l	<1 mg/l
Total Phosphorus	2 mg/l	<0.01 mg/l
Total Coliform Bacteria	400 CFU/100ml	4 CFU/100ml
Turbidity	5 NTU	81 NTU
Colour (True)	15 TCU	60 TCU
Atran River near project site		
Nitrate (N.NO3)	50 mg/l	0.3 mg/l
Dissolved Oxygen (DO)		5.4 mg/l
Biochemical Oxygen Demand (BOD) (5 days at 20 .C)	30 mg/l	16 mg/l
Turbidity	5 NTU	330 NTU
Colour (True)	15 TCU	120 TCU
pH (Lab Results)	6-9 S.U.	7.6
Salinity		0.1 ppt
Total Coliform Bacteria	400 CFU/100ml	18 CFU/100ml

Table 6. 12 Surface Water Quality Results



Thermotolerant (Fecal) Coliform	4 CEU/100ml	
Count	4 CF0/100111	



Figure 6.12 Surface Water quality measure

6.4.5 Soil Quality

In Myanmar, there is still no government guideline for determination of background values of metals and metalloids in soil. Internationally, respective national guidelines use definition of natural background concentration in natural soil. The stepwise approach for deriving background values involves collection of data, statistical analysis of the data and determination of the background value. In this project, baseline soil sample was collected to understand the soil and sediment quality of existing conditions Analyzed results are shown in **Table 6.13**. The result of soil quality compared with FAO Guidelines. Soil quality result can be seen in **Appendix 3**.

No	Doromotors	Project Site	FAO Guidelines
110.	1 al ametel s	Laboratory Finding (ppm)	Maximum Permitted Level (ppm) *
Ι	Heavy Metal Conta	aminants	
1.	Chromium (Cr)	53.9	100
2.	Cadmium (Cd)	ND	0.8
3.	Lead (pb)	38.6	85

Table	6.	13	Soil	Quality	Result
-------	----	----	------	---------	--------



No	Doromotors	Project Site	FAO Guidelines
INU.	rarameters	Laboratory Finding (ppm)	Maximum Permitted Level (ppm) *
4.	Arsenic (As)	31.1	29
5.	Irons (Fe)	88,312	250
6.	Mercury	ND	0.5
7.	Cyanide	-	2
II	Micro Nutrients		Sufficient Level (ppm) *
1.	Zinc (Zn)	127	20-100
2.	Copper (Cu)	37.8	20-300



Figure 6. 13 Soil quality measured

6.5 ECOSYSTEM

(a) Flora

Flora species usually found in Kyaikmaraw Township are Pyinkadoe, Padauk, Inn, Htaukkyunt, Pyinma, Thityinn, Lamu, Thinkhan, Thityar, Kokko, Latpan and Pauk according to the township data. The following table shows the recorded plant species which are referenced from EIA for June Cement Production Project.

Sr.	Common Name	Scientific Name	Family	Habitat
1	Bisat	Chromolaena odorata	Asteraceae	Shrub
2	Chin-baung	Hibiscus surattensis	Malvaceae	Shrub

Table 6. 14 Flora Species Found in Kyaikmaraw Township



3	Gway tauk	Dregea volubilis	Asclepiadaceae	Climber
4	Ha Kyoe (Mon)	Unknown-1	-	Tree
5	Ha Mine (Mon)	Unknown-2	-	Tree
6	Headache tree	Premna serratifolia	Lamiaceae	Shrub
7	Hnee War	Bambusa burmanica	Poaceae	Bamboo
8	Htan	Borassus flabellifer	Arecaceae	Tree
9	Hti-ga-yon-gale	Neptunia javanica	Mimosaceae	Aquatic
10	Ka Zai (Mon)	Unknown-3	-	Shrub
11	Kathit	Erythrina arborescens	Fabaceae	Tree
12	Kazun-galay	Ipomoea aquatica	Convolvulaceae	Climber
13	Kinmunchin	Acacia concinna	Mimosaceae	Climber
14	Kokko	Albizia lebbek	Mimosaceae	Tree
15	Kyaung-sha	Oroxylum indicum	Bignoniaceae	Tree
16	Kyee	Barringtonia acutangula	Lecythidaceae	Tree
17	Latpan	Bombax ceiba	Bombacaceae	Tree
18	Le lu	Erythropalum scandens	Olacaceae	Climber
19	Louk thay	Tadehagi triquetrum	Fabaceae	Shrub
20	Ma U	Neolamarckia cadamba	Rubiaceae	Tree
21	Malzali	Senna timoriensis	Caesalpiniaceae	Small tree
22	Mayan	Bouea burmanica	Anacardiaceae	Tree
23	Mhoe	Agaricus spp.	Agaricaceae	Fungi
24	Mon Daing	Cycas siamensis	Cycadaceae	Small tree
25	Myauk chaw	Homalium tomentosum	Flacourtiaceae	Tree
26	Naung	Ficus spp.	Moraceae	Tree
27	Ngar yanpatu	Clerodendrum indicum	Verbenaceae	Shrub
28	Nget pyaw	Musa sapientum	Musaceae	Herb
29	Nyan Pin	Sesbania bispinosa	Fabaceae	Shrub
30	Pain Ngel	Artocarpus heterophyllus	Moraceae	Tree
31	Panhtain ngo yeil	Calanthe triplicata	Orchidaceae	Herb
32	Phalan taung Way	Costus speciosus	Costaceae	Herb
33	Pyin Kado	Xylia xylocarpa	Mimosaceae	Tree
34	Pyin ma	Lagerstroemia speciosa	Lythraceae	Tree
35	Pyin taw thein	Clausena excavata	Rutaceae	Small tree
36	Sayyoe(Ohn nel)	Streblus asper	Moraceae	Small tree
37	Sin hna maung	Heliotropium indicum	Boraginaceae	Herb
38	Suboke	Acacia intsia	Mimosaceae	Climber
39	Taung Htan	Livistona speciosa	Arecaceae	Tree
40	Taung thale	Garcinia cowa	Hypericaceae	Tree
41	Taung Thapyay	Tristaniopsis burmanica	Myrtaceae	Tree
J	1			



42	Taung war	Asparagus sprengeri	Asparagaceae	Shrub
43	Taw Durin	Durio mansoni	Bombacaceae	Tree
44	Taw sabai	Jasminum rottlerianum	Oleaceae	Climber
45	Taw Zi	Ziziphus rugosa	Rhamnaceae	Small tree
46	Taw-danyin	Connarus paniculatus	Connaraceae	Climber
47	Taw-nget-pyaw	Musa laterita	Musaceae	Herb
48	Tayok-saga	Plumeria rubra	Apocynaceae	Small tree
49	Tha pan	Ficus glomerata	Moraceae	Tree
50	Tha pyay	Eugenia bracteolata	Myrtaceae	Tree
51	Thabyu	Dillenia indica	Dilleniaceae	Tree
52	Thaing-kyein	Calamus erectus	Arecaceae	Climber
53	Thanat-kha-ayine	Dracaena multiflora	Asparagaceae	Tree
54	Thatyet phyu	Mangifera caesia	Anacardiaceae	Tree
55	Thayet	Mangifera indica	Anacardiaceae	Tree
56	Thin baw	Carica papaya	Caricaceae	Small tree
57	Thit phyu	Albizia procera	Fabaceae	Tree
58	Venus hair fern	Adiantum capillus-veneris	Pteridaceae	Fern
59	Wa U	Amorphophallus paeoniifolius	Araceae	Herb
60	War boe	Dendrocalamus brandisii	Poaceae	Bamboo
61	Үеуо	Morinda angustifolia	Rubiaceae	Small tree
62	Yone padi	Hibiscus panduriformis	Malvaceae	Shrub
63	Zi	Ziziphus jujuba	Rhamnaceae	Tree

Source: EIA report for June Cement Production Project

(b) Fauna

Wild boar, barking deer and monkeys are found in Kyaikmaraw Township according to the township data. The following table shows the recorded fauna species which are referenced from EIA for June Cement Production Project.

		L	v 1	
No		Common Name	Scientific Name	IUCN
1		Jungle Cat	Felis chaus	LC
2		Monkey	Unidentified	-
3	mals	Rhesus Macaque	Macaca mulatta	LC
4	Mam	Pallas's Squirrel	Calloscriurus erythreaus	LC
5		Bumblebee Bats	Craseonycteris thonglongyai	LC
6		Geoffroy's Rousette	Rousetttus amplexicaudatus	LC

 Table 6. 15 Fauna Species Found in Kyaikmaraw Township



7		Jungle Crow	Corvus macrorhynchos	LC/R
8		Pigeon	Columba livia	LC/R
9		Common Swift	Apus sp.	LC/R
10		Common Myna	Acridotheres tristis	LC/R
11		Black-capped bulbul	Pycnonotus melanicterus	LC/R
12		Spotted Dove	Spilopelia chinensis	LC/R
13		Green-billed malkoha	Phaenicophaeus tristis	LC/R
14	ds	Asian openbill	Anastomus oscitans	LC/R
15	Bir	Mountain tailorbird	Phyllergates cucullatus	LC/R
16		Crow Pheasant	Centropus sinensis	LC/R
17		Black-headed bulbul	Pycnonotus atriceps	LC/R
18		Indian roller	Coracias benghalensis	LC/R
19		Fulvous whistling duck	Dendrocygna javanica	LC/R
20		Black Bulbul	Hypsipetes sp.	LC/R M
21		Common Weaver	Ploceus hypoxanthus	LC/R
22		Oriental magpie robin	Cosychus saularis	LC/R
23		Python	Python bivittatus	VU
24		Viper	Montivipera xanthine	VU
25	eptiles	Common Garden Lizard	Calotes mystaceus	LC
26	Ř	Cobra	Ophiophagus hannah	VU
27		Gecko	Cyrlodactylus pulchellus	LC
28		Snail	Ashmunella sp.	NT
29	su	Giant River Prawn	Machrobrachium rosenbergil	LC
30	stacea	Golden apple snail	Pomacea canaliculata	LC
31	Cru	Shrimp	Peneaus sp.	NE
32		Freshwater Crab	Somanniathelphusa spp.	DD
33	ibians	Common Toad	Duttaphrynus melanostictus	LC
34	Amphi	Frog	Fejervarya sp.	LC



35		Paradise threadfin	Polynemus paradiseus	NE
36		Croaker	Johnius macropterus	NE
37		Hilsa Shad	Tenualosa ilisha	NT
38		Tropical two-wing flyingfish	Exocoetus volitans	LC
39		Snakehead Murrel	Chanana striata	NE
40		Walking Catfish	Clarias batrachus	LC
41	les	Swanp Barb	Puntius chola	LC
42	Fish	Colorful Eel	Mastacembelus unicolor	NE
43		Perch	Anabas testudineus	DD
44		Featherback	Notopterus notopterus	LC
45		Nile Tilapia	Oreochromis niloticus	LC
46		Murrel	Chana sp.	NE
47		Stripted Dwarf Catfish	Mystus mystus	NE
48		Wallago	Wallago attu	NT
49		Leopard or spotted rustic	Phalanta phalantha	NE
50		Common tiger	Danaus genutia	NE
51		Common grass yellow	Eurema hecabe	NE
52		Black stream glide	Trithemis festiva	LC
53		Slender skimmer	Orthetrum sabina	LC
54		Common crow	Euploea core godarti	NE
55		Brown argus	Aricia agestis	NE
56	nsects	Great Mormon	Papilio memnon agenor	NE
57		Clipper	Parthenos Sylvia apicalis	NE
58		Common Mormon	Papilio polytes romulus cramer	NE
59		Common Mormon	Eurema pallida	NE
60		Pied paddy skimmer	Neurothemis tullia	LC
61		Crimson-tailed marsh hawk	Orthetrum pruinosum	LC
62		The plain tiger	Danaus chrysippus	NE
63		Dragonfly	Potamarcha congener	LC



64	Pond Skaters	Gerridae	NE
65	Locust	Locusta migratoria	LC
66	Common Green Grasshopper	Omocestus viridulus	NE
67	Butterfly	Unidentified	-
68	Spider	Unidentified	-
69	Common red soldier beetle	Rhagonycha sp.	NE
70	Bug	Chrysomela sp.	NE
71	Wasp	Dolichovespula spp.	NE
72	Seven-spot ladybird	Coccinella septempunctata	NE
73	Antlion Lava	Distoleon tetragrammicus	NE
74	Fruhstorfer	Cethosia cyane euanthes	NE
75	Small Dragonfly	Brachythemis contaminatea	LC

NE: Not Evaluate; DD: Data deficiency; LC: Least Concern; VU: Vulnerable; NT: Near Threatened Source: EIA report for June Cement Production Project

(c) Cultural Heritages

There is no cultural heritage site in the project area.

(d) Environmental Condition

Kyaikmaraw Township has 22.04% of total forest coverage and all of them are reserved forest area. There is no protected public forest in the township.

(e) Environmental Conservation Works

For environmental conservation, total area of 72804.88 acres has been established as the reserved forest area. Currently, there is no protected public forest and total forest plantation area for hard wood is 11 acres.

(f) Natural Disasters

Kyaikmaraw Township usually encountered flood in rainy season, especially in heavy raining condition. As a record, no natural disasters such as storm, tsunami, earthquake, fire, have been recorded in Kyaikmaraw Township up to September, 2017. Source: General Administration Department Kyaikmaraw township data (2017)

6.6 SOCIAL ENVIRONMENT

(a) Economic Overview

Kyaikmaraw Township is located in Mon State, Thanintharyi Division and is one of the little undeveloped townships. Agriculture is the main business in the township. From



Kyaikmaraw, Mawlamyine, Mudon, Kawkareik and Kyainseikgyi regions are accessible by land and sea routes and therefore has the good communication network. Rubber is the main product of the region and is mainly exported to Mawlamyine and Mudon.

(b) Ethnic Groups

The followings are the record of ethnic groups living in Kyaikmaraw Township.

No.	Races	Populations	Township population	Percent of total township population
1	Kachin	-	-	-
2	Kayar	-	-	-
3	Kayin	45558	45558	20%
4	Chin	5	5	0.01%
5	Mon	106978	106978	48.18%
6	Myanmar	28377	28377	13.23%
7	Rakhine	35	35	0.02%
8	Shan	1120	1120	0.47%
9	PaOo	-	-	-
10	Others	39970	39970	19.01%
11	Pakistan	2	2	0.01%
Total		222091	222091	101%

 Table 6.16 Ethnic Groups Living in Kyaikmaraw Township

Source: General Administration Department Kyaikmaraw township data (2017)

(c) Households, Families and Populations

Total populations of Kyaikmaraw Township up to September, 2017 are shown in the following tables.

No	Description	Households	Families	Ward	Village Groups	Village
1	Urban	2102	2120	2	43	164
2	Rural	33515	35717	2	43	164
Total		35617	37837	2	43	164

Source: General Administration Department Kyaikmaraw township data (2017)



	Tuble 0.10 Found openations of Ryunkington Township									
No	Description	Over 18 years old Under 18 years old		s old	old Total					
	Description	Male	Female	Total	Male	Female	Total	Male	Female	Total
1	Urban	4308	4628	8936	1967	1952	3919	6275	6580	12855
2	Rural	62814	66685	129499	39581	40156	79737	102395	106841	209236
Total		67122	70313	138435	41548	42108	83656	108670	113421	222091

Table 6.18 Total Populations of Kyaikmaraw Township

Source: General Administration Department Kyaikmaraw township data (2017)

(d) Forest

Table 6.19 Forests in Kyaikmaraw Township

No	Description	Area (acres)	Plants
1	Reserved Forest	72623.30	Pyinkadoe, Inn, Yaymein, Myayar, Didu, Zinpyon, Nabae, Sits
2	Protected Public Forest	-	-
	Total	72623.30	-

Source: General Administration Department Kyaikmaraw township data (2017)

(e) Forest Products

Table 6.20 Forest Products of Kyaikmaraw Township

No	No Type		Production	
1	Firewood	Cubic Tons	430	
2	Bamboo	Unit	34000	

Source: General Administration Department Kyaikmaraw township data (2017)

(f) Mineral Production

Information about mineral production in Kyaikmaraw Township is shown as below.

Table 6.21 Mineral Production of Kyaikmaraw Township

No	Mineral Type	Location	Amount (Sud)	Cost (in millions)
1	Cobble-stone	Kun Ngan village	4400	11000
2	Cobble-stone	Nga Pu Inn village	1600	4000
3	Cobble-stone	Kaw Pa Naw village	1100	2750
4	Cobble-stone	Hpar Thein village	700	1750
	Tota	ıl	7800	19500

Source: General Administration Department Kyaikmaraw township data (2017)


(g) Land use

Different types of land use in Kyaikmaraw Township can be submitted as follows;

No.	Types of Land	Area (acre)
1.	Net acre for plantation	144589
	(i) Farmland	52853
	(ii) Orchard	91736
2.	Vacant Land Area	51708
	(i) Farmland	51708
3.	Pasture Land	8005
4.	Land for industrial zone	1492
5.	Urban Lands	2912
6.	Village Lands	9076
7.	Other Lands	3071
8.	Reserved forest and protected forest area	72602
9.	Wild forest	6569
10.	Wild land	11544
11.	Area not to be cultivated	40482
	Total	327494

Table 6. 22Types of Land Use in Kyaikmaraw Township

Source: General Administration Department Kyaikmaraw township data (2017)

6.7 SOCIAL-ECONOMIC SURVEY RESULTS

E Guard's IEE study team interviewed three villages (Malkaro, KawPaNaw and Kaw Don) located near the proposed project. Most of the local people are migrated workers for their livelihood. Most of the people in KawPaNaw and Kaw Don are used purified water and tube well water. In Malgaro village, tube well water is used for their drinking and domestic water. In KawPaNaw and Kaw Don Village leaders also said transportation is good. In Malkaro, village leader said transportation is very difficult in during rainy season. They said that, transportation, education, economic health conditions and job opportunity may develop due to the proposed project. If June Cement Production Project use coal as fuel for cement production process, local people are worried about environmental pollution may be occurred.



CHAPTER 7

IDENTIFICATION AND ASSESSMENT OF POTENTIAL ENVIRONMENTAL IMPACTS

7.1 IDENTIFICATION AND ASSESSMENT OF POTENTIAL ENVIRONMENTAL IMPACTS

Based on the analysis of environmental baseline information and activities that are to be performed by the project, the possible environmental impacts are identified. The development of the project will bring changes in the local environment in terms of physical, biological and socio-economic aspects. There may be some positive and negative impacts in the surrounding environment of the project. The potential impacts are identified in terms of each environmental issue, likely impacts during preparation, operation and decommissioning/ closure phases. The potential impacts from various activities of the project can be categorized as shown in **Figure 7.1**.





7.2 OBJECTIVE

The main objective of this study is to assess the impacts of mining on local livelihoods and the environments within Kaw Pa Naw Village and Malkaro Village tracts and to assess the environmental impacts of clay soil production operation.



7.3 PHASES OF CLAY SOIL PRODUCTION PROJECT

There are different phases of clay soil production project, beginning with mineral ore exploration and ending with the post-closure period. Each phase of clay soil mining is associated with different sets of environmental impacts. Potential impacts have been separated three main types based on different phases of development, i.e. Preparation phase, Operation phase and Decommissioning/Closure phase.

Preparation Phase: This phase will include site preparation, construction of temporary camps, workshop, water storage tank, kitchen, toilets and other related activities.

Operation Phase: During the operation phase the following will be conducted:

- Operation and maintenance of vehicles, heavy equipment and generators;
- Extraction, Excavations, transportation of materials; and
- Topsoil stockpile.

Decommissioning Phase: This phase related activities would require the use of the demolishing equipment. Where needed, any existing hazardous materials used in decommissioning would be properly handled and disposed of in accordance with governing authority requirements. Tentative schedule for clay soil mining operation is shown in **Table 7.1**.

			Years										
Phases	Activities	2 yrs					30	yrs					1 yr
Preparatio n Phase	Land Clearing and Topsoil Removal												
	Excavation												
Operation Phase	Transportation to the cement plant												
Demolishi ng/Closur e Phase	Demolishing the Clay soil Mining Associated Materials												
	Rehabilitation												

 Table 7. 1 Tentative Schedule for clay soil Mining Operation Activities

7.4 METHODOLOGY & APPROACH FOR IMPACT ASSESSMENT

The assessment of each impact is based on consideration of four parameters: magnitude, duration, extent and probability of activities, which are going to be carried out during three phases and characteristics of the project site.

The following methodology has been applied to assess the environmental impacts of the clay soil mining operation mainly on air, water, soil and etc. Each assess point has 5 scales as mentioned in the **Table 7.2**.



Accessment	Scale										
Assessment	1	2	3	4	5						
Magnitude (M)	Insignificant	Small and will have no effect on the environment	Moderatea nd will result in minor changes in the environment	High and will result insignificant changes on environment	Very high And will result in permanent changes on environment						
Duration(D)	0-1year	2-5year	6-15year	Longer than 15 year	Permanent						
Extent(E)	Limited to the site	Limited to the local area	Limited to the region	National	International						
Probability(P)	Very improbable	Improbable	Probable	Highly probable	Definite						

Table 7.2 Impact Assessment Parameters and Its Scale

Then, the significant point (SP) is calculated by following formula.

Significant Point (SP) = (Magnitude+ Duration+ Extent)*Probability

Based on calculated significant point, impacts significance can be categorized as follows:

i 0										
Significant Point (SP)	Impact Significance									
<15	Very low									
15-29	Low									
30-44	Moderate									
45-59	High									
<60	Very High									

Table 7. 3 Impact Significance

According to the assessment methodology, very low and low significance impacts can be regarded as negligible impact to the environment, in which there is no significant impact on the environment.

However, moderate impact can have little effect on the environment. So, some mitigation measures must be considered. High impact can have significant changes in the environment. Therefore, mitigation measures must be done. Very high impact can be permanent changes in the environment. To reduce and control the impacts and disadvantages on the environment, mitigation measures must be performed.

7.5 POTENTIAL ENVIRONMENTAL IMPACTS IDENTIFICATION AND ASSESSMENT

The proposed clay soil mining project is the extraction of clay soil. Mining operations involve development of benches, approach roads, haul roads, excavation and handling & transportation of clay soil. It is associated with a number of environmental impacts, which are



land degradation, open cast which may serve as the animal traps and may pose health hazards, water pollution, soil pollution, dust and noise pollution. The likely effects of the proposed project activities are:

- 1. Land degradation;
- 2. Visual intrusion of land;
- 3. Fugitive dust generation;
- 4. Higher run-off during rains;
- 5. Higher noise and vibration levels; and
- 6. Human health risks.

The haulage of clay soil within the mining area will lead to emissions of fugitive dust and higher noise levels in the mining area and surrounding village. These operations generally result in generation of dust and higher noise levels and there by pose health hazards. Proposed open cast mine will result in disturbance of the land use pattern of the Area and cutting of benches will result in higher chance of erosion effects due to surface run-off during heavy rainfall. Storage and handling of fuel oils, lubricating oil and grease, are areas of concern from environmental, health and safety point of view. Vehicle and equipment maintenance would generate waste oils; oil and grease and suspended particle. Mine office and worker camps will also mainly contribute towards solid waste and sanitary wastewater.

7.5.1 Impact on Aesthetics resources

Preparation, Operation and Decommissioning/Closure Phase

Throughout the lifespan of clay soil mining, sources of visual impact and their impact will be clearly varied and this needs to be considered and properly addressed at the outset. In addition, due to excavation activities permanent landscape change may occur and therefore long-term visual modification of the landscape must be considered. The clay soil mine project can affect surrounding landscapes and natural landmarks. Potential impacts include:

- Complete destruction of the resource through surface disturbance or excavation;
- Degradation or destruction, due to topography or hydrological pattern changes or from soil movement (removal, erosion, sedimentation); and
- Visual impacts due to clearing of vegetation, large excavations and vehicles.

7.5.2 Impacts on Air Quality

Preparation Phase: During these phases, there can be particulate matter, nitrogen dioxide, carbon dioxide, Ozone and Sulphur dioxide emissions from activities such as operation and maintenance of vehicles, any on-site power generation facilities, site preparation and other related activities. Gas emissions may occur from the combustion of fuels in temporary camps and mobile sources. In addition, potential sources of dust and gaseous emissions during the preparation phase include:

- Land clearance and preparation;
- Heavy vehicle operation;
- Topsoil loading, unloading, transportation and storage;
- Access road preparation; and



• Power generation and general vehicle use.

Operation Phase: During these phases, fugitive dust in the clay soil mining site may be generated from exposed surface such as haul roads and infrastructure and to a lesser extent, gases from combustion of fuels in mobile equipment. Operation of vehicles and generators can also lead to releases of airborne of greenhouse gases and various air contaminants, including sulphur oxides, nitrogen oxide and particulate matter. Open cast topsoil stockpiles are potential sources of windblown particulate matter. In addition, operational activities that may affect the air quality (dust and gas) include;

- Earth moving equipment (backhoes);
- Top soil stripping, transportation and storage;
- Land clearing and road grading;
- Fuel burning in heavy equipment and vehicles;
- Fugitive emissions through use of oils and greases;

Dust and other particulate matters can cause breathing problems for people, especially very small dust particles. Dust can also contain metals and other contaminants which can also cause health problems.

Decommissioning/Closure Phase: During these phases, operation of vehicles, operation of decommission machineries and equipment can also lead to releases of airborne greenhouse gases and various air contaminants, including sulfur oxides, nitrogen oxide and particulate matter. Large quantities of dust will generate during the demolition phase. This will affect the workers engaged in the demolition process.

7.5.3 Odor

Preparation, Operation and Decommission/Closure Phases

Fuel from vehicles and diesel generators will be one of the main sources of odor emissions at the clay soil mining site.

7.5.4 Impacts on Noise and Vibration

Preparation Phase: During the preparation phase, major sources of noise and vibration may include noise and vibration from vehicle engines, power generation and other sources related to preparation activities. Moreover, noise and vibration could be generated from vehicles used for transportation of preparation materials and other preparation machineries and equipment such as hydraulic excavator, generator and etc.

Operation Phase: During the operation phase, the key issues related to noise and vibration is concerned with ongoing excavation of soils involving earth moving equipment operation (hydraulic excavator). The most significant noise and vibration include:

- Material handling equipment and operations;
- Mining equipment operation
- Other internal combustion engine powered equipment; and
- Vehicles operations;



Decommissioning/Closure Phase: The decommission phase will generally involve less noise and vibration generation due to the absence of operational equipment. Much of the area will be reclaimed by covering with soil, involving limited use of earth moving equipment.

7.5.5 Impacts on Soil Quality and Terrestrial Ecosystem

Preparation Phase: During the preparation phase, soil erosion may be caused by exposure of soil surfaces to rain and wind during site cleaning, earth moving, excavation activities and heavy and prolonged rainfall. In addition, degradation and loss of topsoil can be occurred due to the removal and compaction of soil, working activities, and open areas. In addition, site clearing activities, excavation works and preparation activities will cause loss of soil quality in the clay soil mining site. The removal of topsoil from the mine site is exposed the soil and therefore change the original soil texture and structure. The leveling the mine site during the preparation can impact the terrestrial ecosystem of the mine site depending on the condition of the existing vegetation. The most obvious impact to biodiversity from mining is the removal of vegetation, which in turn alters the availability of food and shelter for wildlife. Forests are the most biologically diverse terrestrial ecosystems. The key direct impacts include road building development, which may result in habitat fragmentation and increased access to remote areas.

Operation Phase: During the operation phase, topsoil that will remove and kept for later reuse in reclaiming the site should be taken in care not to affect the mine site and environment. The major effect of clay soil mining activity in the project area is soil erosion. Erosion is caused by land disturbances and removal of vegetation in the process of clay soil mining. Spills or leakages from machineries, vehicles and fuel storage area can happen due to improper handling or disposal that can cause soil contamination. Destruction of the habits is the main component of biodiversity losses, but direct poisoning caused by mine-extracted materials and indirect poisoning through food and water, can also affect animals, vegetables and micro-organisms.

Decommissioning/ Closure Phase: During this phase, other mine facilities will be reclaimed by covering with topsoil at the proposed mine site. There will be some localized reclamation of disturbed sites, including re-grading, re-contouring and rehabilitation, thereby reducing potential erosion.

7.5.6 Impacts on Water Quality and Aquatic Ecosystem

Preparation Phase: The removal of top soil during preparation may affect the quality of surface water recharging of an aquifer. In the project area, potential contamination of water sources may occur early in the mine site during the preparation stage. The removal of trees and other vegetation and level the mine site during the preparation phase can lead to problems with sedimentation in nearby water bodies due to releases of suspended solid in surface water runoff. In addition, potential sources of water quality and aquatic ecosystems during the preparation phase include:



- Operation and maintenance of vehicles;
- Leaks from on-site power generation facilities;
- Spillage of fuel transportation, handling and storage;
- Site preparation and construction activities;
- Sewage and wastewater disposal; and

Operation Phase: The potential impact on the surface water quality is likely to be due to higher load of suspended solids. Sources of suspended solids would be:

- Mine runoff and Wash off from topsoil stock piles;
- Oil spillage from vehicle maintenance; and
- Domestic Effluent and sewage;

Operational activities that may affect water levels and quality include;

- Discharged water from dewatering process in both operation and rainy season when the project activities under steady state.
- Clearing land form for operational purpose;
- Storage and use of hazardous materials (oil and etc.) on site.

Decommissioning/Closure Phase: Demolition activities during monsoon season or rainy periods will produce wastewater generated from workers and staffs, and leakage of oil and grease from vehicles and demolished machines.

7.5.7 Waste Generation

7.5.7.1 Solid Waste

Preparation Phase: The waste includes excavated materials from the earthworks and other non-hazardous solid wastes from the preparation activities. Other types of solid waste may include workshop scrap, household and other potentially hazardous wastes.

Operation Phase: The most significant waste generating from mining activities will likely occur during the operation phases, which require the movement of small amounts top soil. Other types of solid waste may include workshop scrap, household and non-process related chemicals and other potentially hazardous wastes.

Typical non-hazardous and hazardous wastes that will be generated from operations are as follows:

- Domestic wastes (food waste from temporary camp, some plastics and etc.);
- Regulated waste (batteries, tires and etc.) from workshop;
- General waste (beings wood, un-recyclable plastics, etc.);
- Machinery maintenance materials, such as oily rags, used oil filter and used oil;
- Recyclable scrap metal;
- Fuel and oil handling and storage.

Decommission/Closure Phase: During the demolition phase the dismantling of project temporary camps and related infrastructures will result in large quantities of solid waste. The waste will consists of demolition debris such as wood, glass and etc.



7.5.7.2 Liquid Waste

Preparation Phase: Up to 10 personnel will be present at the camp during the preparation phase. Wastewater generated by the increased number of workers will cause aggravation of the existing water quality, if enough portable toilets are not provided at the preparation site.

Operation Phase: During the operation phase, wastewater from domestic may be sources of pollution of nearby water sources. Wastewater generated by the increased number of workers will cause aggravation of the existing water quality if enough portable toilets are not provided at the project site. In addition, wastewater effluent will be generated from sanitary waste produced by 12 employees.

Decommission/Closure Phase: During the decommissioning phase, the generation of sanitary wastewater discharges may occur in varying quantities, depending on the number of workers involved.

7.5.8 Fire Hazards

Preparation, Operation and Decommissioning/Closure Phase

In the clay soil mining area, significant hazards can be occurred due to oil barrel and diesel will be stored in project compound for generator and clay soil mining operation activities, without the proper storage system, that can cause fire hazards during the operation phase. Other types of fire hazards may include storage of preparation and decommissioning materials, improper handling or maintenance of electrical equipment and other related preparation and decommissioning equipment.

7.5.9 Impacts on Occupational and Community Health and Safety

Preparation, Operation and Decommissioning/Closure Phase

In the preparation and decommissioning/closure phase, significant hazards can be occurred due to the potential fall of material or tools as well as temporary hazards such as physical contact, spills, dust emission and noise pollution. Moreover, accidents and injuries to workers and local communities can be caused by the heavy vehicles movement for the transport of construction materials and equipment.

7.5.10 Socio-economic Resources during All Stages of the Mine Cycle

Clay soil mining activities can suddenly affect quality of life and the physical, mental, and social well-being of local communities. Indirect effects of clay soil mining on public health can include increased incidence of asthma, emphysema, and chronic bronchitis diseases.

The Clay soil mine provides effective poverty relief by providing jobs. Most of the impact on socio-economic environment may be positive associated with some adverse effects. During all phases, clay soil mining operation will require both skilled and unskilled employees; thus will provide temporary employment opportunities. Consequently, socio-



economic standards of near the local people will be increased and eventually it may lead to the economic growth at the local and regional level.

During preparation and operation phase, there will be employment opportunities to the population of the nearby villages directly concerned with the work associated with the clay soil mining operation. But, during the demolition phase, most of the workers at the clay soil mining become jobless and their income will be affected. But, clay soil mining may create jobs, roads, schools, and increase the demands of goods and services in and around the Kaw Pa Naw Village track and Malkaro Village track.

7.6 ENVIRONMENTAL IMPACT AND SIGNIFICANCE

Potential impacts are identified in terms of the each environmental issue, likely impacts during preparation, operation and decommission/closure phases.

Mine preparation also involves the preparation of facilities to process the clay soil, temporary camp and other related activities. The site will extract clay soil at Kaw Pa Naw village tract. So, the site will clear for land preparation of temporary camps, kitchen, water storage tanks, workshop, toilets and etc. So, the landscape will be changed from forest to the mining site resulting displacement of vegetation, change in visual quality and loss of key habitat types for the local flora and fauna.

The impacts are likely to be significant as duration and severity of impact are high with the irreversible nature of the recovery of the existing vegetation in the long term. Electrical power supplies are established from existing power generation facilities, for the preparation of on-site power generation facilities. The preparation phase of the project activities, their impacts and significance, the impact are shown in **Table 7.4**.

Item	Environmental Impacts	Project Activities		Signi Po Envii Ir	ficai otent conn npac	Impact Significance					
			Μ	D	Е	Р	SP				
Α	Preparation Pha during the prepa	se: This phase that corresponds to some e ration and renovation phase of the project	e vent, t.	pro	cess,	or a	activi	ty that occurs			
1.	Aesthetics	 Complete destruction of the resource through surface disturbance or excavation; Degradation or destruction due to topography or hydrological pattern change; Changes of soil movement (removal, erosion, sedimentation and etc.); and Clearing of vegetation, large excavations with heavy machines and vehicles. Construction of camp and buildings. 	5	2	1	5	40	Moderate			
2.	Air Quality	 Operation and maintenance of vehicles; Any on-site power generation 	4	2	1	4	32	Moderate			

 Table 7. 4 Analysis Potential Impacts during Preparation Phase



Item	Environmental Impacts	Project Activities	Significance of Potential Environmental Impacts				Impact Significance	
			Μ	D	E	Р	SP	
А	Preparation Pha during the prepa	se: This phase that corresponds to some e aration and renovation phase of the project	e vent, t.	pro	cess,	or a	activit	y that occurs
		 facilities; Site preparation and other related preparation activities; Land clearance and preparation activities; Topsoil loading, unloading and transportation; Building, temporary camp and access road construction. 						
3.	Odor	• Vehicles, heavy machineries and other related machineries	1	2	1	3	12	Very Low
4.	Noise and Vibration	 Vehicle engines; Power generation; Transportation of preparation materials and other preparation machineries and equipment; 	3	2	1	3	18	Low
5.	Soil Quality and Terrestrial Ecosystem	 Site cleaning, earth moving and excavation activities; Removal and compaction of soil, working activities; and Removal of topsoil layer. Land conversion due to the excavation works and removal of existing vegetation. 	5	2	1	4	32	Moderate
6.	Water Quality and Aquatic Ecosystem	 Removal of trees and other vegetation and leveling the site; Site preparation activities such as soil excavation and removal works during the rainy season Fuel spilling due to the fuel transportation, handling and storage and maintenance of vehicle; Sewage disposal (unsystematically) 	3	2	2	3	21	Low
7.	Waste Generation	 Solid Waste Movement of small amounts top soil; Include workshop scrap, household and other potential hazardous waste; and Liquid Waste Wastewater generated by workers Runoff water from project site Hazardous Waste Storage and handle hazardous materials (diesel oil). 	3	2	1	3	18	Low



Item	Environmental Impacts	Project Activities	Significance of Potential Environmental Impacts			Impact Significance		
	D († DI		Μ	D	E	Р	SP	
А	during the prepa	se: This phase that corresponds to some e ration and renovation phase of the project	vent, t.	pro	cess,	, or a	activi	ty that occurs
8.	Fire Hazards	 Fuel transportation, handling and storage Improper handling or maintenance of electrical equipment and other related preparation equipment Open burning on site or nearby 	3	2	2	3	21	Low
9.	Occupational Health and Safety	 Physical contact, spills, dust emission and noise pollution; Accidents and injuries to workers and local communities; Respiratory Hazardous Contagious diseases due to the migrant workers and increased workers. 	3	2	1	4	24	Low
10.	Community Health and Safety	 Respiratory hazards due to the dust emission from the excavation and transportation activities. Nuisance due to noise pollution Traffic accident Contagious diseases due to the migrant workers and increased workers. Fire hazards 	3	2	2	3	21	Low
11.	Social and economic standard	Works opportunities for local peopleCreate jobs, roads, schools	x	x	x	x	x	Positive Impact

During the operation stage, the topsoil and vegetation will be removed for extraction of clay soil. Moreover, the operation phase of the project includes site clearance, excavation and transportation for clay soil recover and etc. clay soil mining operations have the potential to impact of the quality of the air, noise, soil, surface water and groundwater and etc. on and around site. The operation phase of the project activities, their impacts and significance impact are seen in **Table 7.5**.

Item	Environmental Impacts	Project Activities	E S	Signi Po Cnvin Ir D	ficar otent onn npac E	nce o ial nenta :ts P	of al SP	Impact Significance
В	Operation Phase during the opera	e: This phase that corresponds to any ev tion (i.e. fully functioning) phase of the pro-	ent, j opose	proc d pr	ess, oject	or a t.	ctivit	y that occurs
1.	Aesthetics	• Complete destruction of the resource through surface disturbance or	5	4	1	5	50	High



Item	Environmental Impacts	Project Activities	Significance of Potential Environmental Impacts			of al	Impact Significance	
			Μ	D	E	Р	SP	
В	Operation Phase	e: This phase that corresponds to any ev	ent, j	proc	ess,	or a	ctivit	y that occurs
	during the opera	tion (i.e. fully functioning) phase of the pro	opose	a pr	ojec	t.		
		 Degradation or destruction, due to topography or hydrological pattern change; Changes or from soil movement (removal, erosion, sedimentation); and Visual impacts due to clearing of vegetation, large excavations, heavy metals and vehicles. 						
2.	Air Quality	 Using heavy machines and vehicles in excavation, transportation and stockpiling works. Top soil stripping, transportation and storage; Land clearing and Road grading; Fuel burning in heavy equipment and vehicles and generators; Haul roads and infrastructure; 	4	4	1	4	36	Moderate
3.	Odor	• Vehicles, heavy machineries and slurry pump machineries and other related machineries.	2	4	1	3	21	Low
4.	Noise and Vibration	 Using heavy machines and vehicles in excavation, transportation and stockpiling works. Other internal combustion engine powered equipment; and Heavy machines and vehicles maintenance 	3	4	1	4	32	Moderate
5.	Soil Quality and Terrestrial Ecosystem	 Top soil remove and kept for later re- use; Spills or leakages from machineries, vehicles and fuel storage area. Land conversion due to the excavation and stockpiling works and clearance the existing vegetation. 	4	4	1	5	45	High
6.	Water Quality and Aquatic Ecosystem	 Clearing land form for operational purpose; Discharged water from dewatering process Seepage from the storage of sedimentation pond; and Storage and use of hazardous materials (oil etc.) on site. Site runoff and storm water during the 	4	4	1	4	36	Moderate



Item	Environmental Impacts	Project Activities	Significance of Potential Environmental Impacts				of al	Impact Significance
			Μ	D	E	Р	SP	
R	Operation Phase	e: This phase that corresponds to any ev	ent,	proc	ess,	or a	ctivit	y that occurs
D	during the opera	tion (i.e. fully functioning) phase of the pro-	opose	d pr	ojec	t.		
		rainy season.						
7.	Waste Generation	 Solid Waste Domestic waste (food waste from temporary camp, some plastics and etc.); Regulated waste (batteries, tires and etc.) from the workshop; General waste (beings wood, unrecyclable plastics, etc.); Recyclable scrap metal; Liquid Waste Site runoff and storm water; Domestic wastewater generated by the increased number of workers; Hazardous Spilling fuel and oil from fuel handling and storage (diesel, lubricant etc.); 	3	4	2	3	27	Low
8.	Fire Hazards	 Storage of diesel and fuel oil with oil barrel Improper handling or maintenance of electrical equipment and other related preparation equipment Open burning on site or nearby 	3	4	2	3	27	Low
9.	Occupational Health and Safety	 Respiratory diseases, musculoskeletal problems occur in vehicle and equipment, Physical contact, spills, dust emission and noise pollution; Accidents and injuries to workers and local communities. 	3	4	1	4	32	Moderate
10.	Community Health and Safety	 Respiratory hazards due to the dust emission from the excavation and transportation activities. Nuisance due to noise pollution Traffic accident Contagious diseases due to the migrant workers and increased workers. Fire hazards 	3	4	2	3	27	Low
11.	Social and economic standard	Works opportunities for local peopleCreate jobs, roads, schools	x	x	x	x	x	Positive Impact



The decommissioning/ closure phase related activities include operation of earth moving equipment, decommissioning machineries and equipment and other related decommissioning/ closure activities. The decommissioning/ closure phase of the project activities, their impacts and significance impact are seen in **Table 7.6**.

Item	Environmental Impact	Project Activities		Sign F Env]	nifica Poter iron Impa	Impact Significance						
			Μ	D	Е	Р	SP					
С	Decommissioning/Closure Phase: This phase that corresponds to some event, process, or activity that occurs during the decommissioning phase (e.g. destruction, dismantling) of the project. Where needed, any existing hazardous materials used in decommissioning of these would be properly handled and disposed of in accordance with governing authority requirement.											
1.	Aesthetics	 Backfilling with topsoil Dust generation from excavation and backfilling works. Removal of infrastructure. 	4	1	1	4	24	Low				
2.	Air Quality	 Operation of heavy machines and vehicles for decommissioning works; Open burning on site or nearby.	4	1	1	4	24	Low				
3.	Odor	Vehicles and demolishing machineriesOpen burning on site or nearby	3	1	1	3	15	Low				
4.	Noise	 Using heavy machine, vehicle and demolishing machineries and generators. Other related demolition activities. 	4	1	1	4	24	Low				
5.	Soil Quality and Terrestrial Ecosystem	 Backfilling facilities and related other mine facilities; Re-grading, re-contouring and sedimentation pond cover. Removal of buildings and foundations. 	4	1	1	4	24	Low				
6.	Water Quality and Aquatic Ecosystem	 Backfilling facilities and related other mine facilities. Excavation or demolition during rainy periods; Leakage of oil and grease from vehicles and demolished machines. 	4	1	1	4	24	Low				
7.	Waste Generation	 Solid Waste Dismantling of project building and related infrastructures; Demolition debris such as wood, glass and etc. Domestic waste (food waste from temporary camp, some plastics and etc.); Liquid Waste Sanitary wastewater discharges Hazardous Waste 	4	1	1	4	24	Low				

Table 7.6 Analysis Potential Impacts during Decommissioning/Closure Phase



Item	Environmental Impact	Project Activities		Sigr F Env	nifica Poter iron Impa	ance ntial men acts	of tal	Impact Significance
			Μ	D	Е	Р	SP	
	Decommissionin	g/Closure Phase: This phase that correspon	nds (to so	me e	event	t, proc	ess, or activity
С	that occurs dur	ing the decommissioning phase (e.g. destr	uct	ion,	disn	nant	ling) (of the project.
Ũ	Where needed,	any existing hazardous materials used in	dec	omn	nissi	onin	g of tl	hese would be
	properly handle	and disposed of in accordance with govern	ning	g aut	hori	ty re	equire	ment.
		• Spilling fuel and oil from fuel handling						
		and storage (diesel, lubricant etc.);						
		• Storage of decommissioning materials						
0	T : H 1	• Improper handling or maintenance of		1	•	2	10	.
8.	Fire Hazards	electrical equipment and other related	3	1	2	3	18	Low
		decommissioning equipment						
		• Open burning on site or nearby						
	Occupational	• Physical contact, spills, dust emission						
9.	Health and	and noise pollution;	3	1	1	4	20	Low
	Safety	• Accidents and injuries to workers and						
		local communities;						
		• Respiratory hazards due to the dust						
		emission from the excavation and						
	Community	transportation activities.						
10.	Health and	• Nuisance due to noise pollution	3	1	2	3	18	Low
	Safety	• Traffic accident						
		• Contagious diseases due to the						
		migrant workers and increased						
		WORKERS.						
11	Social &	• works opportunities for local people						Positive
11.	economic	• Create jobs, roads, schools	х	Х	Х	Х	Х	Impact
	standard	 Permanent workers will be jobless 						

7.7 SUMMARY OF IMPACTS SIGNIFICANCE

Primary and secondary data were used to assess the environmental impacts. The potential environmental impacts were assessed in a comprehensive and scientific manner. The report provides a full picture of all potential environmental impacts associated with the proposed June Group Cement Industry Limited, and provide recommendations for suitable mitigation measures. The results after scoring evaluation of significant environmental impacts can be summarized in the **Figure 7.2**.





Figure 7.2 Summary of Impact Significance Level due to Project Activities

As per the result of analysis, low significant impact on environmental occurred during all phases such as preparation, operation and decommissioning/closure phases. Moreover, some project activities show moderate significance in the preparation and operation phases. However, some project activities show high significance during the operation phase. Therefore, mitigation measures should be performed especially for activities relating to preparation and operation phase. Some mitigation measures are described in the following and should be performed accordingly.

7.8 MITIGATING ADVERSE IMPACTS OF THE PROPOSED PROJECT

As identified earlier, potential adverse impacts of the proposed project may include air emissions, water, soil, waste disposal and public health and occupational health hazards. Proposed mitigation measures for the above-mentioned adverse impacts are discussed in the following paragraphs.

7.8.1 Mitigation Measures on Aesthetics

Preparation, Operation and Decommissioning/Closure Phase: Mitigation measures that need to be implemented in the mine site to reduce the aesthetics include:

- A rehabilitation plan for the mine site will reconvert to an environment close to its original state by replanting which will one way or other enhance the aesthetic value
- Minimize visual intrusion of clearing of vegetation;
- Do not clear any vegetation for maintenance activities;
- \circ $\,$ Provide thick green belt along the boundary of the mining area
- Contact Forest Department personnel and planned to do replanting at selected spots; and
- Where possible the design and the site preparation team should seek to retain the trees, reducing the visual impact as possible.



During the operational phase large area of land will be subject to clay soil mining operations that will clear most of the vegetation that will take a long time to rehabilitate and will likely lead to be a landscape scarring as the land will be incompatible with the surrounding landscape. June Cement Industry Ltd. should contact Forest Department, Mawlamyine Region for developing a rehabilitation plan to proceed at the closure phase.

7.8.2 Mitigation Measures of Air Quality

Preparation Phase: The following measures need to be implemented as mitigation measures that need to be implemented to reduce air quality:

- Restrict site preparation activities;
- Provide Personal Protective Equipment (PPE) such as dust masks where dust levels are high; and
- Maintain heavy machineries used for site preparation properly.
- Limit speed of speed vehicle travelling on internal roads
- Provide thick green belt along the boundary of the mining area

Operation Phase: The following measures need to be implemented as mitigation measures that need to be implemented to reduce air quality;

- Ensure control of fossil fuels (diesel, petrol) consumption on a daily basis;
- Control vehicle speed in the premises of the project site;
- Provide Personal Protective Equipment (PPE) such as dust masks where dust levels are high.
- Along the haul road, water spray system should be applied.

Decommissioning/Closure Phase: The following measures need to be implemented as mitigation measures that need to be implemented to reduce air quality:

- Schedule decommission activities;
- Perform regular inspection and maintenance of decommissioning vehicles and equipment; and
- Provide Personal Protective Equipment (PPE) such as dust masks where dust levels are high.

7.8.3 Mitigation Measures of Odor

Preparation, Operation and Decommissioning/Closure Phase: Mitigation measures that need to be implemented in the mine site to reduce the odor include:

- Ensure control of fossil fuels (diesel, petrol) consumption on a daily basis; and
- Provide Personal Protective Equipment (PPE) such as facemasks where odor levels are high.

7.8.4 Mitigation Measures of Noise and Vibration

Preparation, Operation and Decommissioning/ Closure Phase: Mitigation measures that need to be implemented in the mine site to reduce the noise and vibration include:

- Schedule noisy preparation activities;
- Perform regular inspection and maintenance of operation vehicles and equipment;
- Limit speed of vehicles on site;



- Restrict work times, modify equipment and appropriated site works, as part of the planning process for exploration sites to minimize noise disturbance.
- Reduce power operation-use only necessary size and power;
- Plan the noisy decommissioning works during the day;
- \circ Provide thick green belt along the boundary of the mining area;
- o Provide enclosures for particularly noisy equipment such as generator; and
- Provide PPE particularly hearing protection devices for those working in noisy areas.

7.8.5 Mitigation Measures of Soil Quality and Terrestrial Ecosystem

Preparation Phase: The following measures need to be implemented as mitigation measures that need to be implemented to reduce soil quality and terrestrial ecosystem:

- Reuse excavated materials for backfilling works;
- Clearly marked soil storage areas and restrict vehicle activity appropriately;
- Limit access by miners to adjacent habitats to reduce potential habitat degradation and interaction with wildlife;
- $\circ\,$ Minimized the disturbed area so as to keep the landform and topography not much altered; and
- Select appropriate low impact vegetation clearing methods.

Operation Phase: The following measures need to be implemented as mitigation measures that need to be implemented to reduce soil quality and terrestrial ecosystem:

- Do not extend the excavation area in the operation stage larger than that allowed by the MIC;
- $\circ\;$ Minimize the disturbed area so as to keep the landform and topography not much altered; and
- \circ Select appropriate low impact vegetation clearing methods.

Decommission/Closure Phase: The following measures need to be implemented as mitigation measures that need to be implemented to reduce soil quality and terrestrial ecosystem:

- Rehabilitate progressively of the site where operations allow;
- Conduct rehabilitation work completely;
- Stabilize of mine areas to prevent erosion, loss of seed bank and reduce feral animal infestation (e.g. seeding of soil stockpiles);
- Handle correctly for topsoil once stripped during the operation stage ;
- Restore vegetation (trees) for reuse as habitat in rehabilitating areas; and
- Optimize re-vegetation at decommissioning/closure stage when seasonal conditions are favorable for promoting seed survival.

7.8.6 Mitigation Measures of Water Quality and Aquatic Ecosystem

Preparation Phase: The following measures need to be implemented as mitigation measures that need to be implemented to reduce water quality and aquatic ecosystem:

- Contaminate water shall be reduced by avoiding earthwork in rainy season;
- All site water is either reused on-site or evaporated;
- Salvage topsoil for use in rehabilitation;
- Temporary toilet shall be provided for workers;
- Water quality monitoring shall be carried out regularly; and



• Repairs, maintenance works for motor vehicles shall not be carried out close to the stream.

Operation Phase: The following mitigation measures that need to be implemented to reduce water quality and aquatic ecosystem:

- Surface runoff from mine site must be collected and channeled to sedimentation pond;
- Control surface water run-off so as to direct away from pit walls;
- Dewatering shall control to ensure groundwater levels are maintained and discharged water must be directly channeled into sedimentation pond;
- Temporary toilet shall be provided for workers;

Decommissioning/Closure Phase: The following mitigation measures that need to be implemented to reduce water quality and aquatic ecosystem:

- Leak proof containers shall be used for storage and transportation of oil and grease, and keeping the impervious floors of oil and grease handling areas;
- Temporary toilet shall be provided for workers.

7.8.7 Mitigation Measures of Waste Generation

7.8.7.1 Mitigation Measures of Solid Waste

Preparation Phase: The following measures need to be implemented as mitigation measures that need to be implemented to reduce solid waste generation:

- Separate bins for food waste, metal and other waste to be located throughout the temporary camp and other facilities on site;
- Combustible items shall be burned in the designated area and non-combustible items should be land filled or recyclable and reusable;
- Appropriate signage shall be used to identify potential spill risk and other hazards; and
- Some types of the waste shall be land filled, some be reused and some be recycled.

Operation Phase: The following measures need to be implemented as mitigation measures that need to be implemented to reduce solid waste generation:

- Smoking shall be strictly prohibited from any site where fuel loading operations take place;
- All used petroleum products shall be collected in tank marked "Waste Oil" and disposed of under the direction of the mine coordinator;
- Empty petroleum containers shall be stored on site in a designated area and returned to the supplier on back hauls;
- Reuse waste rock to fill voids both on the surface;
- All hazardous materials (diesel oil) should be stored in a properly self-bunded tank as appropriate for the volume and nature of the materials.

Decommissioning/ Closure Phase: The following measures need to be implemented as mitigation measures that need to be implemented to reduce solid waste generation:

- The effective solid waste management system should be provided;
- Where recycling/reuse is not possible, the material should be taken to the municipal waste disposal site.



7.8.7.2 Liquid Waste

Preparation Phase: Temporary toilets shall be provided during the preparation phase.

Operation Phase: Mine workers will systematically manage for domestic liquid waste in clay soil mine site. The clay soil mining operation shall provide 2 toilet facilities for 12 employees, which are completely adequate in accordance with the basic HSE guidelines (2007) as shown in **Table 7.7**.

Number of workers or residences of each gender	Minimum number of water closet	Minimum number of sinks
1-15	1	1
16-35	2	2
36-55	3	3
56-80	4	4
81-110	5	5
111-150	6	6
>150	**	**

Table 7.7	Toilet	Facilities	for	Workers
------------------	--------	------------	-----	---------

Sources: HSE guidelines, 2007

Decommissioning/ Closure Phase: During the decommissioning phase, to reduce and control of liquid waste disposal, demolition activities shall be performed with the use of appropriate health and safety procedures in accordance with the regulatory requirements.

7.8.8 Mitigation Measures of Fire Hazards

Preparation and Decommissioning/Closure Phases

At the project site, about three extinguishers will be set up inside of the mine area for fire hazards. In case of fire emergency, the water for firefighting system can be obtained easily from one ground water storage tank. In addition, the project proponent has plans to provide training on firefighting for the employees by a professional or otherwise by sending to Fire Force Department for training courses. The proponent shall perform the following measures to prevent the fire hazards in the project site.

- Fire extinguishers and signage will be installed in the clay soil mine site.
- Regular inspection and testing of oil barrel storage area



- Employee instruction in regard to how to follow manufactures' directions and how to properly handle appliances.
- All emergency phone numbers should be identified, listed in the emergency preparedness plan and posted. Each department should display the diagram in a highly visible area.

7.8.9 Mitigation Measures of Occupational Health and Safety

Preparation and Decommissioning/Closure Phases

The representative of project proponent must provide a health and safety management plan for the preparation workers based on the EMP. For the safety of preparation workers, adequate safety measures, including the availability of first-aid facilities shall be implemented on the project site. Several employment opportunities will be created for preparation and demolition workers, though this will be short term. Adherence to the Occupational Health and Safety Rules and Regulations shall be adopted. Personal Protective Equipment (reflective clothing's, dust mask, safety shoes, hard hats, etc.), shall be provided as shown in **Table 7.8**. Site fencing and safety signage should be done in this phase as shown in **Table 7.9**.

Required Personal Protective Equipments	Functions of PPE	Part of the Body to be protected	Features and characteristics of PPE
Operation Phase			
Dust respirator, Safety Glasses, earplugs, gloves, reflective clothing and safety footwear	Protection from fine particles, bright light, nuisance, allergic, visibility of employees, falling objects and etc.	Head, Nose, mouth, Eye, Ear, Hand, Body and Foot	
Dust Goggles	Protection from dust, fine	Noise and mouth	20C
Dust Mask	mercury vapors	Noise and mouth	

Table 7. 8 Personal Protective Equipment (PPE) and Their Functions

Table 7. 9 Safety Signage and Their Descriptions during the Operation Phase

Description	Safety Signage
These signs indicate all visitors must report to the site office and obtain permission to proceed on to the site or any work area and safety equipment must be used at all time.	SITE SAFETY All visitors and drivers must report to allo office



Description	Safety Signage
These signs should be used to make people aware of nearby dangers such as diesel fuel.	

Operation Phase: Mitigation measures for health and safety impacts on employees of the clay soil mining operation are as follows;

- The representative of project proponent should have a health and safety management plan for the operation workers based on the EMP;
- For the safety of operation workers, adequate safety measures, including the availability of first-aid facilities shall be implemented on the project site.
- Training and licensing, vehicle operators should be provided in the safe operation of specialized vehicles such as backhoe.
- All workers shall be trained in emergency evacuation procedures and performed fire drills regularly.
- When working with mercury always use latex glove, they are cheap and provide good protection.

Personal Protective Equipment (safety glasses, eyewear, dust masks, safety gloves, earmuffs, etc.) and their functions as shown in **Table 7.7** shall be provided and machinery safety measures shall be posted at the mine site. Safety signage and their descriptions as shown in **Table 7.8** are to be provided and required machine cover will be installed as necessary.

7.8.10 Mitigation Measures of Community Health and Safety

Preparation and Decommissioning/Closure Phases

Mitigation measures that need to be implemented to reduce Community health and safety include:

- Controlling the pollutant emissions (Air, Noise and Water) within the NEQEG;
- o Safety and Prohibition signs must be used around the project site
- Providing health services and medicines to community clinic.
- Fencing should be surrounded around the project site
- \circ Provide thick green belt along the boundary of the mining area



CHAPTER 8

PUBLIC CONSULTATION AND INFORMATION DISCLOSURE

8.1 MEETING PURPOSE OF THE PUBLIC CONSULTATION AND INFORMATION DISCLOSURE

It is important to disclose the information about the project during the preparation of IEE report and the opinions of all stakeholders should be considered in implementation of the project. Consultation meeting should be held with people potentially to be affected by the project, administrative bodies, community-based organizations non-governmental organizations, and social organizations. Especially results of consultation with project affected people should be considered in evaluation of impacts, design of mitigation measures and monitoring plans. It is also needed to negotiate with related governmental organizations. Meeting Minutes on Public consultation and information disclosure of Initial Environmental Examination (IEE) of Clay soil Mining Operation, June Cement Industry Ltd. Public consultation power point and attended list attached in **Appendix 4 and Appendix 5**.

8.2 METHODOLOGY AND APPROACH

Information disclosure should be done by announcing the public consultation meeting about the proposed project and its potential impacts to the public and social organizations via local and national media, by posting on the website of the project proponent, by setting up signboards at the project area within an adequate time needed to inform the public. All feedbacks from public consultation meetings should be well addressed and considered in the formulation of EMP, environmental monitoring plan and CSR plan. In this case, the proponent has to inform and invite governmental officials and private companies near the project site and local community to attend the public consultation meeting.

Public consultation and information disclosure concerning with the Initial Environmental Examination (IEE) for the Projects proposed by June Cement Industry Limited was held on 15th June 2019 at Malkaro village, Kyaikmaraw Township, Mon State. It is aimed at disclosing the findings of environmental and social studies and the likely impacts upon them as well as mitigation and monitoring schemes to remediate the impacts caused by the project activities. The impacts were studied for all activities to be carried out in three phases: construction phase, operation phase and decommissioning phase. It is also aimed at receiving public recommendations, feedbacks upon the studies.



Table 8. 1 Meeting Records

E Guard Environmental Services Co., Ltd.	
Meeting Minutes	SERVICES
Subject: Public Consultation of Initial Environmental Examination for related projects in Cement Plant by June Cement Industry Ltd.	Date: 15/June/2019
Venue: Malkaro Monastery, Malkaro Village, Kyaikmaraw Township, Mon State.	Time : 10:00 AM-12:00 PM
Attendees:	
Local People - 106	
Parliament Member - 9	
Government - 22	
Media - 4	
NGO - 2	
Private Company – 9	
Total – 152	
Prepared by : U Lwin Thu Htun (Project Associate, E Gua	ard Environmental Services)
U Zwe Wint Phyoe (Project Assistant, E Gua	rd Environmental Services)

The Stakeholder meeting was held by the following Agenda:

- 1. Opening Ceremony
- 2. Opening speech by U Saw Aung Myint Khine (Minister of Kayin Ethnic Affair, Mon State)
- 3. Speech by U Khin Zaw Oo (Amyotha Hluttaw Representative, Mon State)
- 4. Presentation of project descriptions about related projects of June Cement Industry Ltd. by U Tin Oo (Director, June Cement Industry Ltd.)
- 5. Presentation about the Initial Environmental Examination and Procedure of IEE by U Tin Aung Moe (Director, E Guard Environmental Services)
- 6. Questions and Suggestions by Attendees
- 7. Closing Remarks by U Saw Kyaw Win Maung (Pyithu Hluttaw Representative, Mon State)



1. Opening Ceremony

2. Opening Speech by U Saw Aung Myint Khine (Minister of Kayin Ethnic Affair, Mon State)

Briefly, he said, all of you know that today's ceremony is public consultation for related four projects of cement industry. Public consulation is a must to do and all of you can ask the questions freely which you would like to know without hesitating.

3. Speech by U Khin Zaw Oo (Amyotha Hluttaw Representative, Mon State)

Firstly, he said that he didn't know the detail process of project as well as the villagers (local people). So, the villagers should ask the questions so as to know clearly about the project and he also prepared to ask. He hoped that the project client will be explained how they prepared and planned so that the project would not impact the public and environment. Apparently, June Company proposed MIC and bought the farmlands from nearby villages for the project since 2010. June Company will construct the road near the villages in order to ease project transportation. So the transportation becomes better than before and 700 people will be assigned when the June project is operating. Therefore, local people will get the opportunities. On the other hand, June Company is currently supporting and funding the local people from nearby villages (for example, education, healthcare, etc).

4. Presentation of project descriptions about related projects of June Cement Industry Ltd. by U Tin Oo (Director of June Cement Industry Ltd.)

Briefly, he presented about the related projects, facts and figures of the projects, existing projects' conditions and corporate social responsibility of June Cement Industry Ltd.

5. Presentation about the initial environmental examination and procedure of IEE by U Tin Aung Moe (Director of E Guard Environmental Services)

He firstly explained about the requirements of Initial Environmental Examination of the project which has been prepared in line with the EIA procedure of Environmental Conservation Department of the Ministry of Natural Resources and Environmental Conservation (MONREC), objectives of public consultation, related laws and regulation, background environmental condition of project site. He also presented the anticipated environmental and social impacts, mitigation measures, processes and schedule that will be mentioned and prepared in the IEE Report.

6. Questions and Suggestions by Attendees

Questions (1): U Khin Zaw Oo (Amyotha Hluttaw Representative, Mon State)

He said that how do you plan for jetty project especially the condition of fishermen who are working along the Attaran River before and after the project? Besides, how do you pay 2 percent of profit for CSR? Does 2 percent of CSR intend to Kyaikmaraw Township or Mon State?



Answers: U Tin Oo (Director, June Cement Industry Ltd.)

He said that when the jetty project is finished, we will only allow the ship transfer within the tonnage limits. Currently, the main operation relating to the project is sand transportation to the project site via barges that are sometimes cause some disturbances to fishing activities especially hook with fishing net. Therefore, care has to be taken to implement this operation by pointing out with small boat in front of the barges so as to solve this problem. We will also reduce the quantity of shipping time to the lowest during the fishing season. In the case of CSR, CSR should be for Kyaikmaraw Township because our project is located at Kyaikmaraw Township and this township is higher potential to affect by project activities. Thus, we will emphasize the CSR for Kyaikmaraw Township. We will have to plan and fund for CSR or community development. Even though we haven't planned of funded for CSR, we already supported education, healthcare and donated 5 million to Malkaro village and 10 million to Kawt Pa Naw village in the last two years. At present, we are building crematory that is imported from Myawaddy at Malkaro village and the crematory construction will be finished soon.

Questions (2): U Aung Tin Oo (Fishermen Head)

He asked, if fishermen are affected by ship transferring of June Cement Project, who will response that case and who is a respondent person? Nowadays, MCL Company cooperates with the member of fishing team by giving the number of contacted person, ship number. According to the construction of jetty and channel, fishermen who are working there will face the difficulties and lost their opportunities. So, how will you do if fisher men lost their opportunities?

Answers: U Tin Oo (Director, June Cement Industry. Ltd)

Obviously, there may be more or less confrontation between the barges and fisher men due to the project. We will give the contact number of responsible person or set up 24 hour hot line number to inform their grievance or complaint. As well, we will do an engagement with the affected fishermen and we will do best for not losing too much.

Questions (3): U Naing Shwe Win (Villager, Malkaro Village)

He wanted to know, which power plant is going to be used for cement industry? How many MW to be used for that industry? How many tonnages are produced per day? Where is the clay production area? Is it near the village and how far is it? Does it affect or impact to the nearest village? As for him, he isn't going to object or protest the June Company. MCL Company is currently using Attaran River for their ships' transportation. The river is almost damaged by MCL Company. Also, June Company will have to be used Attaran River for their ships' transportation in the future. So, the Attaran River is probably going to be more damaged. So, which company does we complaint about the impacts in the future? Which organization or department has responsibility to act upon the company that damages the environment seriously? Which organization or department monitors whether the project damages the public or not?



Answers: U Tin Oo (Director, June Cement Industry. Ltd)

Recently, we are intending to use coal-fired plant (15 MW of 2 quantities) for power supply. We've proposed coal-fired plant to get permission from the Union of Myanmar. We didn't get permission yet so that we haven't constructed coal-fired plant. We are going to use a very small amount of clay for cement production. Limestone percentage is 80-83%, clay percentage is 12% and clay soil percentage is 8% are needed for cement production. Fortunately, small amount of clay for cement production. Therefore, we will excavate a small amount of clay site. During the production of clay, we will manage carefully not to damage the environment and also the nearby villages. For barges transportation, the public can complaint by informing to the responsible person by calling 24 hours hot line number. For deciding whether the project damages or not, environment conservation department will be monitoring in the future. Nowadays, ECD has many modern instruments for environmental monitoring and the public can see the monitoring results on the website.

Questions (4): Daw Pa Pa (Local People, Malkaro Village)

She said that, we have lost our farmlands without getting any compensation. Therefore, we would like to get the compensation not only by giving cash but also providing an alternative land. So, do we lose ours without getting any compensation like that? Which opportunities can we get?

Answers: U Tin Oo (Director, June Cement Industry. Ltd)

He said that the purpose of today's ceremony is only noticing and requesting opinions from the local people for the related projects of June Cement Industry. Therefore, Land acquisition case is probably concerned with the land acquisition department so we can't decide it right now.

Questions (5): U Naing Htun Kyi (Villager, Malkaro Village)

He said that the main constituent of cement production is limestone. There is a historical cave near the production area of limestone. He only concern about this cave not to damage. How do you manage not to damage the cave during the limestone production period?

Answers: U Tin Oo (Director, June Cement Industry. Ltd)

He said that we are also Buddhism and we will focus on not to be damaged during the operation period. Foremost, we will operate the limestone production from the boundary of MCL Company that is far away from the historical cave. When we blast the limestone, we will use delay detonator which vibrates lesser than the others. Besides, we will do operation charily till the end.

Questions (6): U Khin Zaw Oo (Philanthropic Officer, Malkaro Village)

He said, it is sure that stones will be reached and affect the nearest farms that are not bought or owned by the June Company because of the blasting of limestone. What would you do if it



happened? And the public should know the detail of the projects and June Company should disclose its projects clearly.

Answers: U Tin Oo (Director, June Cement Industry Ltd.)

He said that the farms near the limestone site will not be damaged by the project because we will be using one type of mining method that starts to extract the inner portion of mineral, we would not blast or explode the outer portion. Even if there is damage to the farms, we would buy the farms with reasonable price or give compensation. And if you want to know the details of project, you can list the facts what you want to know and you can ask directly the company office.

Questions (7): U Htain Win (Villager, Mei Ka Yo Village)

He asked about the location of clay production. The villagers are now facing difficulties about transportation due to the construction of factory. The result of air and water monitoring results need to display as Myanmar language so as to read easily by local people. He desired that local people from nearby villages should include in the Grievance Mechanism. And what kind of coal will be used for clean-coal system?

Answers: U Tin Oo (Director, June Cement Industry. Ltd)

We will start using clay from the plot No. 406 and we will manage not to impact the others as much as we can. For announcing the results of air and water monitoring results, we will display it with Myanmar Language by using LED board. Subsequently, we will organize the Grievance Mechanism with public, stakeholders, responsible person, mayors and philanthropic people. In the case of coal, there are four grades of coal and we will be using third-grade coal that is imported from Australian and Indonesia.



















Figure 8. 1 Public Consultation of Initial Environmental Examination for related projects in Cement Plant by June Cement Industry Ltd.



CHAPTER 9

INSTITUTIONAL REQUIREMENT AND ENVIRONMENTAL MANAGEMENT PLAN

This Environmental Management Plan (EMP) is an action plan that addresses the potential impacts and risks identified by the environmental impact assessment. Environmental Management Plan (EMP) prepared as an environmental management framework for clay soil mining operation project. The environmental management practices, procedures and responsibilities are defined here into getting full compliance with the existing environmental policy, laws, rules and regulations of the Republic of the Union of Myanmar. This objective is to be achieved through preparation of an Environmental Management Plan (EMP) that addresses the potential impacts and risks identified by the environmental assessment. Environmental Management plan (EMP) in the project cycle must performed six main stages such as project concept, pre-feasibility, feasibility, design and engineering, implementation and monitoring and evaluation and it has a role to play throughout each phase (see **Figure 9.1**).



Figure 9. 1 Environmental Management in Project Cycle

Source: Adapted from Asian Development Bank, 1993



Objectives

The objectives of EMP are as follows;

- Identify the possible environmental impacts of the proposed activities;
- Develop measures to minimize, mitigate and manage these impacts and
- Estimate the budget of EMP for each phase

9.1 RESPONSIBLE PERSON FOR EMP

Implementation of the EMP management practices and procedures is the responsibility of all site personnel: however, key personnel (Site Manager, HSE Coordinator, Ministry of Natural Resources and Environmental Conservation (MONREC), Site Leadership Team, Workers and the site Environmental team members) are responsible for communicating environmental matters and ensuring management practices and procedures are being implemented are as follow:

No.	Position	Department	Responsibilities
1.	Managing Director		 Implementation of the EMP Supervision and monitoring of the implementation of EMP
2.	HSE Coordinator	June Cement Industry Ltd.	 Oversight of overall implementation of the project environmental activities Supervision, monitoring and performing of Health and safety for workers and local people
3.	Site Manager		 Implementation of the EMP Supervision, monitoring and reporting of EMP implementation
4.	Members of MONREC	MONREC	 Monitoring and inspection of projects to determine compliance with all environmental and social requirements The Ministry may impose penalties and/ or require the project proponent to undertake corrective action Where, the Ministry views that the project is not in compliance, it shall Promptly inform the project proponent Indicate specific non-compliances of the project environmental and social requirements; and Specify a time period for the project proponent to bring the project into compliance In the event of noncompliance In form the project proponent indicating the specific non-compliances with environmental and social requirements; Where a project is not in compliance or not likely to comply with its environmental and social requirements, take enforcement action including: Suspension of project operation; and Employing third parties to correct non-compliance

1 able 9. 1 Kesponsible Person for EMP	Table 9.	1	Responsible Per	son for EMP
--	----------	---	------------------------	-------------

June Cement Industry Ltd. must manage the development of the proposed project by implementing the EMP which is composed of eight parts as follows;



- i) Environmental Management Plan
- ii) Environmental Monitoring Plan
- iii) Occupational Health and Safety Plan
- iv) Community Health and Safety Plan
- v) Emergency Preparedness and Response Plan
- vi) Topsoil Management Plan
- vii) Mine Closure Plan and
- viii) Corporate Social Responsible Plan

June Cement Industry Limited is a responsible party to this Environmental Management plan of the clay soil mining operation. The June Cement Industry Limited will review and update this plan at least once annually. Revisions will be made as needed throughout the year. Any suggestions, comments and questions should be directed to June Cement Industry Limited.

9.2 ENVIRONMENTAL MANAGEMENT PLAN

The Environmental Management Plan (EMP) prepared for the proposed project covers the anticipated impacts of the said project, mitigation measures, management and monitoring plans during each of the phases:

- Preparation Phase
- ✤ Operation Phase and
- Decommissioning/Closure Phase

The detailed EMP based on the project activities is described in Table 9.2.

CONNE CEMENT MOUSTRY LTD.

Preparation Phase: These phases will include site preparation, construction of temporary camps, workshop, water storage tank, toilets and other related activities.

Item	Potential Environmental	Location	Proposed Mitigation Measures	Mitigation Cost (MMK)	Residual Impact	Responsible Party
	Impact					
А.	Preparation Phase	: This phase tha	t corresponds to some event, process, or activity that occurs during (the preparation phase	of the projec	Ľ.
	Aesthetics	All Preparation Site	 A rehabilitation plan for the mine site will be ploughed back to an environment that will enhance the aesthetic value; Minimize visual intrusion due to clearing of vegetation; Provide thick green belt around the boundary of project site; Do not clear any vegetation for maintenance activities; and Contact Forest Department personnel and plan to do replanting at selected spots. 	Already included in cost estimation for EMP	Low	June Cement Industry Limited
6	Air Pollution	All preparation Site	 Minimize land disturbance; Limit speed of vehicles travelling on internal roads; Restrict site preparation activities; Provide Personal Protective Equipment (PPE) such as masks where dust levels are high; Provide thick green belt around the boundary of project site; Maintain heavy machineries used for site preparation properly; and Along the haul road, water spray system should be applied. 	Already included in cost estimation for EMP	Low	June Cement Industry Limited
r;	Noise and Vibration	All Preparation Site	 Schedule noisy preparation activities; Perform regular inspection and maintenance of operation vehicles and equipment; Reduce power operation-use only necessary size and power; Provide thick green belt around the boundary of project site; Provide enclosures for particularly noisy equipment such as generator; and 	Already included in cost estimation for EMP	Low	June Cement Industry Limited

Table 9.2 Environmental Management Plan for Preparation Phase

Initial Environmental Examination

Page 92

MENT INDUSTRY LTD.
NE

	Potential				: ;	:
Item	Environmental Impact	Location	Proposed Mitigation Measures	Mitigation Cost (MMK)	Kesidual Impact	Kesponsible Party
А.	Preparation Phase	: This phase tha	t corresponds to some event, process, or activity that occurs during t	the preparation phase	of the projec	ť
			 Provide PPE particularly hearing protection devices for those working in noisy areas. 			
4.	Odor	In Mine Site	 Ensure control of fossil fuels (diesel) consumption on a daily basis; and Provide Personal Protective Equipment (PPE) such as face masks where odor levels are high. 	Already included in cost estimation for EMP	Very Low	June Cement Industry Limited
ы.	Soil Quality and Terrestrial Ecosystem	All Preparation Site	 Reuse excavated materials for backfilling works; Clearly marked soil storage areas and restrict vehicle activity appropriately; Limit access by miners to adjacent habitats to reduce potential habitat degradation and interaction with wildlife Minimized the disturbed area so as to keep the landform and topography not much altered; and Select appropriate low impact vegetation clearing methods. 	Already included in cost estimation for EMP	Low	June Cement Industry Limited
ن.	Water Quality and Aquatic Ecosystem	All Preparation Site	 Reduce contaminate water by avoiding earthwork in rainy season; Salvage topsoil for use in rehabilitation; Provide temporary toilets for workers; Monitor water quality monitoring regularly; and Conduct repairs and maintenance works for motor vehicles not close to the streams. Discharged water from dewatering process must be directly channeled into sedimentation pond. Surface runoff from mine site must be collected and channeled to sedimentation pond. 	Already included in cost estimation for EMP	Low	June Cement Industry Limited
7.	Waste Disposal	All Preparation	Solid Waste • Locate separate bins for food waste, metal and other waste	Already included in cost estimation for	Low	June Cement Industry

Page 93

Initial Environmental Examination

Potential Environmental Impact	Location	Proposed Mitigation Measures	Mitigation Cost (MMK)	Residual Impact	Responsible Party
Preparation Phase	:: This phase the	at corresponds to some event, process, or activity that occurs during t	he preparation phase	of the projec	÷
	Site	 throughout the temporary camp and other facilities on site; Burn combustible materials in the designated areas and land fill Burn combustible materials in the designated areas and land fill recycle or reuse for non-combustible items; and Some types of waste should be reused and recycled. Liquid Waste Provide temporary toilets during the preparation phase. Hazardous Waste Use appropriate signage to identify potential spill risk and other hazards. 	EMP		Limited
Fire Hazards	All Preparation Site	 Provide firefighting training and regular fire drills for all workers; and Provide sufficient fire extinguishing devices. 	Already included in cost estimation for EMP	Low	OHSE Officer &June Cement Industry Limited
Occupational Health & Safety	All Preparation Site	 Develop health and safety management plan during the preparation phase by the representative of the project. Proponent based on EMP; Provide Personal Protective Equipment such as safety gloves, helmets, goggles, earmuffs and etc. during preparation phase; and Provide first-aid facilities and adequate safety measures, for the safety of staff, on the project site. Provide precaution signs around the project site 	Already included in cost estimation for EMP	Low	OHSE Officer &June Cement Industry Limited
Community Health & Safety	All Preparation Site	 Controlling the pollutant emissions within the NEQEG. Providing health services and medicines to community clinic Implementing good public relations among project proponent 	Already included in cost estimation for	Low	OHSE Officer &June
E					

JYL .					
TR					
SU					
Ð					
E					
E					
EW					
0					
2					
5					
5					

Responsible Party	ţ.	Cement Industry Limited	June Cement Industry Limited
Residual Impact	of the projec		Positive impact
Mitigation Cost (MMK)	the preparation phase	EMP	ı
Proposed Mitigation Measures	at corresponds to some event, process, or activity that occurs during	and local people • Precaution signs must be located around the project site • Fencing should be surrounded around the project site	 Create job opportunities for temporary employments.
Location	: This phase th		All Preparation Site
Potential Environmental Impact	Preparation Phase		Social & economic standards
Item	Α.		11.

Operation Phase: During the operation phase the following will be conducted:

- Operation and maintenance of vehicles, heavy equipment and generators;
 - Extraction, Excavations, transportation of materials; and
 - Stockpile, etc.

Phase
peration
ō
for
Plar
Management
Environmental
C
6
Table

Responsible Party	tioning) of the	June Cement Industry Limited
Residual Impact	e. Fully func	
Estimated of Cost of Proposed Measures (USD)	he operation phase (i.	Already included in cost estimation for EMP
Mitigation Measures	at corresponds to any event, process, or activity that occurs during	 Do not clear any vegetation for maintenance activities; Minimize visual intrusion of clearing of vegetation;
Location	This phase th	In Mine Site
Potential Environmental Impact	Operation Phase: proposed project.	Aesthetics
Item	B.	1.

Initial Environmental Examination

2
2
R
ST
8
2
T I

5
0
2
_

Item	Potential Environmental Impact	Location	Mitigation Measures	Estimated of Cost of Proposed Measures (USD)	Residual Impact	Responsible Party
B.	Operation Phase: proposed project.	This phase that	t corresponds to any event, process, or activity that occurs during t	he operation phase (i.e	e. Fully funct	ioning) of the
6	Air Pollution	In Mine Site	 Minimize land disturbance; Prohibit uncontrolled burning of domestic waste on site; Follow specific access routes and use designated turning areas by vehicles; Restrict land disturbance to that necessary of current operations; Maintain mining equipment to maximize equipment, fuel efficiency; Ensure control of fossil fuels (diesel, petrol) consumption on a daily basis; Control vehicle speed in the premises of the project site; Provide Personal Protective Equipment (PPE) such as dust masks where dust levels are high. Around the stockpile and along the haul road, water spray system should be applied. 	Already included in cost estimation for EMP	Low	HSE Coordinator and June Cement Industry Limited
r,	Noise and Vibration	In Mine Site	 Perform regular inspection and maintenance of operation vehicles and equipment; Limit speed of vehicles on site; Reduce power operation-use only necessary size and power; Provide enclosures for particularly noisy equipment such as generator; Provide PPE particularly hearing protection devices for those working in noisy areas; and Restrict work times, modify equipment and appropriated site works, as part of the planning process for exploration sites to minimize noise disturbance. 	Already included in cost estimation for EMP	Low	HSE Coordinator and June Cement Industry Limited
4.	Odor	In Mine Site	 Ensure control of fossil fuels (diesel, petrol) consumption on a daily basis; Provide Personal Protective Equipment (PPE) such as face masks where odor levels are high. 	Already included in cost estimation for EMP	Low	HSE Coordinator and June Cement Industry Limited

Initial Environmental Examination

Item	Potential Environmental Impact	Location	Mitigation Measures	Estimated of Cost of Proposed Measures (USD)	Residual Impact	Responsible Party
B.	Operation Phase: proposed project.	This phase tha	t corresponds to any event, process, or activity that occurs during the	ne operation phase (i.e	e. Fully func	tioning) of the
У	Soil Quality and Terrestrial Ecosystem	In Mine Site	 O not extend the excavation area in the operation stage larger than permitted area. Minimize the disturbed area so as to keep the landform and topography not much altered; and Select appropriate low impact vegetation clearing methods 	Already included in cost estimation for EMP	Low	HSE Coordinator and June Cement Industry Limited
ó.	Water Quality and Aquatic Ecosystem	In Mine Site	 Control surface water run-off such that it is directed away from pit walls; Store storm water in appropriate facilities; Control dewatering to ensure groundwater levels are maintained; Provide temporary toilets for workers. 	Already included in cost estimation for EMP	Low	HSE Coordinator and June Cement Industry Limited.
۲- ۲-	Waste Disposal	In Mine Site	 Solid Waste Locate separate bins for food waste, metal and other waste throughout the temporary camp and other facilities on site; Burn combustible materials in the designated areas and land fill or recycle or reuse for non-combustible items; Use appropriate signage to identify potential spill risk and other hazards; and Landfill some types of waste, some reused and some recycled. Liquid Waste Provide sufficient toilets during the operation phase; Dewatering will collect to sedimentation pond and then will be used for plantation and dust suppression. Hazardous Waste Collect all used petroleum products in tanks marked "Waste Oil" and disposed of under the direction of the mine coordinator; Empty petroleum containers will be stored on site in a designated area and returned to the supplier on back hauls; 	Already included in cost estimation for EMP	Low	HSE Coordinator and June Cement Industry Limited

CONTRACTIONS COMENT INDUSTRY LTD.

Initial Environmental Examination

INT INDUSTRY LTD.
CEME
JUNE

Item	Potential Environmental Impact	Location	Mitigation Measures	Estimated of Cost of Proposed Measures (USD)	Residual Impact	Responsible Party
B.	Operation Phase proposed project.	: This phase tha	t corresponds to any event, process, or activity that occurs during the	he operation phase (i.e	e. Fully funct	ioning) of the
			 Store all hazardous materials (diesel oil) in a properly self- bunded tank as appropriate for the volume and nature of the materials. 			
×	Fire Hazards	In Mine Site	 Prohibit smoking at any site where fuel loading operations take place; Provide firefighting training and regular fire drills for all workers Provide sufficient fire extinguishers 	Already included in cost estimation for EMP	Low	HSE Coordinator and June Cement Industry Limited
<u>م</u>	Occupational Health &Safety problems	In Mine Site	 Implement health and safety management plan by the representative of the project proponent for the operation workers based on the EMP; Implement adequate safety measures, including the availability of first-aid facilities on the project site for the operation workers. Conduct training and licensing for vehicle operators of specialized vehicles such as backhoe, aiming at safe operation on site. Train all workers for emergency evacuation procedures and perform fire drills regularly. Provide Personal Protective Equipment (reflective clothing's, dust mask, safety shoes, hard hats, etc.), Provide precaution signs around the project site. 	Already included in cost estimation for EMP	Low	HSE Coordinator and June Cement Industry Limited
10.	Community Health & Safety	In Mine Site	 Controlling the pollutant emissions within the NEQEG Providing health services and medicines to community clinic Implementing good public relations among project proponent and local people Fencing should be surrounded around the project site 	Already included in cost estimation for EMP	Low	OHSE Officer &June Cement Industry Limited
11.	Social &	In the Local	 Work opportunities for employment. 	1	Positive	June Cement

Page 98

Initial Environmental Examination

							UNE CEMENT INDUSTRY LTD.
	Item	Potential Environmental Impact	Location	Mitigation Measures	Estimated of Cost of Proposed Measures (USD)	Residual Impact	Responsible Party
	B.	Operation Phase: proposed project.	This phase that co	orresponds to any event, process, or activity that occurs during t	he operation phase (i.e	e. Fully func	tioning) of the
		economic standards	area			impact	Industry Limited
Decom materia	nmissi (als use	oning Phase: Th d in decommissic	is phase related ming of these we Table	activities would require the use of the demolishing equipould be properly handled and disposed of in accordance wind 9.4 Environmental Management Plan for Decommissi	ment. Where needed (th governing author on Phase	d, any exist rity requirer	ting hazardous nents.
	Item	Potential Environmental Impact	Location	Mitigation Measures	Estimated of Cost of Proposed Measures (USD)	Residual Impact	Responsible Party
	С	Decommission Ph dismantling) of the of in accordance w	ase: This phase t e project. Where n ith local governing	hat corresponds to any event, process, or activity that occurs eeded, any existing hazardous materials used in decommissioning t authority requirements.	during the decomm of these would be prop	uissioning (e. perly handled	g. destruction, 1 and disposed
		Aesthetics	In Mine Site	 A rehabilitation plan for the mine site will brought back to its initial state by planting trees to enhance aesthetic value.; Contact Forest Department personnel and will plan to do replanting at selected spots 	Already included in cost estimation for EMP	Low	June Cement Industry Limited
	2.	Air Quality	All decommissionin areas	 Schedule decommission activities; Perform regular inspection and maintenance of decommissioning vehicles and equipment; and Provide Personal Protective Equipment (PPE) such as dust masks where dust levels are high. 	Already included in cost estimation for EMP	Low	June Cement Industry Limited
	З.	Noise and Vibration	All decommissionin areas	 Plan the noisy decommissioning works during the day. Use the demolition machineries, generators and other equipment in good condition and insulated; and Provide PPE particularly hearing protection devices for those working in noisy areas. 	Already included in cost estimation for EMP	Low	June Cement Industry Limited
	4.	Odor	All Demolishi	1g o Ensure control of fossil fuels (diesel, petrol) consumption	Already included in	Low	June Cement

Initial Environmental Examination

Item	Potential Environmental Impact	Location	Mitigation Measures	Estimated of Cost of Proposed Measures (USD)	Residual Impact	Responsible Party
С	Decommission Pha dismantling) of the of in accordance w	ase: This phase that project. Where neede ith local governing au	corresponds to any event, process, or activity that occurs d, any existing hazardous materials used in decommissioning (thority requirements.	during the decommination of these would be prop	uissioning (e.g perly handled	, destruction, l and disposed
		Site	on a daily basis; o Provide Personal Protective Equipment (PPE) such as face masks.	cost estimation for EMP		Industry Limited
ý	Soil Quality and Terrestrial Ecosystem	All decommissioning areas	 Rehabilitate progressively of the site where operations allow; Conduct rehabilitation work completely; Stabilize of mine areas to prevent erosion, loss of seed bank and reduce feral animal infestation (e.g. seeding of soil stockpiles); Handle correctly for topsoil once stripped during the operation stage; Restore vegetation (trees) for reuse as habitat in rehabilitating areas; and Optimize re-vegetation at decommissioning/closure stage when seaonal conditions are favorable for promoting seed survival 	Already included in cost estimation for EMP	Low	June Cement Industry Limited
6.	Water Quality and Aquatic Ecosystem	All decommissioning areas	 Reduce the excavation and backfilling works during the rainy season. Use leak proof containers for storage and transportation of oil and grease, and keeping the impervious floors of oil and grease handling areas. 	Already included in cost estimation for EMP	Low	June Cement Industry Limited
٦.	Waste Disposal	All decommissioning areas	 Solid Waste Provide effective solid waste management system; Take waste to a waste disposal site, where recycling/reuse is not possible. Liquid Waste Provide temporary toilets for workers 	Already included in cost estimation for EMP	Low	June Cement Industry Limited

Initial Environmental Examination

E.
×
R
S
2
N
-
Z
E.
Ē
0
Lau
-

Item	Potential Environmental Impact	Location	Mitigation Measures	Estimated of Cost of Proposed Measures (USD)	Residual Impact	Responsible Party
C	Decommission Pha dismantling) of the of in accordance w	ase: This phase that project. Where neede ith local governing aut	corresponds to any event, process, or activity that occurs d, any existing hazardous materials used in decommissioning (hority requirements.	during the decommination of these would be prop	issioning (e.; perly handled	g. destruction, I and disposed
			 Use appropriate health and safety procedures Hazardous Waste Empty petroleum containers will returned to the supplier 			
			on back hauls.			
%	Fire Hazards	All decommissioning areas	o Provide appropriate fire extinguishers.	Already included in cost estimation for EMP	Low	June Cement Industry Limited
9.	Occupational Health & Safety problem	All decommissioning areas	 O Use Personal Protective Equipment such as dust masks safety shoes, helmets, etc. O Place site fencing and safety signboards. O Provide adequate toilet facilities. 	Already included in cost estimation for EMP	Low	HSE Officer and June Cement Industry Limited
10.	Community Health & Safety		 Controlling the pollutant emissions within the NEQEG. Providing health services and medicines to community clinic Fencing should be surrounded around the project site 	Already included in cost estimation for EMP	Low	OHSE Officer &June Cement Industry Limited
11	Rehabilitation	All Mine Site	 Contact Forest Department personnel and plan for replanting the mine site. Collection of indigenous tree seeds Establish a tree nursery Raise tree seedlings with indigenous species Plan for replanting the mine site. Organize labor force Site Preparation Planting out 	Already included in cost estimation for EMP	Positive Impact	HSE Officer and June Cement Industry Limited

Initial Environmental Examination



Responsible Party	g. destruction, d and disposed	June Cement Industry Limited
Residual Impact	issioning (e. perly handle	Positive Impact
Estimated of Cost of Proposed Measures (USD)	during the decomm of these would be pro	-
Mitigation Measures	corresponds to any event, process, or activity that occurs ed, any existing hazardous materials used in decommissioning thority requirements.	• Work opportunities for temporary employment.
Location	ase: This phase that e project. Where neede rith local governing au	All decommissioning areas
Potential Environmental Impact	Decommission Phidismantling) of the of in accordance w	Social & economic standards
Item	С	12.

9.3 ENVIRONMENTAL MONITORING PLAN

Environmental Monitoring Plan based on the environmental concern is mentioned in Table 9.5.

	ng Estimated Monitoring Cost (MMK) responsibility		ite Already included in June Cement EMP Industry Limited	Already included in cost estimation for EMP June Cement	Already included in June Cement cost estimation for Industry Limited EMP	ite Already included in June Cement EMP Industry Limited		ite Already included in HSE Officer, June cost estimation for Cement Industry EMP Limited	Already included in cost estimation for EMP HSE Officer, June Cement Industry
Monitorin	Points		In Mine Sit	In Mine Sit	Surface Wat	In Mine Sit		In Mine Sit	In Mine Sit
	Monitoring Frequency	Phase	Once a year	Once a year	Once a year	Once a year		Monthly	Phase
Monitoring	Guidelines and Standards	Preparation	NEQ Guideline	NEQ Guideline	NEQ Guideline	FAO Standards	1		Operation
	Monitoring Parameters		Monitoring of the basic parameters: Temperature, Relative Humidity, Wind speed and direction, O ₃ , NO ₂ , SO ₂ , PM ₁₀ and PM _{2.5}	Equivalent noise level dB(A)	Monitoring of the basic parameters: pH, Total Suspended Solids, Biochemical Oxygen Demand (BOD), Chemical Oxygen Demand (COD), Oil and Grease, Total Coliform Bacteria, Total Nitrogen and Total Phosphorus	Monitoring of the basic parameters: Chromium, Cadmium (Cd), Lead (Pb), Arsenic (As), Iron (Fe), Zinc (Zn), Copper (Cu) and Mercury (Hg)	Visual inspection of sites		
	Environmental Components		Air Quality	Noise Level	Water Quality	Soil Quality	Solid and Liquid Waste	Management	Management
	Item	A	1.	ci		4.	5.		B

Table 9.5 Environmental Monitoring Plan

Page 103

Initial Environmental Examination

Monitoring responsibility	HSE Coordinator, Third-Party.	HSE Coordinator, June Cement Industry Limited	HSE Coordinator, June Cement Industry Limited HSE Coordinator, June Cement Industry Limited	HSE Coordinator, June Cement Industry Limited	HSE Coordinator, June Cement Industry Limited	HSE Officer, June Cement Industry Limited	HSE Coordinator, June Cement Industry Limited
Estimated Monitoring Cost (MMK)	Already included in cost estimation for EMP	Already included in cost estimation for EMP	Already included in cost estimation for EMP	Already included in cost estimation for EMP	Already included in cost estimation for EMP	Already included in cost estimation for EMP	Already included in cost estimation for EMP
Monitoring Points	In Mine Site	In Mine Site	Surface Water	In Mine Site	Temporary camp and kitchen	Diesel storage area	In Mine Site
Monitoring Frequency	Once a year	Once a year	Once a year	Once a year	Monthly	Monthly	Yearly
Monitoring Guidelines and Standards	NEQ Guideline	NEQ Guideline	NEQ Guideline	FAO Standards	1	1	EIA procedures (2015) and relevant procedures
Monitoring Parameters	Monitoring of the basic parameters: Temperature, Relative Humidity, CO_2 , NO_2 , SO_2 , PM_{10} and $PM_{2.5}$	Equivalent noise level dB(A)	Monitoring of the basic parameters: pH, Total Suspended Solids, Biochemical Oxygen Demand (BOD), Chemical Oxygen Demand (COD), Oil and Grease, Total Coliform Bacteria, Total Nitrogen and Total Phosphorus	Monitoring of the basic parameters: Chromium, Cadmium (Cd), Lead (Pb), Arsenic (As), Iron (Fe), Zinc (Zn), Copper (Cu) and Mercury (Hg)	Visual inspection	Visual inspection and regular check	Location: At Mine Area and Residential Areas (Assess the compliance with this EMP, other existing environmental policy, law, rules and instructions)
Environmental Components	Air Quality	Noise Level	Water Quality	Soil Quality	Solid and Liquid Waste Management	Fire Hazard	Environmental Auditing
Item	5		4.	5.	6.	7.	×.

Initial Environmental Examination

Monitoring of the Monitoring of the Temperature, Relative and direction, O ₃ , NO ₂ ,	Parameters	Guidelines				
itoring of the pperature, Relative direction, O ₃ , NO ₂ ,		and Standards	Monitoring Frequency	Monitoring Points	Monitoring Cost (MMK)	Monitoring responsibility
itoring of the perature, Relative direction, O ₃ , NO ₂ ,	I	Jecommissionir	ng Phase			
	basic parameters: Humidity, Wind speed , SO_2 , PM_{10} and $PM_{2.5}$	NEQ Guideline	Once a year	In Mine Site	Already included in cost estimation for EMP	June Cement Industry Limited
ivalent noise level c	dB (A)	NEQ Guideline	Once a year	In Mine Site	Already included in cost estimation for EMP	June Cement Industry Limited
nitoring of the basic pended Solids, nand (BOD), Cher DD), Oil and Gr teria, Total Nitrogei	c parameters: pH, Total Biochemical Oxygen mical Oxygen Demand rease, Total Coliform n and Total Phosphorus	NEQ Guideline	Once a year	Surface water	Already included in cost estimation for EMP	June Cement Industry Limited
ittoring of the omium, Cadmium (), Iron (Fe), Zinc (cury (Hg)	b basic parameters: (Cd), Lead (Pb), Arsenic (Zn), Copper (Cu) and	FAO Standards	Once a year	In Mine Site	Already included in cost estimation for EMP	June Cement Industry Limited
ual inspection			Monthly	In Mine Site	Already included in cost estimation for EMP	June Cement Industry Limited

In order to assess the effectiveness of EMP supervision and monitoring need to be undertaken. Monitoring results, including the development and implementation of corrective action should be documented.



9.4 COST ESTIMATION FOR EMP

The following **Table 9.6** shows the expenditures for the implementation of Environmental Management Plan and it can change according to the situation. We, June Cement Industry Limited also commit that we will add required funds for the implementation of Environmental Management Plan including monitoring plan if this following cost estimation is not enough at the time of real practices through the project lifespan.

No.	Item	Unit	Quantity	Unit Cost	Cost (USD)			
				(USD)				
(A) Mi	tigation Measures							
1.	Dust Control (water spraying)	Day	120	80	9,600			
2.	Dust, Noise and Aesthetics control	Year		Lump sum	3,000			
	(provide thick green belt zone and							
	replanting)							
3.	Noise control measure	Year	1	3,000	3,000			
4.	Mine Rehabilitation and reclamation	Year	1		5,000			
5.	Fire Extinguishers	Nos.			300			
6.	PPE and First Aid Kits			Lump sum	1,000			
7.	Medical Check-up and health care	Year		1	3,000			
	facilities							
8.	Solid and Liquid waste disposal	Month	12	20	2,400			
9.	Dewatering control (sedimentation			Lump sum	3,000			
	pond)							
	Subtotal				414,700			
(B) Mo	nitoring		·					
1.	Air Quality	Year	1	600	600			
2.	Noise Quality	Year	1	100	100			
3.	Water Quality	Year	2	400	800			
4.	Socio-economic Condition	Year	1	250	250			
	Subtotal				1,750			
(C) Env	vironmental Management and Capacity Bui	lding						
1.	HSE Coordinator	Month	6	200	9,600			
2.	HSE Assistant	Month	6	150	4,800			
3.	Training	1*Year	1	800	800			
	Subtotal				14,400			
	Contingency				3,000			
	Total							

Table 9.6 Cost Estimation for EMP Implementation



9.5 OCCUPATIONAL HEALTH AND SAFETY PLAN

The project proponent should appoint one Health, Safety and Environment (HSE) Coordinator for Health, Safety and Environment (HSE) issues throughout the lifespan of the clay soil production project. HSE Coordinator is responsible for implementation and monitoring of Environmental Management Plan (EMP) and Monitoring Plan as well as coordination with Proponent, local authorities and the nearby communities. HSE coordinator also makes regular review of EMP to cover all potential impacts, amendments and modifications. The tentative schedule for OHSE plan is shown in **Table 9.7**.

The responsibilities of HSE Coordinator are as follows:

- Regular site visits and reporting during preparation, operation and decommissioning/ closure work to check whether the objectives of EMP are being followed.
- The HSE coordinator must keep full records of environmental management activities and present to annual independent third-party environment audit.
- Assess the risk in performing various steps of all production processes such as extraction, transportation and stockpiling through operation, and appropriate safety measures.
- The HSE coordinator shall provide necessary information and instructions, as well as providing and arranging training to the workers and supervising them to follow safety rules and safe working procedures strictly.
- Undertaking regular safety and health inspections and audits on-site.
- To obtain Material Safety Data Sheet (MSDS) from suppliers concerning any hazardous substances bring into the site.
- The HSE coordinator shall provide and enforce wearing of effective helmets, and where necessary, safety harnesses, and other personal protective equipment for all employees.
- The HSE coordinator will manage for water usage in every workplace at suitable and easily accessible place for the whole phases.

Phases	Activities	Frequency
	Machineries	
	Safety	Once a year
	Training	
	Chemical	
Preparation,	Handling	Once a year
Operation	and Storage	
and	Training	
Demolishing		
/Closure	First Aid	Once a year
Phases	Training	
	Basic Fire	
	Fighting	Once a year
	Training	

Table 9.7 Tentative Schedule for OHSE plan



Annual Health	Once a year
Examination	

9.6 COMMUNITY HEALTH AND SAFETY PLAN

This community health and safety plan is intended to improve environment conditions which affect the surrounding communities. This can be placed in safe condition by adopting the following measures for prevention of accidents and hazards.

(a) Community Diseases

- Developing and implementing the health awareness training
- Providing health services of community health clinic
- Promoting collaboration with local authorities to enhance the awareness of public health services and facilities to the workers' families and community

(b) Safety and Security

- Trespassing by workers must be prohibited and the appropriate disciplinary action must be taken.
- Access to construction sites must be restricted
- Precaution and warning sign for health and safety risks must be placed around the project site
- Public awareness programmes must be developed to know the potential impacts of clay soil production

9.7 EMERGENCY PREPAREDNESS AND RESPONSE PROCEDURES

Emergency response procedures and systems are those procedures for handling sudden or unexpected emergency situations. These objectives are to:

- Prevent fatalities and injuries to workers
- Protect the environment and people in the community
- Reduce damage to building, stock and equipment,
- Accelerate the resumption of normal operations

The project proponent should prepare an emergency preparedness plan in order to prevent the consequences of natural disasters such as fire, landslide and man-made disasters. The purpose of the Emergency plan is to minimize the danger to life and property in the event of disasters in the clay soil mining operations. The prevention, preparedness and response plan for fire hazards and landslides are described as follows:

9.7.1 Fire Prevention, Preparedness and Response

Oil barrel and diesel will be stored in the project compound for the generator use; without proper storage, there is a high risk of fire hazards. Therefore, the emergency response plan for fire hazards is described as follows:

- Keep using and storage of combustibles to a minimum.
- Store flammable liquids in approved containers in well-ventilated storage areas.



- Smoking is totally prohibited near the storage area of flammable liquids.
- Place oily polishing rags or waste in covered metal cans.
- Store adequate quantity of water for firefighting
- Fire extinguishers should be provided in the project site. It is very effective life-saving tools, if they are used properly. Fire extinguishers come in different varieties. It is important to choose the right kind of extinguishers for putting out different types of fire. Check for the following symbols on the label of fire extinguishers as shown in **Figure 9.2**.



Components of a fire extinguisher

Figure 9.2 Components of a Fire Extinguisher

Fires have been classified into five categories based on the type of fuel as follows:

Table 9.8 Types of Fires

		Types of Fires		
А	В	С	D	K
Fire that is burning from wood, rubbish, paper and other ordinary fuels.	Fire that involves flammable liquids, such as petrol, gasoline and paints.	Fire that involves electrical equipment, transformers and electrical appliances.	Fire that is burning from combustible metals such as magnesium and titanium.	Fire stemming from cooking media (vegetable or animal oils and fats, etc.)

Type A, B and C of fires can occur at the mine site during preparation, operation and decommissioning/closure phase. Although there are many kinds of fire extinguishers, the most appropriate fire extinguishers should be used for the clay soil mining operation as shown in **Figure 9.3**.



Extinguisher				Type of fir	re		
Color	Туре	Solids (wood, paper, cloth, etc.)	Flammable Liquids	Flammable Gasses	Electrical Equipment	Cooking Oils & Fats	Special Notes
	Water	Yes	No	No	No	No	Dangerous if used on liquid fires or live electricity
	Foam	Yes	Yes	No	No	Yes	Not practical for home use
٢	Dry Powder	Yes	Yes	Yes	Yes	No	Safe use up to 1000 voltages.
Í	Carbon Dioxide (CO2)	No	Yes	No	Yes	Yes	Safe on high and low voltages.
	Halon	Halon ex cause da Existing replaced	Halon extinguishers are not recommended due to their toxic nature and cause damage to the environment. Existing halon extinguishers will no longer be re-filled and should be replaced with a utuable alternative.				



Uses of a fire extinguisher properly						
Remember the acronym PASS .						
PULL the pin.	P – Pull the pin- the pin releases a locking mechanism and will allow you to discharge the extinguisher.					
AIM at the base	A - Aim at the base-not the flames. This is important- in order to put out the fire, you must extinguish the fuel.					
SQUEEZE the trigger.	S – Squeeze the trigger – this will release the extinguishing agent in the extinguisher. If the handle is released, the discharge will stop.					
SWEEP from side to side.	S – Sweep from side to side – using a sweeping motion, move the fire extinguisher back and forth until the fire is completely out. Operate the extinguisher from a safe distance, several feet away, and then move towards the fire once it starts to diminish. Be sure to read the instructions on your fire extinguisher different fire extinguishers recommend operating them from different distances.					

Table 9.9 Uses of a Fire Extinguisher Properly



	5 1
Do's to prevent a fire	Don,ts to prevent a fire
• Keep fire extinguishers in the project site.	• Do not let children play with fire.
• Keep a separate water tank for fire extinguishing.	• Do not use lamps, candles, etc. near bamboo sheet/ wooden partitions or mosquito nets.
	• Do not pile hay or corn stems near houses.
	• Do not use petrol for lighting or start a fire.
	• Do not store fuel and fuel oil near the fire place.
	• Do not use ligher or candle light near fuel oil

Table 9.10 Safety Tips on Fire

9.7.2 Landslide Prevention, Preparedness and Response

Land Conversion can occur due to removal of existing vegetation, large excavation activities and extraction of clay soil in the ground. So, the prevention, preparedness and response plan for a landslide are described as follows:

- Keep records of erosion, landslide masses
- Never construct buildings on the debris without the proper analysis of ground stability and resistance. Loosened masses can subside when load is added to them.
- Try to protect the slopes. Prevent people from excavating, removing materials from the soil or cutting trees without proper advice from the technical experts.
- Avoid building houses at the base of slopes that are prone to landslides.
- Replant trees where they have been removed to prevent soil erosion.
- Prevent deforestation and vegetation removal.
- Avoid weaking the slope.
- Retaining walls efficiently reduce localized landslide hazards, like in the case where cuts into the slopes are needed to build a road or a house as shown in **Figure 9.4**. However, they have to be used with caution because they might also increase the hazard if water in the soil is not allowed to drain properly.
- Proper water runoff must be ensured, especially where houses and roads have disrupted the natural flow patterns. This can be achieved by providing a proper canalization network.
- Drainage: good ground drainage is essential to prevent saturation and consequent weaking.
- Reforestation: Root systems bind materials together and plants, both prevent water percolation and take water percolation and take water up out of the slope. Tree roots help holding the different soil layers together and hinder landslides as shown in **Figure 9.5**.





walls



Figure 9.5 Tree roots help holding the different soil layers together and hinder landslide

Table 9. 11Safety Tips on Landslide			
Do's to prevent landslide	Don'ts to prevent prevent		
 Listen to weather forecasts on the radio, TV about heavy rain. Continuous heavy rainfall within a period of a few hours has the potential to trigger landslides. Listen for abnormal sounds of soil and rock movement or breaking of trees. They may be associated with landslide movements. Contact your local authority, village disaster preparedness committee, fire services department, or Myanmar Police Force. Local officials are the best persons who are able to assess potential dangers. If you are near a stream or channel, be alert for any sudden increase or decrease in water flow and for a change from clear to muddy water. Such changes may indicate debris flow activity upstream, so be prepared to move quickly. 	 Do not build near steep slopes, close to mountain edges, near drainage ways or natural erosion valleys. Never go closer to observe cracks on the slope. If you spot cracks, inform the authorities and move out from the area. 		

During Landslide	After a Landslide
 Quickly move out of the path of the landslide or debris flow. Moving away from the path of the flow to a stable area will reduce your risk. If escape is not possible, curl into a tight ball and protect your head. A tight ball will provide the best protection for your body. 	 Stay away from the slide area. There may be danger of additional slides. Listen to local radio or television stations for the latest emergency information. Replant damaged sites as soon as possible since erosion caused by loss of ground cover can lead to flash flooding. Seek the advice of a geotechnical expert for evaluation landslide hazards or designing corrective techniques to reduce landslide risk. A professional will be able to advise you on the best ways to prevent or reduce landslide risk, without creating further hazard.

Table 9.12 During Landslide and After a Landslide



9.7.3 Emergency Communications (Kyaikmaraw Township)

All emergency phone numbers should be identified, listed in the emergency preparedness plan and posted each department should display the diagram in a highly visible mine area.

Department	Phone No.		
Fire Brigade			
Central Fire Station	057-86015		
POLICE			
Kyaikmaraw Police Station	057-86004		
HOSPITAL & AMBULANCE			
General Hospital	057-86008		

Table 9.13	Emergency	Contacts
------------	-----------	----------

9.8 TOPSOIL MANAGEMENT PLAN

This Topsoil Management Plan (TMP) has been prepared to demonstrate how topsoil will be preserved in a condition as near as possible to its pre-mining condition in order to allow successful mine rehabilitation. The TMP will include procedures for storage of topsoil during the life of the revised project and appropriate use of topsoil during progressive pit closure and rehabilitation. Topsoil is a finite resource and a vital component of successful rehabilitation.

Existing Topsoil Resources



A Horizon (Topsoil) layer is generally darker than other horizons and may contain decomposed organic materials. Topsoil includes the O layer which contains organic material in varying stages of decomposition. The horizon has the maximum biological activity for any given soil profile. B Horizon (Subsoil) layer has a distinctly different structure or consistency to the A horizon and usually contains a higher clay content. Plant roots penetrate through this layer, although it has very little humus. The A horizon is referred to as 'topsoil'

and the B horizon is referred to as 'subsoil'. The topsoil and subsoil will be selectively handled (stripping depth and depth of return) depending on the soil type, and will either be directly returned or stockpiled for later use, which depends on the rehabilitation requirement and the stage of mine development. Topsoil and subsoil stockpile for later use in rehabilitation will require different management during storage and reuse. Subsoil recovery across the revised project site for re-vegetation purpose will be limited due to its general adverse physical nature.



9.8.1 Vegetation and Topsoil Management

Clearing of vegetation should at all times be kept to a minimum to ensure safe working conditions and to conserve the natural vegetation as much as is possible. Vegetation establishment is generally improved by the direct return of topsoil and is considered 'best practice' topsoil management. Suitable topsoil will be stripped for use in the rehabilitation program. All cleared vegetative material may be buried in-pit, or if suitable, placed as habitat within the proposed or current conservation areas. All vegetation is to be collected with the top soil in most proposed project areas this will comprise grasses, to small and medium shrub. Vegetation may be stockpiled separately to topsoil, if necessary due to vegetation causing damage to scrapers on recovery.

Top soil stripping will be undertaken in areas of planned mining activity, the active pit areas, out-of-pit area, haul roads, access roads and other general infrastructures. The topsoil will either be stockpiled until suitable re-contoured areas are available, or preferably be directly returned immediately across the areas to be rehabilitated. Topsoil will be recovered using appropriate equipment. During removal of soils from the stockpiles, take care to minimize structural degradation of the soils. If stockpiling of topsoil cannot be avoid the following should be considered:

- Do not store in large heaps;
- Re-vegetate the stockpile to protect the soil from erosion, discourage weeds and to maintain active populations of beneficial soil microbes;
- Try to avoid using scrapers to build stockpiles as they will compact the soil reducing any biological activity;
- Soils should not be stripped when they are wet as this can lead to compaction and loss of structure;
- Stockpile location must be signposted "TOPSOIL STOCKPILE" and;
- Topsoil stockpiles must be located in a separate planned location. They must not be used for roads, bunds or windrows.

The performance outcomes for the TMP are:

- Soil survey is conducted prior to stripping
- Soil stripping is scheduled to minimize exposed areas
- Soil materials suitable for reuse are recovered and utilized in an appropriate manner; and
- Procedures are in place detailing methods to be used for the stripping and stockpiling of soils.

Always consult the site manager for advice and direction at the planning stage and throughout the topsoil collection, stockpiling and reuse phases. This TMP will give the best results as it prevents or reduces biological deterioration in the soil.

9.9 MINE CLOSURE PLAN

Mine closure is the process of shutting down mining operations in a clay soil mining area. Mine closure plans are specific to each clay soil mine site, and includes details on how

the June Cement Industry Limited will close out the clay soil mine site, how environmental protection will be achieved, and how the mine site will return to an acceptable state to a prearranged land use. The term reclamation, remediation, rehabilitation and etc. are all used to describe mine closure activities that attempt to alter the biological and physical state of a site.

In planning for closure, there are four key objectives that must be considered:

- Protect public health and safety;
- Alleviate or eliminate environmental damage;
- Achieve a productive use of the land, or a return to its original condition or an acceptable alternative; and,
- To the extent achievable, provide for sustainability of social and economic benefits resulting from mine development and operations.

Mine closure activities typically consist of several steps;

- **Shut down**: Once production stops, the number of workers is reduced, and only a small workforce is retained to permanently shut down the mining equipment. The mine owners should provide retaining or early retirement options for their workers before the mine is closed.
- **Decommissioning**: Care should be taken, where processing facilities and equipment, are dismantled, pipelines are drained, equipment parts are cleaned and sold: demolishing of the buildings and warehouse materials, and disposal of waste.
- **Remediation**: The cleanup of the contaminated area to safe levels by removing or isolating contaminants. At clay soil mine site, remediation often consists of isolating contaminated material in storage facilities, domestic waste with clean topsoil, and collecting and treating any contaminated mine water if necessary.
- **Reclamation**: The objective of reclamation is to return the land and watercourses to an acceptable standard of productive use, ensuring that any land forms and structures are stable, and any watercourses are of acceptable water quality. Reclamation typically involves a number of activities such as removing any hazardous materials, reshaping the land, restoring topsoil, and planting native grasses, trees, or ground cover.
- **Rehabilitation**: The existing ecosystem of the project area is a degraded forest ecosystem with some growth of native tree species. A progressive rehabilitation program will be implemented throughout the life of the project and reported in each plan of operations, and will commence when areas become available within the operational land:

The main features of the progressive rehabilitation process are:

- Use of suitable topsoil, sourced from stockpiles;
- Contour ripping as an erosion control measure;
- o Establish a tree nursery
- Collection of indigenous tree seeds
- Raise tree seedlings with indigenous species
- Prepare plan for replanting the mine site.



- Organize labor force
- Site Preparation (digging pits)
- Seeding with an appropriate seed mix (grass, shrub and tree species) prior to the commencement of the wet season to maximize the benefits of subsequent rainfall;
- Planting out
- Application of appropriate fertilizer for plant establishment, if required

The following areas on the clay production mine site will need to be rehabilitated on closure:

- 4 Mine Pit Area
- 4 Topsoil stockpile
- 4 Access Roads and Other Disturbed Areas

Specific rehabilitation plan for these areas, including time frames for rehabilitation works, will be outlined in a Decommissioning and Rehabilitation Plan (to be developed prior to mine closure). The final land use of the project will be both teak plantations (as required by Forest Department) in areas which are currently designated as teak plantation, and native forest for other areas (such as the mine pit). Regularly inspect rehabilitated areas for declaring plants and environmental weeds and control significant weed outbreaks using chemical or mechanical control methods. Regularly inspect and maintain rehabilitation areas to facilitate sediment and erosion control and re-vegetation success.

Top Soil Resource

During the initial clearing works, topsoil and vegetation will be stockpiled adjacent to mine-pit areas for later use in rehabilitation. Stockpiled topsoil and soil will be backfilled in mine pit areas and drainage reinstated to its original state. Plantations will be re-established together with other valuable hardwood species.

Mine Pit Area

Due to the reactive nature of the clayey sand and clay, the pit design and mining schedule will aim to minimize and delay exposure of this material within the pit wall where possible. The final mine pit will be left as a fish pond. Water quality will be monitored to ensure as healthy pond. If the situation is not effective, appropriate treatment will be implemented.

4 Topsoil stockpile

The surface of the topsoil stockpile will be capped with stockpile topsoil and revegetated by valuable hardwood plantations after consultation with the Forest Department.

4 Access Roads and Other Disturbed Areas

These will be ripped and capped with clays and top soil and re-vegetated by hardwood plantation as required by the Forest Department. As any buildings and amenities on site will be demolished, these can simply be removed upon closure and the cleared areas re-vegetated.



• **Post-Closure**: Monitoring programs should be used to assess the effectiveness of the reclamation measures. In addition, mines may require long-term care and maintenance after mine closure such as an ongoing treatment of mine discharge water and periodic monitoring, etc.

Technical audits and reviews of mine closure plans and activities are often completed by professional specialists, government agencies and review committees in order review the safety, stability and environmental risks at mine sites.

9.10 CORPORATE SOCIAL RESPONSIBILITY (CSR) PLAN

June Cement Industry Limited implements Corporate Social Responsibility (CSR) plan together with EMP during its 30 years operation period. The objective of this plan is to create social welfare of miners and the local community, and to prove that the establishment of proposed extraction of the clay soil. Even though the project proponent participates in implementation of CSR plan using 2% of the net profit starting from the very first year of the project, the company focuses more on regional development. A CSR plan formulated for the proposed project can be described in **Table 9.14**.

June Cement Industry Limited has planned the commitments with Environmental Conservation Department under the Ministry of Natural Resource and Environmental Conservation (MONREC) as attached in **Appendix 9**.

No.	Activity	Responsible Company	Frequency	Estimated Amount (% of Net Profit)
1.	All around development in schools	June Cement Industry Limited	Annually	0.4%
2.	Contribution to communication	June Cement Industry Limited	Annually	0.4%
3.	Contribution to employees for health and wellbeing, retirement planning, training and development, social welfare	June Cement Industry Limited	Annually	0.8%
4.	Contribution to regional development	June Cement Industry Limited	Annually	0.4%
	Т	otal		2.0%

 Table 9. 14 Corporate Social Responsibility Plan

9.11 COMMUNITY GRIEVANCE REDRESS MECHANISM

People who live in the project effective area or stakeholders can complain about the impacts that they suffer though Grievance Committee, which includes the responsible persons of June Cement Industry Limited, quarter administrator and representative of Township Fire Department. Small issues are solved at the Grievance Committee stage and other unresolved problems are submitted to higher responsible authorities and finally decided by the court in



legal terms. The following diagram show steps of Grievance Redress Mechanism of June Cement Industry Limited.



Figure 9.6 Steps of Grievance Redress Mechanism of June Cement Industry Limited



CHAPTER 10

CONCLUSIONS AND RECOMMENDATIONS

10.1 CONCLUSION

This Initial Environmental Examination (IEE) Report and Environmental Management Plan (EMP) was prepared by E Guard Environmental Services for Clay soil production proposed by June Cement Industry Limited. The main objective of the study is to identify the major environmental impacts due to the implementation of the project activities in all three phases (preparation phase, operation phase and decommissioning phase). Initial Environmental Examination (IEE) has been conducted for the proposed project under the Environmental Impact Assessment Procedure as per the comments of Environmental Conservation Department (ECD). The project proponent has to implement the proposed project in compliance with the National laws and regulations for environmental protection.

In this IEE report study, baseline environmental data collection and site visit activities conducted on 12th March, 2019. According to the data interpretation for ambient air quality, noise level, water quality results were compared with National and Environmental Quality (emission) guideline and international guideline standards. According to the observed data, dust level of PM10 is within the guideline value but PM 2.5 is exceeding the guideline value. Dust concentration and Ozone level may high during summer seasons. Other gases are within the limit of guideline values. Noise level and water quality results are also within the acceptable limit of guideline values. As soil laboratory results, Heavy metal contaminants of Irons (Fe), Arsenic (As) and micro nutrient contaminant of Zinc (Zn) were exceeding the (FAO) guideline and other results ate within the limit of (FAO) guideline.

This project can create job opportunities for local people in all three phases. The assessment of each impact is based on consideration of the magnitude, duration, extent and probability of activities which are going to be carried out during preparation, operation and decommissioning phases. The impacts for the environment are mostly low during the implementation of the project. All of the impacts during preparation, operation and decommissioning phases can be minimized by using mitigation measures and implementing Environmental Management Plan.

Environmental Monitoring Plan (EMOP) must need to implement for monitoring the environmental quality of the proposed project. Then, the estimated budget need for implementing Environmental Management Plan and Environmental Monitoring Plan are mentioned in this report. Moreover, CSR plan, firefighting plan, emergency preparedness and response plan, mine closure plan and grievance redress mechanism to solve the complaints related with the proposed project are also described in this report. It is also necessary to consider every opinion of all stakeholder potential to be affected by the development of the proposed project.



10.2 RECOMMENDATIONS FOR FUTURE WORKS

The following recommendations have been made for efficient and effective implementation of environmental conservation, health and safety and social responsibilities through the lifespan of the proposed project.

- ✓ Follow the comments and suggestions made by ECD after reviewing this IEE report.
- \checkmark Once EMP is approved by concerned authorities, strict implementation is essential.
- ✓ For full and proper implementation of EMP, well understanding and supports by proponent and authority is deem necessity.
- ✓ Well experienced and knowledgeable HSE Manager and HSE Assistants shall be appointed.
- ✓ Daily, monthly and annual action plan shall be formulated based on this EMP and practiced at operation level.
- ✓ Necessary care and environmentally sound practices should be taken for activities out of factory site particularly on raw material collection and transport.
- ✓ Keep full records of environmental management activities and present to annual independent third-party environment audit.
- ✓ Follow the audit report and comments.
- ✓ Abide environmental policy, laws, rules and instructions of the Republic of the Union of Myanmar.
- ✓ Implement Grievance Redress Mechanism (GRM) to solve the complaints and Corporate Social Responsibility (CSR) plan.
- ✓ Implement EMP and EMOP for balancing development and environmental conservation

Finally, the proponent should follow the comments and suggestions made by ECD after reviewing this IEE report. Once EMP is approved by concerned authorities, effective implementation of EMP by the project proponent is essential. The proponent should abide environmental policy, laws, rules and instructions of the Republic of the Union of Myanmar.



10.3 Disclosing of Initial Environmental Examination (IEE) for Clay Soil Production Project

အများပြည်သူလေ့လာသုံးသပ်အကြံပြုနိုင်ရန် ဖြန့်ဝေထားရှိမှုအစီအစဉ်

June Cement Industry Limited ၏ ရွံ့စေးမြေတူးဖော်ထုတ်လုပ်ခြင်းလုပ်ငန်းနှင့် ပတ်သက်၍ ရေးသားပြုစုထားသော ကနဦးပတ်ဝန်းကျင်ဆန်းစစ်ခြင်းအစီရင်ခံစာ (IEE) အား အများပြည်သူများ ဝင်ရောက်လေ့လာသုံးသပ်၍ အကြံပြုချက်များပေးနိုင်ပါရန် အောက်ပါနေရာများတွင် ဖြန့်ဝေပေးပို့ထားရှိပါသည်။

```
၁။ အမှတ် (၂၁–က)၊ တောင်ဝိုင်းလမ်း၊ ပဲဆီရုံ ကုံးထိပ်၊ ဈေးကျိုရပ်၊ မော်လမြိုင်မြို့
```

၂။ အီးဂတ်ပတ်ဝန်းကျင်ဆိုင်ရာဝန်ဆောင်မှုကုမ္ပဏီ၏ ဝက်ဘ်ဆိုဒ်

(http://www.eguardservices.com/disclosure)

၃။ ပြည်ထောင်စုဝန်ကြီးရုံး၊ သယံဇာတနှင့် ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဝန်ကြီးဌာန၊ နေပြည်တော်

၄။ ညွှန်ကြားရေးမှူးချုပ်ရုံး၊ ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဦးစီးဌာန၊ နေပြည်တော်

၅။ ညွှန်ကြားရေးမှူးရုံး၊ ပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဦးစီးဌာန၊ မွန်ပြည်နယ်

၆။ မွန်ပြည်နယ်သဘာဝပတ်ဝန်းကျင်ထိန်းသိမ်းရေးကော်မတီ

ဂ။ အမှတ် (၁) သတ္တုလုပ်ငန်း

၈။ ကျိုက်မရောမြို့နယ် အုပ်ချုပ်ရေးမှူးရုံး၊ မွန်ပြည်နယ်

၉။ ကော့ပနောကျေးရွာအုပ်ချုပ်ရေးမှူးရုံး၊ ကျိုက်မရောမြို့နယ်၊ မွန်ပြည်နယ်



References

- International Finance Corporation, 2007. Environmental, Health and Safety Guidelines: Construction and Decommissioning, World Bank Group.
- International Finance Corporation, 2007. Environmental, Health and Safety Guidelines: Occupational Health and Safety, World Bank Group.
- International Finance Corporation, 2007. Environmental, Health and Safety Guidelines: General, World Bank Group.
- International Finance Corporation, 2007. Environmental, Health, and Safety Guidelines for Mining, World Bank Group.
- World Health Organization, 2010. WHO guidelines for indoor air quality: selected pollutants, regional office for Europe.

National Environmental Quality (Emission), 2015. NEQ Guidelines

Environmental Management Plan for M/s. Velchal Clay soil Quarry Prepared by SRI SAI MANASA NATURETECH PVT .LTD Hyderabad

Environmental Management Plan for Mining Clay soil Prepared by M/s G. Bal Reddy



APPENDIX 1- Surface Water Quality Laboratory Result (1)





WTL-RE-001

Laboratory Technical Consultant: U Saw Christopher Maung B.Sc Engg: (Chrl), Dip S.E(Dett) Looturer of YIT (Retd), Consultant (Y.C.D.C), LWSE 001, Former Mamber (UNICEF, Water quality monitoring & Surveillance Myseman)

Issue Date - 01-12-2012 Effective Date - 01-12-2012 Issue No - 1.0/Page 1 of 2 W0319 590

WATER QUALITY TEST RESULTS FORM

Client	Clay	
Nature of Water	Surface Water	
Location	Kyelkmayaw Township	
Date and Time of collection	17.3.2019	
Date and Time of arrival at Laboratory	18.3.2019	
Date and Time of commencing examination	19.3.2019	
Date and Time of completing	24.3.2019	

Results of Water Analysis

WHO Drinking Water Guideline (Geneva - 1993)

pН	7.2	6.5 - 8.5
Colour (True)	TCU	15 TCU
Turbidity	NTU	5 NTU
Conductivity	micro S/cm	
Total Hardness	mg/l as CaCO ₃	500 mg/l as CaCO3
Calcium Hardness	mg/l as CaCO ₃	
Magnesium Hardness	mg/l as CaCO ₃	
Total Alkalinity	mg/l as CaCO ₃	
Phenolphthalein Alkalinity	mg/l as CaCO ₃	
Carbonate (CaCO ₃)	mg/l as CaCO ₃	
Bicarbonate (HCO3)	mg/l as CaCO3	
Iron	mg/l	0.3 mg/l
Chloride (as CL)	mg/l	250 mg/l
Sodium chloride (as NaCL)	mg/l	
Sulphate (as SO ₄)	mg/l	500 mg/l
Total Solids	mg/l	1500 mg/l
Suspended Solids	mg/l	
Dissolved Solids	mg/l	1000 mg/l
Manganese	mg/l	0.05 mg/l
Phosphate	mg/l	
Phenolphthalein Acidity	mg/l	
Methyl Orange Acidity	mg/l	
Salinity	ppt	

Remark: This certificate is issued only for the receipt of the test sample.

Tested by	Heiro	Approved by	Secont-+
Signature:	Zaw Hein Oo	Signature:	Soc Thit
Name:	B.Sc (Chemistry)	Name:	B.E (Civil) 1980.
	Sr. Chemist		Technical Officer
ision of WEC Co. Ltd.	ISO TECH Laboratory		ISO TECH Laboratory

(a division of WEG Co.,Ltd.)

No.16. Lanthit Road, Nanthargone Quarter, Insein Township, Yangon, Myanmar. Ph. 01-640955, 09-73225175, 09-30339681, 01-644506, E-mail: isotechiaboratory@gmail.com. Website: weg-myanmar.com









WTL-RE-001 Issue Date - 01-12-2012 Effective Date - 01-12-2012 Issue No - 1.0/Page 2 of 2 W0319 590

WATER QUALITY TEST RESULTS FORM

Client Clay Nature of Water Surface Water Location Kyelkmayaw Township Date and Time of collection 17.3.2019 Date and Time of arrival at Laboratory 18.3.2019 Date and Time of commencing examination 19.3.2019 Date and Time of completing 24.3.2019

Results of Water Analysis

WHO Drinking Water Guideline (Geneva - 1993)

Temperature (°C)		'C	
Fluoride (F)	r	ng/l	1.5 mg/l
Lead (as Pb)	n	ng/l	0.01 mg/i
Arsenic (As)	n	ng/l	0.01 mg/l
Nitrate (N.NO ₃)	n	ng/l	50 mg/l
Chlorine (Residual)	n	ng/l	
Ammonia (NH ₃)	n	ng/l	
Ammonium (NH4)	n	ng/l	
Dissolved Oxygen (DO)	n	ng/l	
Chemical Oxygen Demand (COD)	32 n	ng/l	
Biochemical Oxygen Demand (BOD)	8 n	ng/l	
(5 days at 20 °C)			
Cyanide (CN)	n	ng/l	0.07 mg/l
Zinc (Zn)	m	Ngri	3 mg/l
Copper (Cu)	n	ng/l	2 mg/l
Silica (Si)	π	ng/l	

Remark: This certificate is issued only for the receipt of the test sample.

Tested by Signature:

Heres
Zaw Hein Oo

Approved by

SUCH-Signature: Name:

Soe Thit B.E (Civil) 1980, Technical Officer ISO TECH Laboratory

Name:

B.Sc (Chemistry) Sr. Chemist ISO TECH Laboratory

(a division of WEG Co.,Ltd.)

No.18. Lanthit Road, Nanthargone Quarter, Insein Township, Yangon, Myanmar. Ph: 01-640955, 09-73225175, 09-30339681, 01-644506, E-mail: Isotechiaboratory@gmail.com, Website: weg-myanmar.com





ANALYSIS REPORT

ORIGINAL

Job Ref: 2000391/19 Date: 25/03/2019 Page 1 of 1

Sample Described as : Client Name Sample Received Date : Sample Brought By : Sample Marking Sample Location Analysed Date Lab Code No.

Waste Water **Clay Production Project** 18. March .2019 Client GW Kyaik Ma Yaw 19. March .2019 093/19

No.	Test Parameter	Method	LOQ	Unit	Result
া	Total Suspended Solid	Standard methods for the examination of water & waste water APHA ,AWWA & WEF,22nd ed, 2012; 2540-D.Dried at 103-105 °C	20	mg/L	46
2	Total Nitrogen	Standard methods for the examination of water & waste water APHA ,AWWA & WEF,22nd ed, 2012; 4500-Neg B.Macro Kjeldahi Method	1	mg/L	<1
3	Total Phosphrous	Standard methods for the examination of water & waste water APHA ,AWWA & WEF,22nd ed, 2012;4500-P E.Ascorbic Acid Method	0.01	mg/L	<0.01
4	Oil & Grease	Standard methods for the examination of water & waste water APHA ,AWWA & WEF,22nd ed, 2012;5520B	5	mg/L	<5

End of Report

SGS (Myanmar) Limited NA (Nu Nu Yi) Manager

This document is issued by the Company under its General Conditions of Service accessable at <u>Hits/Networkge conditions international problems interaction</u>. And under the General Conditions of Service accessable at <u>Hits/Networkge conditions international problems interaction</u>. Any index of his document is advised that information contrained hereon relates the Company's findings at the time of a latent and units of Claim 3 instructions, if any. The Company's sole responsibly is to be Contained therein. The instruction of the law."

SBS (Myanmar) Limited Minerals Services, 79/D, Bo Chein Street, 6 ½ Mile, Haing Township, Yangon, Myanmar 1+95(1) 854 795, 654 796, 654 864, 654 865 e sps myanmar@sgs.com

Member of SBS Group(SBS SA)



APPENDIX 2- Surface Water Quality Laboratory Result (2)





WTL-RE-001 Issue Date - 01-12-2012 Effective Date - 01-12-2012 Issue No - 1.0/Page 2 of 2

WATER QUALITY TEST RESULTS FORM

Client	Limestone Quarry	
Nature of Water	Surface Water	
Location	Kyeikmayaw Township	
Date and Time of collection	17.3.2019	
Date and Time of arrival at Laboratory	18.3.2019	
Date and Time of commencing examination	19.3.2019	
Date and Time of completing	24.3.2019	

Results of Water Analysis

WHO Drinking Water Guideline (Geneva - 1993)

W0319 586

Temperature (°C)	25.0	°C	
Fluoride (F)		mg/l	1.5 mg/l
Lead (as Pb)		mg/l	0.01 mg/l
Arsenic (As)		mg/l	0.01 mg/l
Nitrate (N.NO ₃)	0.3	mg/l	50 mg/l
Chlorine (Residual)		mg/l	
Ammonia (NH ₃)		mg/l	
Ammonium (NH ₄)		mg/l	
Dissolved Oxygen (DO)	5.4	mg/l	
Chemical Oxygen Demand (COD)		mg/l	
Biochemical Oxygen Demand (BOD)	16	mg/l	
(5 days at 20 °C)		0	
Cyanide (CN)		mg/l	0.07 ma/l
Zinc (Zn)		mg/l	3 mg/l
Copper (Cu)		mg/l	2 mg/l
Silica (Si)		mg/l	

Remark: This certificate is issued only for the receipt of the test sample.

Tested by

Heir Signature: Zaw Hein Oo B.Sc (Chemistry) Name:

Sr. Chemist ISO TECH Laboratory

Approved	by
Signature	:

Name:

Soe Thit B.E (Civil) 1980, Technical Officer 1SO TECH Laborator

See-

(a division of WEG Co.,Ltd.)

No.18. Lanthit Road, Nanthargone Quarter, Insein Township, Yangon, Myanmar. Ph: 01-640955, 09-73225175, 09-30339681, 01-644506, E-mail: isotechlaboratory@gmail.com, Website: weg-myanmar.com







W0319 586



WTL-RE-001 Issue Date - 01-12-2012 Effective Date - 01-12-2012 Issue No - 1.0/Page 1 of 2

WATER QUALITY TEST RESULTS FORM

Client	Limestone Quarry	
Nature of Water	Surface Water	
Location	Kyeikmayaw Township	1.1
Date and Time of collection	17.3.2019	
Date and Time of arrival at Laboratory	18.3.2019	
Date and Time of commencing examination	19.3.2019	
Date and Time of completing	24.3.2019	

Results of Water Analysis

WHO Drinking Water Guideline (Geneva - 1993)

рН	7.6		6.5 - 8.5
Colour (True)		TCU	15 TCU
Turbidity	330	NTU	5 NTU
Conductivity		micro S/cm	
Total Hardness		mg/l as CaCO ₃	500 mg/Las CaCOa
Calcium Hardness		mg/l as CaCO ₃	
Magnesium Hardness		mg/l as CaCO ₃	
Total Alkalinity		mg/l as CaCO ₂	
Phenolphthalein Alkalinity		mg/l as CaCO ₂	
Carbonate (CaCO ₃)		mg/l as CaCO ₂	
Bicarbonate (HCO ₃)		mg/l as CaCO ₂	
Iron		mg/l	0.3 mg/l
Chloride (as CL)		mg/l	250 mg/l
Sodium chloride (as NaCL)		ma/l	230 mg/i
Sulphate (as SO ₄)		ma/l	
Total Solids		mg/l	1500 mg/l
Suspended Solids		mg/l	1500 mg/i
Dissolved Solids		mg/l	1000
Manganese		mg/l	1000 mg/l
Phosphate	Nil	mg/l	0.05 mg/l
Phenolphthalein Acidity		mg/l	
Methyl Orange Acidity		mg/l	
Salinity	0.1	mg/i	
	0.1	ppt	

Remark: This certificate is issued only for the receipt of the test sample.

Tested by Signature:	Zaw Hein Oo	Approved by Signature:	buest t	
Name:	<u>B.Sc (Chemistry)</u> Sr. Chemist	Name:	B.E (Civil) 1980,	
(a division of WEG Co.,Ltd.	ISO TECH Laboratory		ISQ TECH Laboratory	

No.18. Lanthit Road, Nanthargone Quarter, Insein Township, Yangon, Myanmar. Ph: 01-640955, 09-73225175, 09-30339681, 01-644506, E-mail: isotechlaboratory@gmail.com, Website: weg-myanmar.com







Laboratory Technical Consultant: U Saw Christopher Maung B.Sc Engg: (Civil), Dip S.E(Delft) Lecturer of YIT (Retd). Consultant (Y.C.D.C), LWSE 001. Former Member (UNICEF, Water quality monitoring & Surveillance Myanmar)

WTL-RE-001 Issue Date - 01-1-2016 Effective Date - 01-1-2016 Issue No - 1.0/Page 1 of 1

M0319 052

WATER QUALITY TEST (MICROBIOLOGY) RESULTS FORM

Client	Limestone Quarry	
Nature of Water	Surface Water	
Location	Kyeikmayaw Township	
Date and Time of collection	17.3.2019	
Date and Time of arrival at Laboratory	18.3.2019	
Date and Time of commencing examination	18.3.2019	
Date and Time of completing	19.3.2019	

Results of Water Analysis

WHO Drinking Water Guideline (Geneva - 1993)

Total Coliform Count	18	CFU/100ml	Not detected
Thermotolerant (fecal) Coliform Count	4	CFU/100ml	Not detected
рН	7.6		6.5 - 8.5
Turbidity	330	NTU	5 NTU
Colour (True)	120	TCU	15 TCU
Free Chlorine	Nil	mg/l	
Total Chlorine	Nil	mg/l	

Remark : Unsatisfactory for drinking purpose.

: This certificate is issued only for the receipt of the test sample.

: < - Less than

Tested by

Signature:

Name:

Zaw Hein Oo B.Sc (Chemistry) Sr. Chemist **ISO TECH Laboratory**

Approved by

Signature:

Name:

South Soe Thit B.E (Civil) 1980, chnical Officer ISO TECH Laboratory

(a division of WEG Co.,Ltd.)

No.18. Lanthit Road, Nanthargone Quarter, Insein Township, Yangon, Myanmar. Ph: 01-640955, 09-73225175, 09-30339681, 01-644506, E-mail: isotechlaboratory@gmail.com, Website: weg-myanmar.com



APPENDIX 3 – Soil Quality Laboratory Result



United Analyst and Engineering Consultant Co., Ltd.

3 Soi Udomsuk 41, Sukhumvit Road, Bangchak, Phrakhanong, Bangkok 10260

In Tel. 0 2763 2828 Fax 0 2763 2800 www.uaeconsultant.com E-mail: uae@uaeconsultant.com

ANALYSIS REPORT

PROJECT NAME	JUNE GROUP (CLAY)		
CUSTOMER NAME	E-GUARD ENVIRONMENTAL SERVICE CO., LTD		
ADDRESS	INO.11, AIRPORT AVENUE ROAD YANGON MYANMAR		
CONTACT INFORMATION	:TEL: +97 9700 5170 e-mail: Chue@guardservies.com		
SAMPLING SOURCE	1.		
SAMPLE TYPE	:500L	RECEIVED DATE	: JUNE 27, 2019
SAMPLING DATE	:JUNE 16, 2019	ANALYTICAL DATE	: JUNE 27 - JULY 14, 2019
SAMPLING TIME	24	REPORT NO.	: 2019-039419
SAMPLING METHOD	14	WORK NO.	: 2019-004631
SAMPLING BY	CUSTOMER	ANALYSIS NO.	: T19AI862-0001
ANALYZED BY	MISS CHOMTHANAN APHIPATPAPHA		

			RESULT	
PARAMETER	UNIT	METHOD OF ANALYSIS	S - 1 T19A1862-0001	DETECTION
METALS	1.4			
ARSENIC (As)	mg/kg (dry weight)	ACID DIGESTION AND HYDRIDE GENNERATION AAS METHOD (U.S. EPA 1996/3050 B AND 1992/7061 A)	31.1	0.100
CADMIUM (Cd)	mg/kg (dry weight)	ACID DIGESTION AND DIRECT AIR ACETYLENE RAME METHOD (U.S.EPA 1996:3050 B AND 2007:7000 B)	ND	0.300
MERCURY (Hg)	mg/kg (dry weight)	ACID DIGESTION AND COLD VAPOUR AAS METHOD U.S.EPA 2007/74718)	ND	0.100
CHROMIUM (Cr)	mg/kg (dry weight)	ACID DIGESTION AND DIRECT AIR ACETYLENE R.AME METHOD (U.S.EPA 1996/3050 B AND 2007:7000 B)	53.9	0.500
COPPER (Cu)	mg/kg (dry weight)	ACID DIGESTION AND DIRECT AIR ACETYLENE RAME METHOD (U.S.EPA 1996:3050 B AND 2007:7000 B)	37.8	0,300
IRON (Fe)	mg/kg (dry weight)	ACID DIGESTION AND DIRECT AIR ACETYLENE RAME METHOD (U.S.EPA 1996:3050 B AND 2007:7000 B)	88.312	0.500
LEAD (Pb)	mg/kg (dry weight)	ACID DIGESTION AND DIRECT AIR ACETYLENE FLAME METHOD (U.S.EPA 1996:3050 B AND 2007:7000 B)	38.6	1.55
ZING (Zn)	mg/kg (dry weight)	ACID DIGESTION AND DIRECT AIR ACETYLENE RAME METHOD (U.S.EPA 1996:3050 B AND 2007:7000 B)	127	0,350
SAMPLE CONDITION			BROWN SOIL	

ND NON-DETECTABLE

*United Analyst Engineering Consultant Co., Ltd is Sub-contractor of REM-UAE Laboratory and Consultant Co., Ltd

MISS BENJAWAN VIRIYOTHAI) LABORATORY SUPERVISOR

JULY 22, 2019

DO NOT COPY PARTIAL OF THIS ANALYSIS REPORT WITHOUT OFFICIAL APPROVAL .
 REPORTED ANALYSIS REFERS TO SUBMITTED SAMPLE ONLY.

1/1

APPENDIX 4 – Presentation File

Aguard	June Cement Industry Limited	အကောင်ထည်ဗော်ဆောင်ရွက်မည့် ဘီလပ်မြေစက်နှံစီမံကိန်းအတွက် လိုအပ်သည့်	ဆက်စင်လုပ်ငန်းများအတွက်	ာနဦးဟာ်ဝန်းကျင်ဆန်းစစ်ဖြင်းလုပ်ငန်းနှင့်ပတ်သက်၍ ရှင်းလင်းတင်ဖြစြင်းနှင့်	အများပြည်သူသစဘာထားရယူခြင်း	so e este este este este este este este	
C		930		8			

၂၀၁၉ ခုနှစ်၊ ဇွန်လ (၁၅) ရတ်၊ စနေနေ့ ၁

G		lune Cement Industry Li	mited of Aguard
		ဒါရိုက်တာအမည်စာရင်	:ch:
So	အမည်	နိုင်ငံသားစိတ်ရေးကတ်အမှတ်	နေရာ်လိပ်စာ
IC	ဒေါ် နနဝင်း (မန်းနေးဂျင်းဒါရိုက်တာ)	၀၃၂၄၃၀ (ဒိနို)မဟမ/၀၀	အမှတ် (စဂ)) ဆရာစံလမ်းသွယ်၊ ဗဟန်းမြို့နယ်၊ ရန်ကုန်မြို့၊
5	ဦးအောင်မိုး (ဒါရိုက်တာ)	5၀၁၀၄၀ (ဒိနိ) နဟαျ∕Le	အမှတ် (၁၁/၁၃)၊ သရဇီလမ်း၊ အလုံမြို့နယ်၊ ရန်တုန်မြို့၊
EC.	ဦးမြင့်နိုင် (ဒါရိုက်တာ)	၁၂/ကတတ(ဧည့်) လဂ၂၉၁	အမှတ် (၈၀)) ဆရာစံလမ်းသွယ်) ဗဟန်းမြို့နယ်၊ ရန်ကုန်မြို့။
çı	ဦးမြင့်စိုး (ဒါရိုက်တာ)	၁၂/ဗဟန(နိုင်) ဂ၄၈၆၈၄	အမှတ် (၂၇)၊ ရွှေတောင်ကုန်းရိပ်သာ၊ အင်းဂျားမြိုင်လမ်း၊ ဗဟန်းမြို့နယ်၊ ရန်ကုန်မြို့။

2

द्वेविहः	- June Cement Industry Limited	- ပြည်တွင်းရင်းနှီးမြုပ်နှံမှု	-ဆိပ်စံတဲ့တားတည်ဆောက်လုပ်ခြင်။ တူးခြောင်း ဆောက်လုပ်ခြင်။ ဝဝတျောက် ထုတ်လုပ်ခြင်း နှင့် ရှို့စေးခြေတူးတော်ခြင်း လုဝ်ငန်းများ။	-ဘီလပ်မြေစကိရုံ တည်ဆောက်လည်ပတ် နိုင်ရန်	-ကော့ပနေးကျေးရွာအနီး၊ ကိုကြာမရောမြို့နယ်၊ မော်လမြိုင်၊ မွန်ပြည်နယ်။	- ၂၀၁၅ ခုနှစ်၊ ညာဂုတ်လာ၊ (၁၉) ရက်	ſ
	ရင်းနီးမြှင်နံမှု ကုမ္ပကီ	ရင်းနှီးမြင်နှံမှုပုံစံ	လုဝ်ငန်းအ <mark>မ</mark> ူးအစား	စိမံကိန်းအဲဒောရည်ရွယ်ချက်	ပိမံကိန့်သည်နေရာ	မြန်မာနိုင်ငံရင်းနီးမြှုဝ်နံ့ရတော်မရှင် (MIC) သို့အရာမြူလွာ တဝိပြသည့် ရက်စွ	

C	ASS 405	မင်ေပမာက		aguarc
1				
ŝ	အကြောင်းအရာ	အမေရိကန် ဒေါ် လာ သန်းပေါင်း	ကျပ် သန်းပေါင်း	စုစုပေါင်းကျပ် သန်းပေါင်း
ō	စိမံကိန်းဖွံ့ဖြိုးတိုးတက်ရေးလုပ်ငန်းများ နှင့် ဆက်စပ် အဆောက်အဦးများ	ცები.ი	ა-ეეგ	კე. კე. კე.
5	စက်ပစ္စည်းများ ၊ စက်ကရိယာများ စသည့် ပစ္စည်းတို, ၏တန်ဒိုးပမာက	പംപ		ပိုင်ငံ
E.	ရုံးသုံး ပစ္စည်းကိနိယာများ	C000.0	650.0	o)o
5	ဒိုသား	550.0	dd-c	දර-ලද
	စုစုဝေါင်း	c62.0	9,69e	çeo
<u>ه</u>	ဆိပိန်တံဘားငယ်ဘည်ဆောက်လုပ်ခြင်း၊ တူးမြောင်းစောက်လုပ်ခြင်း၊ ဂဝံကျောက်ထုတ်လုပ်ခြင်း နှင့် ရဲ စေးမြေတားဖော်ခြင်း လုပ်ငံနီးများ	ရင်းနှီးမြုပ်နှံ	နွေ၏ ၄၀%	الم

5


*	စီမံကိန်းဆိုင်ရာ အချက်	အလက်များ	Gguar
ဆောက်လုပ်ရေးကာလ		- (၃) နှစ်	
ပမာက စူးစမ်းလေ့လာ		مې (c) -	
ရင်းနီးမြှုပ်နံ့မှကာလ		- နှစ် (၃၀)	
စုစုပေါင်းမြေကွက်အက	p5	- (စစမ်းမြေ) တေ	
၀န်ထမ်းအရေအတွက်		- ပုဝဝ ဦး	
စိမံကိန်းတည်နေရာ (ဂ	ာတ်တီတွဒ်)	မင္ဘာ.၂.၂.၉၁၃	z
လောင်ဂျီတွဒ်		-	

٢



စီမံကိန်းအနီးရှိကျေးရွာဆိုင်ရာအချက်အလက်များ ခြ**guard** 00 စီမံကိန်းဆိုင်ရာ တည်နေရာမ<mark>ှားပြ</mark>ပုံ 97-48-30-8 480'6 0 0.15 0.3 0.6 0.9

ක්රීමේ ක්රීකානවිතු අනුව දනු නුංග දැළ දාළ දාළ දනු
--

C













cc

ြင္ အနားသားဝည္ဝနားကျင်ဆိုင်ရာ အရည္ကအသွေး (ထုတ်လွတ်မ်ာ့) လမ်ိဳးညွှန့်ရက်မ်ား ပထမ









- စောင့်ကြာပ်ရှမည့်အစီအစဉ်များ ကြိုတင်ပြင်ဆင်ပြီးအကောင်ထည်ဖော်ဆောင်ရွက်ခြင်း
- ကနဦးပတ်ဝန်းကျင်ဆန်းစစ်ခြင်းလုပ်ငန်း လုံလောက်မှု ရှိ/မရှိဆန်းစစ်ခြင်း

အများပြည်သူနှင့် ဆွေးနွေးညိန္ဒိင်းသဘောထားရယူခြင်း၏ရည်ရွယ်ချက်များ

- ဖြစ်ပေါ် လာနိုင်သည့် ကောင်းကျိုးမိုးကိုတင်ပြခြင်း
 မိဝင်မတ်သက်ဝမူမှား၏အဖြင့်နှင့်အကြံမြန်ကိမ္မား။ ထိနိုက်သက်ရောက်လာနိုင်မှုများကိုကျွောခုဖေနိုင် မင်္ဝင်မတ်သက်ဝမူမှား၏အဖြင့်နှင့်အကြံမြန်မည့်အစီအစဉ်မှားတွင် ထည့်သွင်းစဉ်တားဖော်ခြင်း မည့်အစီအစဉ်မှား။ စောင့်ကြင်ကြည့်ရှမည့်အစီအစဉ်မှားတွင် ထည့်သွင်းစဉ်တားဖော်ခြင်း
 စီငံကိန်းအကောင်အတည်ဖော်ဆောင်ရွက်ခြင်းနှင့် လည်တတ်ခြင်း၏ မွင့်လင်းခြင်းသာမှုနှင့် တာဝန်မှန်ခိုနှ
 - တိုးတက်စေခြင်း
- Se အငြင်းပွားမှုလျှော့ချင်ားနှင့် စီးကိန်းအကောင်အထည်ဖော်ရာတွင် ချောမွေမှုရှိရန်ထောင်ရွက်ခြင်း



eguard

Guard

နောက်ဆက်တွဲ (စ)

ပတ်ဝန်းကျင်ထိနိုက်မှုဆန်းစစ်ခြင်းလုပ်ငန်းစဉ်

စီမံကိန်းအဆိုပြုလွှာစိစစ်ခြင်း

ဖြစ်စုစွာနှင့် နောက်ဆက်တို "တ " ပါ အမိုးအက မူဂာကို အရမ်းရှိ အစဉ်ချင့်ကား စိုးနေပြီး

IEE လိုတောက် EIA သို့မဟုတ် EMP ဆောင်စွက် ရန် လို မလို ဆင်ကြက်မှာ

IEE သို့မဟုတ် EIA သို့မဟုတ် EMP ဆောင်ရွက်ရန် မလို အရှိပြုလာ တင်သူင်းခြင်း

သက်ဆိုင်ရာ အနှင့်အမိန်ရ ဥကုန အနု အရက်ထုန မေကိန်း သိမာက္စာ လုဝင်နေသောင်ရွက်ရန် ရန်စန်း သိမာက္စာ သက်လက်ဆောင်ရွက်ရန်

စိဖ်ကိန်းအဆိုပြလူသ မြင်ဆင်ခြင်း စိမံကိန်းအဆိုပြသူ

န EIA ဆောင်စွက်နှန် စိမ်ကိန်း သို့ပော့တိ လုပ်ငန်းအရိုးအစား

ပိုပြစယား စစ်ဆားဖြင်းနှင့် IEE အစီရင်စောပြုစု (၂) တင်ဖြစ်ပီး

IHE / EMP ဆောင်ရွက်ရှင် စိမ်ထိန်း သို့တျော်ဂ လုတ်ဝန်းအမျိုးအမား





လေထုတွင်ပါဝင်သည့် အမှန်လာက

aptrostation

Y

လေထုတွင်ပါဝင်သည်

നാറാട്ടെ ഗണന ရေအရာဉ်အသွေး

ສຸມຸວ່ວບອາກ











စိမံကိန်းအနီးနန်းအနည်အနစ်အရည်အသွေးကောက်ယူသည့်ပုံ

5

Initial Environmental Examination

ထိနိုက်မှ အ उक्दर्हहरू (very low iÅ5∱ (wol) အလဟ် အလတ် (moderat idp (high sange tyrev စုစုပေါင်း 3 (a) guard နည်းလမ်းနှင့် အစီအစဉ်များ ဗော်ပြသည့်စိမံချက် o C_c S 0 Ъ စီပံကိန်း ရက်သိမ်းသည် NCCO G 0 5 9 လုစ်ငန်းလည်ဖတ် သည့်*ကာ*လ ပတ်ဝန်းကျင်စီမံခန့်ခွဲမှုအစီအစဉ် 5 ı. 5 7 0 ဆိုးကျိုးသက်ရောက်ခြင်းမှ တည်ဆောက် သည့်ကာလ < ကာကွယ်ရန် < ရှောင်လွှဲရန် < လျော့နည်းစစရန် G i, 5 5 ထင်ရှားသောသက်ရောက်မှုရှိ၍ ကောင်းမွန်စေရေး အမှန်တကယ် ဆောင်ရွက်ရန် လိုအပ် သက်ရောက်မှုအနည်းငယ်ရှိ၍ ကောင်းမွန်စေရေး စေဆာင်ရွက်ရန်လိုအပ် လုံးလသက်ရောက်မှုမရှိသော အနေအထား သက်ရောက်မှုနည်းပါး ရေရှည်ဆောင်ရွက်ရန် ထိနိုက်မှု ဖော်ပြချက် စီမံကိန်းလည်ပတ်ခြင်း (လုစ်နေးလည်ပတ်သည့် ကာလ) • စီမံကိန်းအကြိုတည်ဆောက်ခြင်း၊ (တည်ဆောက်သည့်ကာလ) • စိမံကိန်းသက်တမ်းကုန်ဆုံး၍ ကုန်ဆုံး၍ ဗိတ်သိမ်းရြင်း (စိမံကိန်းပိတ်သိမ်းသည်ကာလ) opedf:

uard	ამდენ:	1	ъ	ଜ	٦		od
69	စိမံကိန်း ဖျက်သိန်းသည် ကာလ	1	QC	E.	15		oc
ာက်တူးဖော်ခြင် <mark>း</mark> မူတိခြင်း	လုပ်နေးကည်တာ် သည့် ကာလ		G	Q.	٦	æ	oc
ခြင်းနှင့် ဂဝံကျော ဘုမ္မအဆင့်သတ်	တည် သော က် သည့်ကာလ	1	o	٦	e.		oc
ရှိ စေးမြေတူးဗော် သက်ရော	ထိနိတ်မှု ခော်ပြချက်	လုံးပသက်ရောက်မှုမရှိသော အနေအထား	သက်ရောက်မှုနည်းပါး	သက်စရာက်မှုအနည်းငယ်ရှိ၍ ကောင်မွန်စစေရေ ဆောင်ရွက်ရန် လိုအပ်	ထင်ရှားသောသက်ရောက်မှုရှိ၍ ကောင်မှုန်စစရေး အမှန့်တကယ် ဆောင်ရွက်ရန် ကိုအပ်	ရေရည်ထောင်ရွက်ရန် မသင့်တော်သော အနေ့အထား	იიძელი
	သိုက်ရ အဆင့်	කැය ුදි දි ව්ය (very low)	¥ट्रिः (NoN)	အလယ် အလတ် (moderate)	чр: (high)	အလွန်များ (very high)	



ဆိုးကျိုးလျော့နည်းစေသည့် အရေးယူဆောင်ရွက်မှုများနှင့်

စီမံကိန်းတည်ဆောက်သည့် ကာလ

စောင့်ကြပ်ကြည့်ရှုမည့် အစီအစဉ်

5



တူးမြောင်းတူးဖော်ခြင်းနှင့် ဆိုဝိန်တံတားဆောက်လုပ်ခြင်း 🖰 guard

သက်ရောက်မူအဆင့်သတ်မှတ်ခြင်း

အလွနိုန်ည်း (very low)

နိုက်နိုတ် ဒုအဆ

(moderate)

အလယ်

ၚ၀လၼ

:ද්දද (wol)

4p: (high)

အလွန်များ

very high)



ေသလံုက်တာသေဘာသောကို ရန်းဆက်နှင့် ကိုယ်ရမ်အတော်ရှိတာ ကိုယ်ရမ်အတော်ရှိတာ မိုင်ကို ကိုလ်စစ်ဆော်ရှိတာ မိုင်ကို ကိုလ်စန်းရှိတဲ့ တက်မရွက်နေ မိုင်ကို ကိုလ်စန်းရှိတဲ့ တွက်နိုင်သော ကုန်းခဲ့ရနိုင်ကက္ကတစ်ခုတ်မရာရှိတ်များ သည်ရုံအရြက်အ

လျေားည်းစစရန်အရေးသ ဆောင်ရက်မ	 ათბატრთოცათიიტანტრითენი ათბატრთოცათიიტანტრი იტინი გითანტიოგნ ითზაცენოცორ იტინი გითანტითა გარაფენოცორ მირაფიო გათათანტითადენა ითარენი 	ေရည်သံကုန်သံကော်ရှာ ထွက်နိုင်သာ ကိုယ်ချေးများ သောကိုက်တများကို ကိုယ်ချီးများတာကွယ်ရေးကိုက်တာ သည့်များ၏ကောက္စာကို ရုပ်ထားခြာ။ ယာဉ်များ၏ကေရာကို ရုပ်ထားခြာ။	လျော့နည်းစေရန်အရေးသူ ဆောင်ရွက်မှု	မဂၢနီးအတွင်းအတုန်ခြင့် ဖွန့်မစ် မည့်ဆျားနှုန်းစီနှံ ဆိုက်ပွဲအျကသားခြင်း။ ဆေဒီလမည့်ဆွက်မှာကိုသူတဲ့ သာတန်ဟာခြင်း။ နေ့စ်မက္ကည်းမှာကောမှာ ခြန်မက်ကွက်သော အိန်သာများ တရိုးဆန်တာကို ချွန်းကိုသူသောမှိခြင်း။ အခုက်တန်ချွန်းကို သူတွေကိုခြင့် ဆိုကျားရှိသားအား တရိန်းဆိုန်တာအတွင်း ချွန်းမိမာရွက်မှာ နေရာန်မှုန်းတာသိရာနေ တရိန်းဆိုကာအတွင်း ချွန်းမိမာရွက်မှာ နေရာန်မှုန်းတာသိရာနေ တရောက်ခြင်း	- - - - - - - - - - - - - - - - - - -	တာများမှာ ကျော်များကျောက်မှုန်း သားခုနှရာယ်နှင့် ပတ်သတ်သော ထိုင်းဘုတ်များထားရှိရန်၊ သားခုန္တရာယ်နှင့် ပတ်သတ်သော ထိုင်းဘုတ်များထားရှိရန်၊
စိုင်္ခကိန်းဆောင်ရက်ချက်	ေလွှားမြားလုံးကျော်သူ အစေးပါသမြားလုံးမြားမှန် အစစ်းစီးရားမှတ်သွေးစစ်များမြား မူကျားလမ်းများ မူကျားလမ်းများ စာတွက်ရှိပြားသည့်	 ဆောက်ကုဒ်ရေးလုပ်ငန်းခွင်တွ ဆောက်ကုဒ်ရေးလုပ်ငန်းချင်း မားသင့်များ စေရာက်ခြင်း။ စားဘက်ကုဒ်ရေးမှာရန်းသည့် စားဘက်ရှင်း၊ ရာတုန်ခြင်း။ စားဘက်ရှင်း၊ ရာတုန်ခြင်း။ တွေ့နိုင်ခြင်းများ ရာသုသ်တွောက်ခြင်း။ အဝေရာပေါ် မီဖက်များ အသုန် ခြင်ပြီး။ 	စိမံတိန်းဆောင်ရွက်ချက်	ອອດປັບປະຊິບສັງງານເຊິ່ງເຊິ່ງ ອາດປະການສາມານ ກາງການເຊິ່ງເປັນງານເຊິ່ງກາງ ກາງການເຊິ່ງເປັນ ກາງການເຊິ່ງການເຊິ່ງການ ກາງການເຊິ່ງການເຊິ່ງການ ກາງການເຊິ່ງການເຊິ່ງການ ກາງການເຊິ່ງການ ກາງການເຊິ່ງການເຊິ່ງການ ກາງການເຊິ່ງການ ກາງການເຊິ່ງການເຊິ່ງການ ກາງການ ກາງການເຊິ່ງການເຊິ່ງການ ກາງການ ກາງການເຊິ່ງການ ກາງ ກາງ ກາງ ກາງ ກາງ ກາງ ກາງ ກາງ ກາງ ກາງ	ဆိတ်ရုံများ သူတိစသေးဘူးရုံ မူနီကွဲများသည့် အလိုးသာဖွင့်မှုပစ် မရွက်များ ရမ္မကျားရှားသူသက္ကသေး လမ်းပေါ်တွင် ရမ္မေရာကျက်သားရှိသေး ရ	လောင်စာဆီများ သိုလောင်တားရှိခြင်း - ဦးဒ စီလောင်လွယ်မစ္စည်းများ စုဂုံတားရှိခြင်း - ဦးခ
စဉ် သက်ရောက်မ	နေရာက်သူ		ာဉ် သတ်ရောတ်မှု	క్రిశిధియ్యాశ్రీతిలు క్రిశిధియ్యాశ్రీతిలు		මං නාතුදුආරා
အရေးပူဆောင်ရွက်မှု	င်ရများဆုတ်တွင်ရန်းလင်းများတွင် နေည်းအအာင်စီးမဦးဆောင်စွက်ရန် မမြို့ရင်သင်များမှ အေငင်မြစ္စာရေးများနို မမောင်ပြီး။	များ အဝန်ကြီးစစ်ခြီး။ သည့် စနေတုတွင် ဝတ်များများ သည့်များအား သည့်များနိုင် သည့်များနိုင် နမာကုတ် စရာခြန်ခြင်း။	အဆာင်ရွက်သည့်ကာလတွင် များကို ဒယ်ရှား၍	ითფიცითნეში იცინიკოცოი გათაცნათყ იციფირანცთივნი ორენერი რანეთაც აციდითი აციკითნენ თაც აციდიდენ	နှစ်တေန် ကင်းလူင်ထားခြင်း နှင့် တင်ပစ္စည်းများကို ရည်းများကို ရော့ထဲသို့ မပစ်ရန်	ထဲမှတ်ခန့်မာ အတွင်းတွင် ကေရက်စရေနို့ မာသမိရတာအာမ် ဝင်ရေရနို့ မာသမိရတာအာမ်
လျော့နည်းစေရန်	 ခြော်ပြင်ခြင်းဆောက် သစ် တက်နိုင်သမျ မတ်ဝန်းကုန်းထိန်ကို ရေ ကြောကူးနှန်းခြီးခြံ စဘာ အဝင်ပေါ် ကိုများကို ထိန်းပါ ကာလတွင် ခြန်းလည်နိုက်နို 	 ဆာာင်မျှန်သည့် တက်ယွန်းရှိ လုတ်ခုံးရှိတားချားအားတွင်အရော လောက် ကုပ်ချေးရှားအားတွင်း အရှိ ဆောက် ကုပ်ချေးတို ကြောက်များကို ရဲဆနာပြင်းရှိသန် မူမှန်စစ်ယားခြင်းa ဓို့ဆာက်များကို ရဲဆနာပြင်းရှိသန် 	• လုပ်ငန်းပြင်ဆင်ခြင် အဝေါ် ယမြေဆီလွှာ	ດຸດທິດສູກ້ອງສາຊັ້ ດຸດທິດສູກ ອາຍຸດ ອີດີ ອີດອາດສູກເຊິ່ງ ອີດີ ອີດອາດສູກຊີວິສ ອາດດາວທີ່ເຮັດເຊັ່ງ ອີດອາດສູກຊີວິສ ອາດດາວທີ່ເຮັດເຊັ່ງ ອາດດາວທີ່	 နေစီးနေလာကောင်း နေစီးနေလာကြောင်းများစင် နေစိုင်ခင်းသည်များ ပုံမှန်စစ်ဆော်ခြင်း သို့နေစစ်ဆော်ခြင်း ဘားခြစ်စေစမည့် တားခြစ်စေစမည့် ကို ကို ကို ကို ကို ကို ကို ကို ကို ကို	 စက်ပစ္စည်းများကို သ ပြင်ဆင်ခြင်း။ တူးခြောင်းတည်စေတ အသွာ့ရံမြစ်အတွင်း မ တည်စဆောက်ရြင်း။
စီမံကိန်းဆောင်ရွက်ချက်	 အဝေါ် သင်္ခြတီသွားမင်နာရှင်းရှင်း သင်းရှင်းမှားခုသိတ္တင်ရှင်းလင်ခြင်းမှင့် စမြရှင်းလင်ခြင်းခ 	 ອຍິດູຍາວການຊີເວັດແຊ່ວ. ອຍິດູຍາວການຊີເວັດແຊ່ວ. ເວລີຍາດ ຊີເຊັ່ງແລະດີຊ ເຊັ່ງເຊັ່ງແລະດີຊີເຊັ່ງແລະດີຊີເຊັ່ງແລະດີຊີເຊັ່ງເຊັ່ງແລະດີຊີເຊັ່ງແລະດີຊີເຊັ່ງແລະດີຊີເຊັ່ງແລະດີຊີເຊັ່ງແລະດີຊີເຊັ່ງແລ ເຊັ່ງເຊັ່ງເຊັ່ງແລະດີຊີເຊັ່ງແລະດີຊີເຊັ່ງເຊັ່ງເຊັ່ງເຊັ່ງເຊັ່ງເຊັ່ງເຊັ່ງເຊັ່ງ	• အပေါ်ယံမြေဆီလွှာဖယ်ရှားခြင်း နှင့် ခြေကြိတ်ခြင်း။	 აანისფოდნავინფნიან წემაცნ იკინაციათ არკიკითი იარკი იკინაცია თავსაფიითი იარკი თბავიკანიათი აციყა თაციაცი თხვიკინაიზენი იციცნიიდენ 	 နီးတွင်းကာလစမြှေလိုးလမ်းခြင်းနှင့် မြေဘူးစတ်ခြင်း သင်္လင်းများတို့သွင့်ရင်းလမ်းခြင်း ဆနေပါသခြေသို့ဘွာများခို မြေအောက်ရေးနမ်းများခြင်း စက်သမ္မာရာကျားမှုထိလိုက်ခြင်း စက်သမ္မာရာကျားမှုထိလိုက်ခြင်း 	• တူးမြောင်းတောက်လုပ်ခြင်းလုပ်ငန်းများ
စဉ် သက်ရောက်မှု	ອີຊິນຊີ່ສຸກ	ร้ะร้างสรรรับสรรรษ	း မြောရည်အသွေးနှင့် ကုန်းနေကောစနစ်		ရောနတောာ်နိုင် ရောန်လောာန်စိ	
	0	3	0		େ	

Page 136



6 2 0	ဖွဲ့စေရန်အရေးမှု ဆောင်ရွက်	რთიიეაღლაფიარეთი და იმის წ თავი თავიავი აცგინი სივა თარადიზითიცწვი სივა თარადის და იმის და იმის და იმის და იმის იკი იმის და იმის და იმის და იმის და იმის და იმის და იმის და იმის და იმის და იმის და იმის და იმის და იმის და იმ იმის და იმი	
	enped	ာလာန္လာတ္ •	
	စီမံကိန်းဆောင်ရွက်ရွက်	 ဗီရှန်းလင်ရှင်းအဝွက် အပင်များ မှတ်သူခြင်း။ စရာသို့ရတ်ကို စရာအီများ စတော်တယ်မှစ်ရေးလုပ်နေ့များကြာင် ရာည်သံမားခြင်း။ 	
	သက်ရောက်မှု	မ ကိုယ်စစ်ကျောက် နားကိုင်ရမ်းရှိသူ	LE VILLAN
	ဝိ	8	

od	

ŝ	သက်ရောက်မှု		စီမံကိန်းဆောင်ရွက်ရှက်	လျော့နည်းစေရန်အရေးပူဆောင်ရွက်မှု
	မြင်ကွင်းပသာဓ		အပေါ် ယံမြေဆီလူဘဗယ်ရှာမြင်။ သစ်ပင်များစုတ်ထွင်ရှင်းလင်မြင်း နှင့်	 မြေပြုင်ခြောင်းခြင်းအတွက် သစ်ပင်များ စုတ်တွင်ရှင်းလင်းရာတွင် တတ်နိုင်သာမျှ ပတ်ဝန်းကျင်ထိုခို
			မြေရှင်းလင်းခြင်း၊ မြေဖို့ခြင်း၊ စက်ယန္တရားများဖြင့် ကုန်ကြမ်းများ	ေလျှာနည်းအောင် စီစဉ်ဆောင်ရွက်ခုန်၊ • လုပ်ကွက်ခရိယာတွင်း ပျိုးပင်ပေါက်များ (ကြီးထွားမှုနှံနံမြို
			တူးစော်ထုတ်လူမြင်း။ စွန့်ပစ်မြေစာများ စုပုံမြင်း။	စေသမံဖို့ကျင်းပင်များ) ဖို့၊တောင်ထား၍ လုပ်ကွက်ပြီးထုံးရှိနို့တွင် မြန်လည်စိုက်ဖို့။ပေမြင်။ - သတိယမော်င်းဘုတ်များစုံက်တူမြင်း နှင့် မြိုစည်းရှိကာာခြင်း
				 သတ်မှတ်ထားသောလုပ်ကွက် စရီယာတွင်း ဆောင်ရွက်ခြ စွန့်းစစ်အနိုက်များအား သတ်မှတ်နေရာတွင် စနစ်တကုရွန့်ပစ်ခြင်း။
5	လေအရည်အသွေး		အပေါ် ယံမြေဆီလွှာဖယ်ရှာခြင်။ သစ်ပင်များခုတ်တွင်ရှင်းလင်းခြင်း နှင့်	 ကြားခံခရိယာအဖြစ် လုပ်ငန်းဝန်းကျင်ရှိ မြေလွှတ်မျာ သစ်ပင်စိုက်ပိုးခြင်း။
			ဓမြရှင်းလင်းခြင်း၊ ဓမြနိုခြင်း။ စက်ယွန္စရားများဖြင့် ကုန်ကြမ်းများ	 အရည်အသွေးကောင်းမွန်သည့် လောင်ဗာ ရေးချင်္ပအသံမပြုခြင်း၊
			တူးဖော်ထုတ်ယူခြင်း။	 အစရာပေါ်မီးစက်များ၊ ယာဉ်များအား ပုံမှန် စစ်ထေးခြင်း၊
		•	လုပ်ငန်းသုံးယာဉ်/စက်များ	• ကောင်းမွန်သည် ယာဉ်/တာများကို အသုံးမြှ စေခြင်း
			သွားလာခြင်။ စွန့်ပစ်ရမ်စာများ စုပုံခြင်း။	 လုပ်ကွက်စရီယာနှင့် ကုန်ကြမ်းမစွည်းသယ်ယူ ပို့ဆော လမ်းစာလျောက် တစ်ရက်လျှင် နှစ်ကြိမ်းဖြန်းပေးရှင်း။
		•	ကုန်တင်ကားများ သင်္ဘောများမှ	 မိီးဖိုးချောင်တွင် ကောင်းမှုန့်သော လေဝင် လေထွက်ရှိန
			ပစ္စည်းများအား သူ့လူလူကောင်ကောင် နှင့်လို့နေ	ဆောင်ရွက်ခြင်း။
			enobacups confides	

ဂျော့နည်းစေရန်အရေးသူ ဆောင်ရွက်	 ສາງດ້າວນາກມູກສາກາ ເງດີດຊຳສູດວ່າ, ສາງປ້ອງສາງດີ, ເຊິ່ງຊຳຊາດເຊິ່ງຊຳຊາດ ຂອງປຽມອຸດອີດຊຳຊາດຊຳຊາດ ຂອງປຽມອຸດຊາດຊຳຊາດຊຳຊາດ ຂອງປຽນທາງດີຊຳຊາດຊຳຊາດ ອາງປ້ອງຊາດແດງດ້າວດີ, ເວດຊຳຊາດຊຳຊາດ ອາງປ້ອງຊາດເຊັ່ງຊຳຊາດ ແດງຄາຍຊຳຊາດຊຳຊາດຊຳຊາດ ຊຳຊາດດ້າວກາງຄາຍຊຳລາດ ແດງຄາຍຊຳຊາດຊຳຊາດຊຳຊາດ ຊຳຊາດຊຳຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງຊາດ ເຊັ່ງຊາດ ເຊັ່ງຊາດຊຳຊາດຊຳຊາດ ເຊັ່ງ ເຊັ່ງ ເຊີນ ເຊັ່ງ ເຊັ່ງ ເຊັ່ງ ເຊັ່ງ ເຊັ່ງ ເຊັ່ງ ເຊັ່ງ ເຊັ່ງ ເຊີ	 အလုပ်အကိုင်ပေါ်ခေါက်လာခြင်း ဝင်စွေတိုးပွားလာခြင်း လူနေမှုအဆင့်အတန်းတို့တက်လာခြင်း 	Aguard 83302
စီမံကိန်းဆောင်ရွက်ချက်	 ინაცირიბებათი იყყონარებით იკანათის იცებიციინდა მაწირწრა იკანათიყი ინაიცირათინენ იყვითანცანეთ იკანათინყორი ინაიცირა იგინათინცარ იგინათინცარ მაბატანება თვნებიცირი იწყება მაბატანება 	• တောင်းကို	ပတ်ဝန်းကျင်ဗိမံခန့်ခွဲမှုအ
သက်ရောက်မှု	လုပ်ငန်းစွင် ကန့်မာတရေးနှင့် ဘေားမွန်လုယ် ကင်းရှင်းရော	ibescfugktu	
စဉ်	5	<u>ت</u>	C AL



ထိုးကျိုးဂျော့နည်းစသာည့် အရေးယူဆောင်ရွက်မှုများနှင့် စောင့်ကြပ်ကြည့်ရှုမည့် အစီအစဉ်

စီမံကိန်းလည်ဟာသည့် ကာလ

cd



ကျော့နည်းစေရန်အရေးပုံဆောင်ရွက်မှု	ေတ်မည်များ တပ်ထပ်ခြက်။ ခြည်ခြိမ်များကို သတ်မှတ်နေရာတွင်မြကုပ်ခြည်နေတြ တေရိုမာမိုးသောသို့ရန် တရန သတ္တတ်များတတွက် တေရိုမာမိုးသို့ ကို ကို ကို ကို ကို ကို ကို ရန် ကို ကို ကို ကို ကို ကို ကို ကို ကို	ေရရက်ထင်အဘာရန်တော်ရှိမပြော်မှုန် ရေမြှောင်းများ ဆူတစ်တမ်ခြင်း ဆူတစ်တမ်ခြင်း သူတံက်မှုတာကရှိငြားနှင့် စတာရန်မှုမ်းခြင်း မြန်မလူင်းရာကို ကြောင်မှုန် တောင်ရွက်တာမြင်း မရှိတ်မှာကျောက်များသောမြင့်က ဆိုတ်မှာကျောကာများသောမြင့်ရာ ဆိုတ်မှာကျောကာမြင့်တာကြင်း မရှိတ်များသောမြင့်ရတာကြင်း မျှင်စင်းရှင်းအသုံးများသောမြင့်ရတားခြင်း	ဝန်ထောင်မူရေးသူများထားကုအနိုင်မြို့ကိုကိုအတူမိုးရှိနှ ့တော်ရည်းမိမြင်း။ အညီရွန်းမိမြင်း။	လျော့နည်းစာရန်အရောသူဆောင်ရွက်မှ	 အာလုပ်အာလုံးအစုန် အာလမ်း ရနိန်ခြင့်၏ စာသစ်အုန်းများကို စီးများအဖြစ် ကိုတာသို့သြား အာလုပ်များ၊ စက္ခင်ာများ၊ လမ်းများ မီးရှိရရာများ၊ စနံ့ပင်စာပန်ငြင့်သုံး 		
စိမံကိန်းဆောင်ရွက်ချက်	 . ဟာသီ ရှိန်မီလမ္ဘည်း သို့လက်သည် . . ဟာသိ ရှန်မလမ္ဘည်း သို့လက်သည် . . ဟူည်းများ ဘယ်သူရီမဆားရာ တွင် အသူရှိချောင်း . . ဟူည်းများ ဘယ်သူရှိချောင်း . . တူည်းများ အသိမရှိချင်း . . တူည်းများ သို့သို့ရမှိခြား . 	 ရှိနေစာမြန် ကံတောက် ကူးစာတိုးတွင် - မူတွန်ကားသာတွင် ဖိုန်းစီးခြားကျော မက္ကဆိုက်ကသာတွင် ဖိုန်းစီးခြားကျော စာလူဒ်လားကန်းများနှင့် ရဲတစ်များ ကျော်များအခြားတိုက်များနှင့် စစိုးချက်တွက်ကများနှင့် စစိုးချက်တွက်ကများနှင့် စစိုးချက်တွက်ကများနှင့် စစိုးချက်တွက်ကများနှင့် စစိုးချက်တွက်ကများနှင့် စစစိုးချက်တွက်ကများနှင့် စစစိုးချက်တွက်ကများနှင့် စစစိုးချက်တွက်ကများနှင့် စစစိုးချက်တွက်ကများနှင့် စစစိုးချက်တွက်ကများနှင့် စစစိုးချက်တွက်ကများနှင့် စစစိုးစစစိုက်များနှင့် စစစိုးစစစိုက်များနှင့် စစစိုးစစစစိုးချက်နေနေနေနေနေနေနေနေနေနေနေနေနေနေနေနေနေနေနေ	သန့်ဝင်စန်းမှ ဖွန့်ပစ်အည်များ ကုပ်ငန်းသုံးသင့်များနှင့် ဝောိများ အန္တာလှင်ခြစ်စေသာ အသုံမြို့မ ကုန်းထိုးစိုးထိခိုတ်ခြင်း။ အားမှုည်မြင်းစင်ကြာင့် ထိလိုခိတ်ခြင်း။	စီမံကိန်းဆောင်ရွက်ချက်	acrossingly		
ဉ် သက်ရောက်မှု	รู้ร่า เรื่องอาวิตรีสุด	ේ ඉදිංහ-හැදිය කෙදේවා කෙදේවා කෙදේවා		် သက်ရောက်မှု	rapeoco		MA IN
•	G	G		0	8		1
ကျော့နည်းစေရန်အရေးပူဆောင်ရွက်မှု	အရည်အသေရွအကာင်မှုန်သည့် လောင်ကောီကို စစ္စာရာတ်အသုံးမြင်း တောင်မှုန်သည့် ယာဉ်ကင်များကို အသုံးမြို့စစ်ခြင်း စကင်များနာ့ သောလူမသောရေးမည့် တားခြို့ခြင်း ကုပ်ငန်းမှုသုံး ကာက္တယ်ရောက်မှုည်များ အသုံးမြို့ခြင်း တေသမြိုးရာင်က်ရောမနဲ့ အခိုင်ရင်များ စိုက်ခြံမြင်း	အခေါ်လဲ စပြည်သွာကို ရနစ်ကားစုလဲသူခြင်း ကုတ်ကွက်စနစ်မှာသူ့ရေး တနည်းကလာရှိသည်။ အမိတောင်များ ဆွေ့ကြာလန်းနှင့်ကြောကို စနစ်တောင်မနာ ဆြည်လန်းသက်များ အာက်မှုဖြည်။ ကာကွယ်ရန် သက်များ၊ အာက်မှုဖြည်။ ကာကွယ်ရန် သက်များ၊ အာက်မှုဖြည်။ တူကျည်းကတ်၊သူများ၊ အတက်များမြင်း။ ထိန့်မှာလုပ်စနေများ၊ အတာင်မွက်ခြင်း။	စရင်းအတိသောလနှစ်ထားရှိတေးရှိသူ့မှ စရာမြာတီးများ ထူးဖေစ်ပေးခြင်း စနှစ်တော့နှစ်ပေးခြင်း နေစ်တော့နှစ်ပြောင်း တော်လူန္တာကျော် လူနဲ့စစ်ဆောက္ဆိ အသူမ်းခြင်း။	ရေပျာနည်းစစရန်အစရာပုဆောင်ရွက်မှု	မ မီအတစ်ရောကိုတောင်ကန်နှင့် မီအတစ်အတွေကြောကားရှိရန် - မီအဘာမျာတာမိုးကျာက်များတားရှိရန် - စော့အဖြစ်စေရန် ပီယာကြာများကို ပုံမှန်စေရန်နှင့် - ရွောဖြစ်စေရန် ပီယာကြာများရှင်နေရန်နှင့် မီအလားလိုသင့်၊ ဖေင်အကျော်န	ေက္ခရီမက္ခရီလက္ခံသေၾကားသား ခန့်ဆင်လာမ်ခြင်း - အလုပ်ခံရှိန်အလည်ကျ သောင်ရွက်စာခြင်းနှင့် - လုပ်ငန်းရှင်ငံသူ၊ ကာကလူင်စာရာဖူးရည်မယ္က။ - လုပ်ငန်းရှင်ငံသူ၊ ကာကလူင်စာရာဖူးရည်မယ္။	ောက်မျှနှာစခြား အလမ္ဂကန်တာဘာ စမုန်ကသူကြန္နာ၊ ရန်တပ်ခြင်း။ အစေရာအပါ က်စုံရမှာအတွက် နိုးစင်ကုစဆော် ဆေရာအပါ ကိစ္စရမှာအတွက် နိုးစင်ကုစဆော် ဆောက်အခြောက္ခြင်းက ကယ်ဆောင်မှု ဗီဗီဦးသင်တိုမှာ။ ဆောက်အခြောက် ကယ်ဆောင်မှု ဗီဗီဦးသင်တိုမှာ။ ဆောက်အခြောက် ကျင်တာ ကြို့စင်တာကို ေပယ်ကြောမှာအားက ပုံနှစ်စစ်ဆောင်မြော်။ လူတ်စစ်အလွန်အတက္ခမှာမိုခြင်း ကိုက်သည်
စိမံကံန်းဆောင်ရွက်ချက်	 ဝနားကိုရာတွင် ဆာပုံမြစ်သော ကော်ညွှန်ကုနောမှ ဆုည်သံခြစ်ဆဲခြင်း ကုန်ကြမ်းများဆား သသံသူတို့ရသားဝန်ခြား - မရှည်များဆား သသံသူ ဖို့ဆောင်ရာတွင် ဆာပိုခြစ်သော သာင်များမှ ဆည်မခြစ်သော သင်များမှု 	 თბისძციდნიებერიინტში აწე თბისძციდნიებერიინტში აწე მაგან თირა თირა თავენააც მაგან თირა თირა თავენაც მადიკუნეს აქ მანინეტში თათავი კათინეტური თათავი კათინეტური მაკისიყვა საქვიიი მაკისიყვა საქვიიი მაკისიყვა საქვი მაკისიცისიყვა საქვი მაკისი	 ຊື່ແວງຄຳ ກາງແບງຄຳ ອົງອູຊີເລີ້າ ເດຍີ່ເຊິ່ງເລີ້າຊຳຄູ່ . ຊື່ແວງຄຳກາງແດງຄູ່ ອີງອູດີເລີ້າ ເດຍີ່ເຊິ່ງເຊິ່ງເຊິ່ງ . ຊື່ແວງຄຳກາງແດງຄູ່ ອູຊີເບີຍອີ່ເຊັ່ງເຫຼີ . ອອຸດູຊີອີຊີຄິຄາ 	စီမံကိန်းဆောင်ရွက်ချက်	ေ စလင်တအိမ္မား ဆိုလှောက်တာမြင်း မီလောင်လွှည်တွေ့ကိမ္မား စုပုံထားမြင်း ဝယာရာမြစ်ခြင်း ပိယာရာမြစ်ခြင်း	 ယာဉ်များအသုံးမြှမြင်း နှင့် သွားလာခြင်းများမှ စတော်ဘာထားရှိနှင့်ဘုံးများ စာလုပ်သမားများ နိုက်ရန်ခြစ်ပွားမျှနှင့် အငြားများမျိုး 	- თატირელი ყველი - თათითამითარც ფრცნიო - ფითითარციარც ფრცნიო - იალიარციარც ფილიკი - იალიარციალი - იალიკი - ი - ი - ი - ი - ი - ი - ი - ი - ი -
သက်ရောက်မှု	နိုင်ငံသူ	မြင်အရည်စတင်နှစ် ကိုန်အနှစ်ကာဝနေစ် ကို	စရအလာတနော် စရာနေလကာစနစ် နိုင်	သက်ရောက်မှု	Quorage and	လုတ်ငန်းခွင် ကျန်းမာစရေးနှင့် သေးကျွန်ရာယ် ကင်းချင်းရေး	
20	ō	ō-	6	So	5	-	

မိုက်မှုကားရှိသြားနှင့် စနစ် တက္ခရွန်မစ်ခြင်းရ နှင့်နယ်ရှည့်ရာများကို သိမ္မားခဲ့တာခြင်း နှင့် မြန်းလည်းသက်ခြင်းနှင့် မှုစနေဖူနှင့် ရမ်တာ်ရာမှာသောင်တို့သွင် မှုစနေဖူနှင့် ရမ်တာ်ရာမှာ အတွန်းခြင်း သင့်ရင်းရန်ရာ အတွန်ချင်း သင်စင်သက်ရန်ရာ အတွန်ကွယ်။ ရနိုင်စည်းရာကာ အတိုက်သိုး ရောက်စည်ရေးကား ရမ်တည်း ရောက်စည်ရသောသာ ရေးရခွဲ ဆွန်ကြားချင်ရာရာခြို့ နှစ်သို့ စသင်စည်လောကာ ရောက်ချင်း

အလုပ်အတုပ်အစုပ် အလမ်း ရန်နိုင်ခြင်း
 အေသစ်လူနီးသူးချိန်ခြက်ဆက်ရှိခြင်း
 အလုပ်များ ကျောင်းများ လမ်းများ မီးရရှိရေးများ စနံ့တိုးတမိုးခြင်း

	ල
V un	





ာ မြင်ကွင်းယားအ • ခရြမင်လွှာတူးတော့တုင်လုခ်ခြင်း • ကုန်းများ ရှိရှိများကို ရှန်းမစ်ခြက်လုန်မှာခြင့် လုပ်ငန်းစကြားခဲ့ ကုန်းများ ရှိရှိများ • ရှန်းတော်များကို ရက်နောက် ကိုန်းခင်းမကားရှိနှင့် စာသင်များရာမှာ • စန်းတစ်ခြက်များ • စန်းတစ်ခြက်များ • စာသောရှိက ကိုနားကို ရန်းမကြောက်များ တွေကိုခြားသည့် ကားတွင် ပြန်းကုန်ကိုချားမခြင်း

လျော့နည်းစရန်အရေးယူဆောင်ရွက်မှု

စဉ် သက်ရောက်မှု စီမံကိန်းဆောင်ရွက်မျက်

ထိုးကျိုးလျော့နည်းစေသည့် အရေးယူဆောင်ရွက်မှုများနှင့် စောင့်ကြည်ရှူမည့် အစီအစဉ်

စီမံကိန်းဝိတ်သိမ်းသည့်ကာလ

EC.

65

ဂေျာ့နည်းစစုန်အရေးသူ ဆောင်ရွက်မှု	ောက်ယ္ကရကၾကာရှိ ပုံမှန် စစ်စေအခြား။ စစ်စစ်သက်နမူအဆာပုံမံခြင်း။ စည်တွော်ထားခုန်ခြင်း ကိုလ်ဘွာ်ထားခုန်ခြင်း ကုလ်ဘွာ်ကုန်းအဆင်မှာမံခြင်းမား စနစ်တက်ခြန်းလည်မြန်မာခြင်း စနစ်တက်ခြန်းလည်မြန်မာခြင်း	ေရေးမြားများအတွင်းသို့ ဖျက်သမီးကမှ ထွက်လာသော အမိုက်များအမှု ရမ်းမကြီးကို ကမ္မမမြိုင်း။ ဆေရိကားများကိုလည်း စနစ်တက်ခုမြည့်နဲ့ဖြိုးဖုံးဆုတ်နှို မိန်းဘာရားကိုလည်း စနစ်တက်ခုမြည့်နဲ့ဖြိုးဖုံးဆုတ်နှို - လုပ်ငန်းသိုးသင့်ရားကို ပုံမှန်စစ်ဖော်ပြီး။
စီမံကိန်းဆောင်ရွက်ရျက်	 လိုင်းနိုးသွင့် ယာဉ်လွှေ့ရားများ တေရှိတာ နှင့် စာဘိုတော့စ်သောနေရာမှ ထိရားကိုစိုးရှိခြင်း သူမာတ်တာချ ခဲ့တာကြန်းရား မိန့်များကို 	 იინამანანებიკელავითა იინა და კალი კალი კალი კალი კალი კალი კალი კალ
သက်ရောက်မှု	ခြောလာသူနှင့် ကုန်အနုတလာနစ် ကို	ရေးအရည်အစသူ့နှင့် ရေရာနေ့စာကာနေစ
δg	ō.	.

မြန်မာဗီခြင်းကြက်ခဲ့ရှိလာသော ဗြီးရတီပမည့်အျကတို မေနတ်ကာရှည်တော်ခြည်း - လုပ်ငန်းနည်းကာဘူသီလေးရည်းမန်း ဖြစ်တွေ့ကြန်း - လုပ်ငန်းနက်သက်တွေကြားမန်း ဖြစ်ညို့ရှိကာဘာတာခြား - လုပ်ငန်းရက်သက်တွေက ကောင်းမွန်သောသည်လူနှံရာအျား - ရက်သိမ်တာတောသာ ပည့်ရမာအသား နနို႔ခြင်းကို တာမိုရီခြင်းရိ	 လိုင်းနီးရက်သိမ်းရာတွင် အသုံးခြာသည့် လာဦးလွှေးရားများနှင့် တိုးစွာအားသုံးနှစ်စစ်ဆားခြားa လော်များအားသုံးနှစ်စစ်ဆားခြင်းအား လွှင်းနီးရှင်ကာက္ခယ်ရေး ဖန့်ညီးများ အသုံးခြုံရခြင်း။ လုပ်ငန့်းနှင်ကာက္ခယ်ရေး ဖန့်ညီးများ အသုံးခြုံရခြင်း။ 	လျော့နည်းစေရန်အချောာ ဆောင်ရွက်နှ	 မြန်လည်အသုံးမြန်စီသော ဖြောအနောက္စမာတွင် မြန်လည်အသုံးမြန်မာ ဖော်စန်စန်တွင် မြန်လည်အသုံးများအတွက် ပောလ်ဆိုသောရှား တာရှိပေရည်းရာ ပောလာခိုသောရှင်မစ်ရည်းရာ ပောလာခိုသောရှင်မစ်ရည်းရာ ပောလာခိုသောရှင်မစ်ရည်းရာ ပောလာခိုသောရှင်မစ်ရည်းရာ ပောလာခံခံလောင် ပောလာခံခံလောင် ပောလာခံခံလောင် ပောလာခံခံလောင် ပောလာခံခံလောင် ပောလာခံခံလောင် ပောလာခံခံလောင် ပောလာခံခံလောင် ပောလာခံခံလောင် ပောလာခံခံလောင် ပောလာခံခံလောင် ပောလာခံလောင် ပောလာခံလောင် ပောလာခံလောင် ပောလာသန်းမြားရာ ပောလာခံလောင် ပောလာခံလောင် ပောလာခံလောင် ပောလာခံလောင် ပောလာခံလောင် ပောလာခံလောင် ပောလာခံလောင် ပောလာခံလောင် ပောလာနာက်ကောင် ပောလာခံလောင် ပောလာခံလောင် ပောလာခံလောင် ပောလာခံလောင် ပောလာခံလောင် ပောလာခံလောင် ပောလာနာကာခံလောင် ပောလာနာကာခံလောင် ပောလာနာကာနာက်ကောင် ပောလာနာကာနာကာနာကာနာကာနာကာကား ပောလာနာကာနာကာကာ ပောလာနာကာနာကာကား ပောလာနာကာကား ပောလာနာကာနာကာကား ပောလာနာကာကား ပောလာနာကာနာကာကား ပောလာနာကာကား ပောလာနာကာနာကာကား ပောလာနာကာနာကာကား ပောလာနာကာနာကာကား ပောလာနာကာနာကာကာကား ပောလာနာကာနာကာကား ပောလာနာကာနာကာကား ပောလာနာကာနာကာကား ပောလာနာကာကား ပောလာနာကာကား ပြာလာနာကာကာကား ပြာလာနာကာနာကာကာကာကား ပြာလာနာကာနာကာနာကာကာကာကာကာကာကာကာကာကာကာကာကာက
 အဆောက်အဦးမှားများသိုင်းခြင်းခ စေးကိုးချက်သေးတွင် စေးကိုးချက်များမှ စုံမှန်းများ စာတ်ရှိခြင်းခ စာတ်ရှိခြင်းခ စမြေးတိုလှာခြန်းများခြင်းခ စမြေးတိုလှာခြန်းများခြင်းခ 	 ဗီမာနိုးခံတဲ့သမီးရားတွင် အသုန်ခြစသာ ယာဉ်များ တနာ့မိုးများများများများများ တနာ့မိုးများရှားများများ စင်ဘံသိမ္မာ ရမ္မာရာနိုင် သယ်သူရိစဆားခြော်။ 	စိမံကိန်းဆောင်ရွက်ရှက်	 ຢັ້ນຄຳຊື່ເຂີດດ້ວຍອາທູກ ສາດກ່ຽວນາກທຸກສວນອ້ຽງສູ່ສວນ ສີຍ້ວິດນາທຸກພູ ຍິດກາສລາງຄ້າງສາມ ທຸກກາດກ້າງຊີເລີ້າ ຢ້ວງກີນຄ້າງສາກູກີດ ຄື
နိုင်စင်းပြီမင်လစ	ရောင်းလဲ နှင့် ဝင့်နိုးဆို	သက်ရောက်မှု	စွန့်ပစ်ပစ္စည်း (အစိုင်အစဲနှင့် အရည်)

 ເກີດຊາຍເວັ້ງຊາວິດຊາວ ເວລາວຽຽງວ່າງ ເມີດແມ່ນ ແມ່ນ ແມ່ນ ແມ່ນ ແມ່ນ ແມ່ນ ແມ່ນ ແມ່ນ	မီးသတ်ရေးဒိုရေးကိုက်နှစ် မိန်းသတ်စအခုမှုမှားထားရှိနှစ် မိဆာအန္တရားမိနစ် ပတ်သတ်သောအတိုးကုတ်မူစာတာရှိရန်။ - စည့ာမြစ်စရေန် မိသက်ကြာများကို ပုံနှစ်စစ်နှန်နိုင် မိသက်ကိုတွင်၊ စစ်စဆာရန်။
မိဒ်တဲ့နိုးဆောင်စွက်ရက္ မိန်းကိုန်းတိုင်သိုးရရ အလုပ်သမားမှားဆော်ခြာသော မိန်းဘူးများ မိလူအသွေးစားဆော် မက်သိုးများ ဆိုက်အတွင်းရားဆွင် သည့်များ ဆက်အတွင်းအတမူး။ သူမိသူများ ဆက်အတွင်းအတမူး။ လူန်းဘူးများ သောအတွင်းအတများ	 လောတေးရိမ္မား သိုလောက်ဆြာ။ စီးလောင်ကုန်းသူး စုဂုံတားခြင်။ မီယာခရာခြင်း။
သတ်ရောက်မှု နိုန်းမီးမူညီး အရည်)	රීශ නාසතුළ ආයර
<mark>പ്</mark> വി	5

Initial Environmental Examination



Pa	ခွင်သုန် မေပါသ ရာမရှင် အရာမရှင် အ		
ရးသူ ဆောင်ရွ	လုပ်ငန်း မမြိုင်း အရေး ကေိပမှု သေးရှိသေး ကို ရှိသူအသွေး စား စုသာမြိုင်း။ စွဲတာမြိုင်း။	်များပြန်လည် စိုက်	တခြင်။ စာက်လာခြင်။
လျော့နည်းစေရန်အဝ	 ສວດງດ້າວນາກຊາກສາກ ສວດງດ້າວນາກຊາຍເຊັ່ງເຊິ່ງເຊິ່ງເຊິ່ງເຊິ່ງເຊິ່ງເຊິ່ງເຊິ່ງເຊິ	 စီမံကိန့်းခရိယာတွင် အပ ပေးခြင်း။ 	ေ အဂုပ်အတိုင်ပေါ်ပေါက် - ဝင်နွေတိုးပွားလာခြင်း - ဂူခုနမ္မအဆင့်အတန့်၊တို
တ်ချက်	ສູສສາດໃຊ້ຄວາງ ອີວຣ໌ ດີສິດກິຊິລິສາ ເວັດຊີວິສີສຸດໃຊ້ເມື່ອນນີ້ ອອດຊິສູນິນຊາຍອາເ ຍຊູນີ້ນຊາຍອາເ	ားကို ချေထဲသို့	
စိမံကိန်းဆောင်ရွ	 ဝန်နိုစက်ဘွဲသို့သော လိုင်နော်မှာ မန္တည်းရားစဉ် လိုင်နော်မှာ မန္တည်းရားစဉ် အမ္တာလိမ်းရားသော သည်သို့သော သည်သို့သော သင်လိုခြင်း။ လွှင်ခန်းများသည် သင်လိုခြင်း။ 	• အန္ဒရာယိရှိ တတုမစ္စည်းမ မပစ်ရန် တားမြစ်ထားမြင်း	. ຈາກນິມຖິ
သက်ရောက်မှု	လုစ်ကွေးရှင် ကျန်းသားရေးရ နောက် ကျင်းရှင်အရ နောက် ကျင်းရှင်အရ နောက် ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်းရ ကျင်း ကျင် ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင် ကျင်း ကျင်း ကျင်း ကျင်း ကျငးကျင် ကျငာ ကျင်း ကျငာ ကျင်း ကျင်း ကျင် ကျင်း ကျင်း ကျင်း ကျင်း ကျင်း ကျင် ကျင်း ကျင် ကျင် ကျင် ကျင် ကျင် ကျင် ကျင် ကျင်	ဒီလမီးဗုဒိုများ (အပင်နှင့် သတ္တဝါ)	ibenchighth
ဝဉ်	5	ق	100

ကည့်ရှာအစီအစဉ် <mark>Aguard</mark> အာဂိကာက	ဝန်တာမည်နေရာ	စီမံကိန်းရရိယာအတွင်း သင့်တော်သောနေရာ တစ်ခု	စီမံကိန်းရရိယာအတွင်းနှင့် မြင်ပ သင့်တော်သော နေရာ နှစ်ခု	စီမံကိန်းအနီး အသုံးမြုသောအဝိစိတွင်းရေ	စီမံကိန်းဓရိယာအတွင်း သင့်တော်သောနေရာ တစ်ခု	စိမံကိန်း၏ ဗွန့်ပစ်မြေစာပုံနေရာ
စ်ရန်းကျင်စောင့်ကြာပ် ဂီမံကိန်းကာာရောက်	တိုင်းတာမည့်အကြိမ်	တစ်နှစ်တစ်ကြိမ်	တစ်နှစ်တစ်ကြိမ်	တစ်နစ်တစ်ကြိမ်	တစ်နစ်တစ်ကြိမ်	ဒ္ဒိစလ
oot	ပတ်ဝန်းကျင်ဆိုင်ရာ အချက်အလက်	လေထုအရည်အသွေး	ရာည်သံ	ရေအရည်အသွေး	ရြအရည်အသွေး	အစိုင်အခဲ စွန့်ပစ်ပစ္စည်း ထွက်ရှိမှု
	လို	0	ر ۲	Q.	5	6

	دن- س ت ۵۰۰۵ ۲۰۰	
ဂျော့နည်းစေရန်အရေးမှု ဆောင်ရွက်မှု	 အားတက်စားဦးရာက လုပ်ငန်းသိုးမဟာရှိသေး ကေိမ္ဘာရားတား ဖြန်းလည်းမဟာရှိသေး တွေ့အားနိုင်ရား ဖြန်းလည်းမဟာရှိသေး စားသမိနာရာဗိန်ဖြစ်သော စားသမိနာရာဗိန်ဖြစ်သော စားသမိနာရာမရန် စားသင့်ရောက်ရန်းရာနေရန် စားသင့်ရောက်ရန်းရာ စားရန်းလည်း စားသင့်ရောက်ရန်းရာ စားရန်းတည် စားသင့်ရောက်ရန်းရာ စားသင့်ရောက်ရန်းရာ စားသင့်ရောက်ရန်းရာ စားသင့်ရောက်ရန်းရာ စားသင့်ရောက်ရန်းရာ စားသင့်ရောက်ရန်းရာ စားသင့်ရောက်ရန်းရာ စားသင့်ရောက်ရန်းရာ စားသင့်ရောက်ရန်းရာ စားသင့်ရောက်ရန်းရောက် စားသင့်ရောက်ရန်း စားသင့်ရောက်ရန်းရောက် စားသင့်ရောက်ရန်းရောက်ရန်းရောက် စားသင့်ရောက်ရန်းရောက်ရန်း စားသင့်ရောက်ရန်းရောက်ရန်း စားသင့်ရောက်ရန်းရောက်ရန်း စားသင့်ရောက်ရန်းရောက်ရန်း စားသင့်ရောက်ရန်းရောက်ရန်းသင့် စားသင့်ရောက်ရန်းရောက်ရန်း စားသင့်ရောက်ရန်းရောက်ရန်း စားသင့်ရောက်ရန်း စားသင့် စားသင့ စားသင့ စားသင့် စားသင့ စားသင့ စားသင့ စားသင့ စားသင့ စားသင့ စားသင့ စားသင့ စားသင် စားသော စားသေ စားသော စားသော စားသော စားသေ စားသေ စားသေ စားသော စားသေ စားသော စားသေ စားသော စားသေ စားသော စားသော စားသော စားသေ စားသေ စာသေ စားသေ	စွဲမှူးဆစ်အစဉ် <mark>မို guard</mark>
စီမံကိန်းဆောင်ရွက်ရှက်	₩. across	ပတ်ဝန်းကျင်စောင့်ကြာည်
သက်ရောက်မှု	accordence Billion	
S	ō	

	ကည်ရှုအစီအစဉ် <mark>ဓိguard</mark>	ည့်ကာလ	ဝဒိုင်းတာမည့်နေရာ	စီမံကိန်းရရိယာအတွင်း သင့်တော်သောနေရာ တစ်ခု	စိမံကိန့်းဧရိယာအတွင်းနှင့် ပြင်ပ သင့်တော်သော နေရာ နှစ်ခု	စိမံကိန်းအနီး အသုံးပြုသောအဝိစိတွင်းရေ	စီမံကိန်းဓရိယာအတွင်း သင့်တော်သောနေရာ တစ်ခု	စီမံကိန်း၏ ဗွန့်ပစ်မြေစာပုံနေရာ
	ာနီးကျင်စောင့်ကြလ်	စိမံတိန်းလည်ပတ်သ	တိုင်းတာမည့်အကြီမ်	တစ်နှစ်တစ်ကြိမ်	တစ်နှစ်တစ်ကြိမ်	တစ်နှစ်တစ်ကြိမ်	တစ်နှစ်တစ်ကြိမ်	ဒိုစလ
(ပတ်ဝ		ပတ်ဝန်းကျင်ဆိုင်ရာ အချက်အလက်	လေထုအရည်အသွေး	စည်တံ	ရေအရည်အသွေး	ရြေအရည်အသွေး	အစိုင်အခဲ စွန့်ပစ်ပစ္စည်း ထက်ရိမ
	C		လို	o	J	9	5	େ



ာည်ရှုအစီအစဉ် <mark>မိုရိယard</mark>	ည့်ကာလ	တိုင်းတာမည့်နေရာ	စီမံကိန်းဓရိယာအတွင်း သင့်တော်သောနေရာ တစ်ခု	စီမံကိန်းရရိယာအတွင်းနှင့် ပြင်ပသင့်တော်သော နေရာ နှစ်ခု	စိမံကိန်းအနီး အသုံးပြုသောအဝိ8ိတွင်းရေ	စီမံကိန်းဖရိယာအတွင်း သင့်တော်သောနေရာ တစ်ခု	စိမံကိန်း၏ စွန့်ပစ်မြေတပုံနေရာ
၀န်းကျင်စောင့်ကြာပ်ဂြ	စီမံကိန်းပိတ်သိမ်းသ	တိုင်းတာမည့်အကြိမ်	တစ်ကြိမ်	တစ်ကြိမ်	တစ်ကြိမ်	တစ်ကြိမ်	တစ်ကြိမ်
coố		ပတ်ဝန်းကျင်ဆိုင်ရာ အချက်အလက်	လေထုအရည်အသွေး	ဆူညံ့သံ	ရေထုအရည်အသွေး	ရေအရည်အသွေး	အစိုင်အခဲ စွန့်ပစ်ပစ္စည်း ထွက်ရှိမှု
C		ۍ ک	0	ر ر	d	5	୍ଚ

ALC: N		
	အရေးပေါ်ကိစ္စများအတွက်စီမံရက်	(a) guard
are contravention		

. မီးဘေး လုုံရှိရေးစီးချက် (ကြိုတင်/ဖြစ်ပွားခိုန်/ပြန်လည်ထွထောင်ခြင်းကာလ)ရေးဆွဲခြင်း

ကြတတောကွယ	ဖြစ်ပွားချိန်အတည်ပြုပြီး	ဖြန်လည်ထူထောင်မည့်
ဓရးနည်းလမ်း	ဖြေရှင်းမည့်နည်းလမ်း	ဘာလ
မီးသတ်ပစ္စည်း ကိရိယာများထားရှိခြင်း	အရေးပေါ် အရြေအဝနအား အခြားနေရာ	📥 သက်ဆိုင်ရာတာဂန်ရှိသူများ
လုံလောက်သောမီးသတ်ရန် ရေဟာက၊	များသို့ မပြန့်ပွားစေရန်ဆောင်ရွက်ခြင်း	သက်ဆိုင်ရာ
သံဗုံးများ အသင့်ထားနိခြင်း	လူနှင့်ပစ္စည်းပျက်စီးဆုံးရှုံးမှု အနည်းဆုံး	အဖွဲ့ အစည်းများ နှင့်
မြင်လူယ်ကားလွယ်သော	ဖြစ်စေခြင်း	ပူးပေါင်းဆောင်ရွက်ခြင်း
အချက်ပေးစနစ်များ ၊လှေကားများ	▶ ထိရောက်သောကယ်ဆယ်မှု နှင့်	l
တပ်ဆင်ခြင်း	ဆေးဝါးကုသမူပေးခြင်း	;
သတိပေးဆိုင်းဘုတ်များထားရှိခြင်း	🏲 ဘေးကင်းရာသို့ပို့ ဆောင်ပေးခြင်း	
မီးဘေးအန္တရာယ် သင်တန်းဖေးခြင်း	🕨 သက်ဆိုင်ရာ မြို့နယ်မီးသတ်ဦးစီးဌာန	
ေ အရေးပေါ် မီးဘေးအန္တရာယ်သရုပ်ပြ	နှင့် ပူးပေါင်းဆောင်ရွက်ခြင်း	
းဒွင်္ကေးခြင်း		

1	



- ကျန်းမာရေးနှင့် ဘေးအန္တရာယ်ကင်းရှင်းရေး ဘာလနိုခံမှ တိုက်ရိုက်စောင့်ကြပ်ခြင်း။
- ပတ်ဝန်းကျင်ထိခိုတ်မှု ရှိ၊ မရှိကို ပုံမှန်စစ်ဆေးခြင်း၊ တားမြစ်ထိန်းချုပ်ခြင်း။
- မြည်သူလူဝုဏ်အကြံမြုတ်များ၊ ဆွေးနွေးချက်များနှင့် ကန့်ကွက်မှုများအတွက် သတင်းများ ရယူပြီး ဖြေရှင်းဆောင်ရွက်ခြင်း။
 - ပါဝင်ပတ်သက်ခြင်းမရှိသည့် ကြားနေအဖွဲ့ အစည်းမှစစ်ဆေးခြင်း။







အသားတင်အမြတ်ဓင္ပ၏ ၂% ကို ရန်ပုံငွေအဖြစ် ထားရှိပြီး အောက်ပါလုဝ်ငန်းများတွင် အသုံးပြုရန်ရည်ရွယ်ထားသည်။

ရန်ပုံငွေအ်ရာခိုင် _{ရှိ} န်း	οģ	od	od
အကြောင်းအရာ	ပညာရေးအတွက် အထောက်အပုံ	ကျန်းမာရေးအတွက် အထောက်အပံ့	လူမှုရေးအတွက် အထောက်အပံ့
ဝိ	ō	5	۳Ċ

65







cG









JUNE CEMENT INDUSTRY LTD.

- 05				good - Goop	စုနှစ်၊ စွန်လ (၁၅)
0.056	కుంద్ర	epoqe	အဖွဲ့အရည်အမည်	ခုန်းနံပါတီ	ronfiged
神	"Inconside"	glional Stanolly	S. Surger & Cogera	092557497041	all
J.	$\tilde{\mathcal{A}} = O^{1/2} \mathcal{C}$	96600.00	Q. coori	60.6 660-50	04-
÷.					
9 8					
58					
61					
4					
68					
£*					
201					
0.08					
0,9					
opi					
361					
100 (2			*		4
June Co	ر مۇرۇپچېلومىتى بىلىنىتى مۇروپچېلومىتى ئىلىنىتى مېروپر	ဖြက်မားကုန်ဖြစ် အတွေအနေအော့ရကူးကျောက္ အကွက်ကန္ကဒီအတိလိုက္ကေရ အနေအြန်း(၂၄၈၄) ကြွတွဲနှင့် နေရာနေ့ကျင်သည့်သို့	්ද කතෝරිකණ්ඩෙෝද්ෂුණිණු ශ්ර මහතාකයක් සිතාකයක්-182) අදි ඡානා කඩේපෙළතෝලෝරෝලෝරාන	ირულის და კული ფილის ფილის ფილის ფილის ფილი ფილის ფილის ფილი	'i Laundgrößtaj Pj
June Cr	ာ nont Industry ယားအနေဖြင့်ဖြင့်ရှုတ်က လိုထပ်သောဆင်ကိုပေါ်ဆံကိန်နာရာက အများရှိ သူရွက်မျှား (Private: Company)	ဖိုက်မာရေးမြို့နယ်။ လော့ပာနေဝကေရုရှာဆန်းတွင် မာရွက်ကနေကြီးတစ်နောက္ကင်းဆန်းစစ်ဖြစ် () NKM ကြို့လူနှစ်စရောစနေ့ကဒိုစီယစ်ဖြစ် (Pather Connell	າະ ຫລະກາຣົດດູລິຣະກໍຣະນາດີສູກໂນຊູລີ ເຮືອ ການລະຫະເຈັດ Summaine-III) ຊື່ນີ້ ຢາກງ ແລະລິດສຽກເຖິດກາດລາງເດີດນາ	ფირე - ეთდ ფა ისიენირებილიანებიები ისფირდიებილიანებიები ისფირდიებილიანებიები ფირე - ეთდი ფირე - ეთდი ფირი ფირი ფირი ფირი ფირი ფირი ფირი ფი	်း ဆောင်ရွက်နိုင်ရန် နင့် ၆၄ ခွန့်လ (၁၅) ရက်
June Cr ogcións: og	າ ກອກປະກັບປະມານ ແລະການສະດຸດຜູ້ຊຶ່ງຜູ້ຮູ້ອອີດເຈົ້າ ດັ່ງແຮງໂຮແດນແຜດດີແຕ່ທີ່ສະດີຊຶ່ນແຜກ ການຊາງສູ ການຊາງສູ ການຊາງສູ ການຊາງສູ ການຊາງສູ	ဖိုက်မရေးမြို့နယ်၊ ကော့အနောေရာရွားသန်းတွင် မလွတ်ကနည်းတစ်လုံးကွင်ဆန်းစစ်ပြင်() (KBA) ကြွတ္စနစ်ကျောနေ့တိုင်ငံဖြင်း (Patak: Danus) ရာထူး	్ కాలాంద్ రాజులు లేకు లేకు సాలాంటికి రాజులు లేకు చే కురు అందిలుగార్మే రాగులు రాజు దృజ్రాగిణుల్లు దృజ్రాగిణుల్లు	ანიწიურდადათანწნიიება ფიუნილიდნი ფიუნილიდნი ფირც - კიიც ფა ფარც - კიიც ფა ფა ფა ფარც - კიიც ფა ფა ფა ფა ფა ფა ფა ფა ფა ფა ფა ფა ფა ფ	్, కంయాప్యానక్రిస్కర్ ల్ రంగ్రాహ్ రంగ్రాహ్
Jane Cr sgrðinna øĝ ai	ారాగ Industry carnedoga@ద్రద్ గర్తియెదయాపరాదేందికిందికిందిందా ఇంధార్ గ్రాహింధిక (Private: Company) పంట్రద్ద లైగ్ ప్రద్ ప్రద్	ဖိုက်မရေးရှိနေကို တော့ပာနောကျေးရှားဆန်းတွ မလွတ်ကနောက်ငန်းကွင်ဆန်းစစ်ဖြင် () ကမာ မလူတူး (၃၄ ကြ	్ కారాజాలు సారాజాలు ప్రాజాలు స్టార్లం కారాంధి	ούοβιτήφοςδουτήβδηψο αγγβαλαροβιτοδιτήθου οφοροίο φοροίο φοροίο φοροίο ο 1208/γ Γιο Ο 1708/γ	်းတောင်ရွက်နိုင်ရန် နင့် လေက်မှထိ - လက်မှထိ
June Ce og ar J ¹	nont industry commeteyský ప్రధుగం గర్గించించాయింగింగిరింగిరింగిరింగి గర్గాగురూ: Company) ఇంటింద్ లో జిగ్ ఇర్ లై భాల్ ప్రార్ట్ క్	ဖြက်မားကုန်းမြေးမာဒ် အတွေးအနေအကျောက္ကာသန်းတွဲ အတွက်ကန္နားတင်လိုက်ကို ကန်းမစ်ဖြစ် (Jacob ၂၉၇ လုန်စနေ့ ဆန်းပင်မြင် (Astate: Consult ရောက္ကာ (M ကြ စာကြ ပြောကင်ကြ (M)	ు కంలారదుద్రకాగంపార్కరుర్తు సాహారాజకు కుణాంపిరాగుల్లు కుణ) అంపిలంధాంప్రిరాగంపార్ కుణ ద్రాజాగాంపు ద్రాజాగాంపు ప	υδοβιστέφαιζουστέββουρία φορείαφαιροποδιστόξηδο φοραιοφέ: φέξι - μουρ φι φέφιλοδ σ1 418051214 σ2 - 41 976 (1209)	'' iwwritgristad ri Gegleu (sy) orf Carloed S
Jane Cr oggråon: ogg	າ nom industry umsetzyjejeje nýzelezosacholočké kjejen mape gynkysi (Private Company) ແລະຊີ ທີ່ອີຊີ ເຊຣີ ຫຼວງ (ຊີ ຊີ ທີ່ອີຊີ ເຊຣີ ທີ່ມີເຊັ	Solver Buch worker open gegen start wydan fan de fan fan start fan start Soge fan start fan start fan st start gege M.D Dat Gymet of nt Minnig Eurg	ి కారారార్ సంస్థ సంస్థ సంస్థ సంస్థ సం సాహారార్ కి మారార్ సంసారార్ రాజ్రార్ సాధార్ సాధార్ సంసార్థ సం సం సం సం సం సం సం సం సం సం సం సం సం	05060046002000056200056200 1000500000055 100050000055 10005000055 10005000055 1000500005 1000500005 100050000000000	in start grifted fi fi fi fi fi fi fi fi fi fi fi fi fi
ອີສາດ ປີດ ອີຊີດີ ມາ ມາ ມາ	າ ກາກt. Instatty Ummedgessfeldensk ດັ່ງເຮັດແລະກາດເຮັດທີ່ປະກິນສາງກ ກາງກ້າວງາ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ ເຊິ່ງເຊິ່ງເຊິ່ງ	Solveor & who was a solve or a solve of the solve was a solve of the s	ి కారాయాద్వి సంగంపారణ్యగుండ్ర చేర సారాయాది కురాయాయార్ 113) భేక కురా) యెకింబ్రంలో రూహించారు రాజ్రాగియుద్ర గ్రేధింగం రాయం ని కు	060600040002000004850000 1900502000000000000000000000000000000000	in and a start of the start of
ລາ ມາ ມາ ມາ ມາ ມາ ມາ ມາ ມາ ມາ ມາ ຍາ ຍາ ຍາ ຍາ ຍາ ຍາ ຍາ ຍາຍ ຍາຍ	rom Industry Company ດ້ວຍໂຣດາລອດໄດ້ທີ່ໄດ້ເຊິ່ງແຕ ກອງກັ ຊູດກັ້ນຊາ (Private Company) ແລະລູລີ ຊີ. ອີຊ. ແລະ ຊີ. ອີຊ. ແລະ ເຊິ່ງ ແລະດີ ຊີ. ແລະ ຊີ. ອີຊ. ແລະ ເຊິ່ງ ແລະດີ ຊີ. ແລະ ຊີ. ອີຊ. ເຊິ່ງ ເຊິ່ງ ເຊິ່ງ ແລະ ຊີ. ເຊິ່ງ	Internet in and and a sources of the source of the sou	్ కారాహద్యాప్రంగంయి త్రిగుడు త్రి సాగాంజంగిక కంటాంటించి!కి) భే కట్ని నించి రాజుంటి గ్రాజంగం రాజుంది గ్రా గ్	000 Funder and Standard 1977 Standard and Standard 1978 - 1978 - 1978 94 1978 - 1978 - 1978 94 1978 - 1978 - 1978 1978 - 1978	inamstyrfyllogi fi Gafaa (sy) arh Carlydd Carlydd G
June Cr ອຍູ້ ມາ ມາ ມາ ມາ ຍຸຍ ຍຸຍ ຍຸຍ ຍຸຍ ຍຸຍ ຍຸຍ	າດຕາ Industry carnedoga@gebach ດ ດຽວເມີດແລະດາດ່ອດໃຫ້ແຮ້ງຂອກ ແຮງຊາ ອູງກ້າຍງາ (Private: Company) ແຮງຊາ ອີດເຊຍ ອີດເຊີອີດເຊຍ ອີດເຊຍ ອີດເຊຍ ອີດເຊຍ ອີດເນ	Internet in the service of the servi	్ రాజారావ్యాసంగంపార్కరుడ్డ మె రాజారావడ కుంగాంపించారి! దిశ్ర తుగ్గాం గ్రామాంత్ కండాంది గ్రామాంత్ కండాంది గ్	000EurilgazioantBlanda apylationsontBlanda apylationsontBland off 41805122 092-49261229 092-49261229 092-5928496 PC 25372499 092555292499 -	in inamstyrsfitaf fr Gastra (sy) an Cashads
3446 Cr 685 01 1 1 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	root Industry connective High Science on Nacional and Angel Science of Science of Science (Private Company) Science Private Company) Science of Science Private Science of Private Science of Private Private Science of Private Science of Private Private Science of Private Science of Private Private Science of Private Science of Privat	Bolance Buch annuage any spatial and the second sec	్ ఇందార్ ఇర్రంగ్ అమార్యం చేర్ సాగారాజుకు E కురణాంటింగా (11) భో కిరణ) ఇండి రంధాంలో గారం (21) భో కిరణాంలో గారం (22) 	000800480280004880460 90000000 9000000 9000000 900000 9000000	in and good to all
ໂທຍ Cc ເຊີງຕໍ່ແກງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີ	ront industry connective filled filler of a fictor source for the filler of a fictor source for the filler of a filler of filler of a fi	Priver Bud worker property alorg working to a consequent provide ist opping to a consequence of the provide opping of the conset of the consecutive provide opping of the which a consecutive consecut	్ కారారార్ ఇర్రంగ్ అర్హాంత్ర మె సాగారాజుక E కంగారంటార్ (17) ఉన్ కికి 11) అండిరాధార్కార్ రారా ద్వారంగా కాగారం గ్రా ల్లింగా కాగారం ల్లింగా ల్లంగా లా ల్లంగా లా లా లా లా లా లా లా లా లా లా లా లా లా	00000000000000000000000000000000000000	issumst gohijtesi Fi Be gijes (seg) oph Cashqub Fi Be
Jane Cr (पुर्वेका) (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे (पुर्वे)) (पुर्व)) (पुरे)) (पुर)) (पुरे)) (पुरे)) (पुरे)) (पुर)) (पुरे)) (पुरे)) (पुरे)) (पुरे)) (पुर)) (पुरे)) (पुरे)) (पुरे)) (प्र	ront Industry unmadequilided factors of coloroscolorided factors mapping (Prinate: Company) sector Provide (Erhang Bula unscreppingening unschnietzungeningenigtening unschnietzungenigtenigter Borge MD Der Erhanzen MD Erhanzen Geologisch erhanzen Geologisch erhanzen Geologisch erhanzen Geologisch erhanzen Geologisch erhanzen Geologisch erhanzen Geologisch erhanzen Geologisch erhanzen Geologisch erhanzen Geologisch	ి కారారార్ రిష్టర్ సంగ్ర స్ట్రి సంగ్ర సాహారార్ రిషారాల్ రెయిరంధార్ రార్ కరిగా గాండి రాధాల్ స్టోరార్ స్టోరార్ రాగులు లై స్ స్ సి సి సి సి సి సి సి సి సి సి సి సి సి	00000000000000000000000000000000000000	i launstyrijtaj fi fi fi fi fi fi fi fi fi fi fi fi fi
Jane Cr တွင် ဆ ျ မ မ မ မ မ မ မ မ မ မ မ မ မ မ မ မ မ မ	າ nont industry ummetry (José or not industry ummetry) name name name name name name name name	Erberge & wie worken von eine son anderen wysion fan de fan fan de fan fan de	າ ກອດການໂດຍຊີວິເທີຍແຫາດີສູກໂທຊູລູ້ ເຮືອ ກາກກອກແປະ Example (Brit) ຊື່ໃ ເຮັກ) ແລະໂອເຊກະຊີໂດຍຊະດີ ເຊິ່ງ ເວລາ ເຊິ່ງ ເວລາ ເຊິ່ງ ເວລາ ເຊິ່ງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີ	00-66-42 20-22	i baanstyristool fi carhydr y Gran
June Cr ອງດີ ມາ ມາ ມາ ມາ ມາ ມາ ມາ ມາ ມາ ມາ ມາ ມາ ມາ	room industry companying of the second of th	Internet was an concerned and a second and a	າ ກາວກາວົດກູ່ວະກ່ອມກາຈູ່ຫຼາກແລ້ວ ມີ ກາວລະແປກ Examination-IED ຊື່ ເຮັກ ເຊິ່ງຜູ້ການ ອີກແນນນີ້ ເຊິ່ງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີ	000 funka a down fif boyda spyrafa syndraf an State spyrafa syndraf an State spyrafa syndraf an State spyrafa syndraf an State spyrafa syndraf an State an State	in and good to go
June Co oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop ogg oggedinop	nom industry comessage のです ngortuga (Private Congany) 300度を そのこの分子子子 い env5の名ものを そのころの子子子 そのこの分子子子 そのこの分子子子 そのころの子子子 そのこの分子子子 そのこの分子子子 そのこの分子子子 そのこの分子子子 そのこの分子子子 そのこの分子子子 そのこのの そのころの そのころの そのころの そのころの その 子子の 子子の 子子の 子子の 子子の 子子の 子子の 子子の 子子の	Internet in an and a second se	¹⁴ ກາວກາວໂຕເຫຼົາວກ່ອນກຳຜູກແຫຼ່ວ ທີ່ ກາວກາວກາວໄປ Summarian-IEE) ຊື່ ອ້າງ ອ້າງ ເຊິ່ງ ເຊີງ ເຊີງ ເຊິ່ງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີງ ເຊີ	00000000000000000000000000000000000000	in and a start of the start of

Page 143

JUNE CEMENT INDUSTRY LTD.

	Revenue		5	နယ်စို - ၂၀၁၉ ခုနှစ်၊ ခွန်လ (oil) elup
οģ	ఇంభర్త	φοδφοοδ	იყინიზნთ	ансубаноўб	полбуаб
0ì	Second St.	DOWNER SEDERER	Selector .	S. O. Q.	575
J.	8:000 868.	31/man Bosenso	Subar Ob	NUT IS TO THE	and and
$\overline{\gamma}^{q}$	And - had	The latting	to service age	- sender superior	ful a
9	Norshine	ngl de merche	0-0110.	(29)(3-)	a.
9	હનીકદેવી છે.	29mag (Rt702019)	gsenyq5 mpm	- nillinger - Brow	3-18 09-4421
61	କେଇକ୍ଷର୍ବରେହିକେଇ	30/226) (#) (030/236	udiry deal	2 (075 1 072	m Duc 9992
<u>q</u> !	Rasm	44. 35		Carlo 34 Parto 200	1 coli
0)	enent G625	2000 Dans	. Com	and fast	Roin
6ª	3065-	Minner Stenerite	201000	Criston Charles	20
DCR	2 ChiSot	Same Realers	# Ebaro	ADM S (NUD	The start of the s
10,01	Sugar S.	schwerter our son		Chillion Chillion	
ي ا	Solet Charles	1000 grap 0.14 (200	10 C C	1. C M. G. M.	Carlos and and a

June Cement Industry Limited မှ ຜູ້ຊື່ຜູ້ຊື່ນັ້ນ ເຖິງເດີ່ມແຊກຊື່ງ, ແລ້າ ແກງແຜດກອກງະຊຸກກາຊົດງດີ ກອດກາວວິດຸດວິດອ ວ່າກາວບໍ່ລຸດການເຊິ່ງແມ່ນເຊິ່ງແມ່ນເຊິ່ງແມ່ນີ້ແມ່ນ ແມ່ນ ເຊິ່ງແມ່ນ ເຊິ່ງແມ່ນດີ້ກຳຊົດແຜ່ຊື່ນຊື່ ແມ່ນ ເຊິ່ງແມ່ນີ້ ເປັ ທີ່ເປັນເຊິ່ງແມ່ນ ເຊິ່ງແມ່ນ ເຊິ່ງແມ່ນ ເຊິ່ງແມ່ນ ເຊິ່ງແມ່ນ ເຊິ່ງໃນຜູ້ກາງຊື່ຜູ້ແມ່ນ ເຊິ່ງແມ່ນ ເຊິ່ງແມ່ນ ເຊິ່ງແມ່ນ ເ

ು	လက္ခင္စာရွက္ကားရား			ရက်၌ - ၂၀၁၉ ခုနှစ်	ခွန်လ (၁၅) ရက်	
ĝo	ఇంద్ర	φαδφανδ	နေရမ်းစိမ်က	თიენთიტნ	сообуаб	
.96	8-28-18	all man gillements	Adres with	alan minuta	1/2	
J	SPROE	solwari fts cogons	M1177	field aparter	l	1
-be	Sagarmaly mat my ?	palano (2) any	thing.	Repater	Mar 09-8	estopold
ç.	Fremerer	odmina (fordare	MAN	~(1) のかのかってい	ERM	09.9918 9.840
9	aleast.	- Warier	Darn	an your of the	, DE	04-17.44
Ge	in of	allen for crew	41	0	1	71864
9						108-10
01						
81						1
008						
008						
0,8						

JUNE CEMENT INDUSTRY LTD.

June Carment Instantry Limitedမှုနှံန်ပြည်နယ်၊ တို့က်မရောမြို့နယ်၊ ကော့ပရောကျော့အဆိုတွင်အတော်ထိုက်တွင်တောင်ခြင်ကန်ထည်ထောင်ခြင်းမှင်ငန်ဆောင်ရွက်နိုင်ရန် လိုအင်ဘောတက်စစ်စီမံကိန်ရာအတွင်ကနေရီတက်နေကြင်ကန်အဖြစ်ကြက်၊tai Environmental Commistion-LEE) ထိုင်ရာလှစ်ငန်နေမှာရှင်လင်မသင်ပြည်နေနှင အျေးရပ္ပြည်ရန်ရာတူအနွေကိုလင်မြည် (Authic Consultation) အခင်အနောက်ကွက်ကားသူများကနေရီ 22

Stationard Colores

ŝ	కాటర్	1.455	ခုနှစုန်းလိမ်းဘ	თიენთიწნ	იაინყინ
01	contrap us -	99.925355295 .	308	an 2016 27:5	State
ji	airest.	telet i z	wing	82	675
9 4	e dissé	-	11	Nes	12
çx.	E og fi com	07-9656 74341	+1	NuS	DE.
9	of BE	-	emuer-	need	ANGE
Gi					Mago
q#					
99					
91					
010					
006					
, ji					
ops					24
sga					

အတိမှတ်	3000	J.G	-	CH1	121	_ 82		0																
လိပ်စာ	Guimo.	2 *	em Gass.	Guiter	> *		Sm Gyr	Sm &A.																
au D	8.24. 405.	- 601 846.	" Emession	· Brićoć.	4 NEME	5 84°	" 286.96:	- 																
ംപ്പ് എ	ě	5	.2	16	.6	6	5	G	e	20	0	-	4	- v	. 61	G	2	6	e	00	2	P	Ŷ	100

Initial Environmental Examination

ာ June Cement Industry Limitedမှုနှံပြည်နယ် ကြိုက်မေရုမြို့နယ် ကော့ပရောက္ခေရာအာအနိုးဂုင်အကောင်ထည်မော်သောင်ရွက်နိုင် ကိုအင်ဘောစက်ပေါ်မိမကိန်မှာအားတွက်ကန္ဒင်မာတ်နော်မှုဆိုမဆိုနော်ခြင်း(Initial Environmental Eusimention IEE) ဆိုင်ရာပင်မာနေကြောက်များကို နှင့် အမှာခြင့်ခြင့်ကျနှင့်ရောနော့တိုင်ကြိုင်၊ (Fubire Consultation) အခေါ်ကနေကော်ကျောက်က ကျွောကာကြောက်

o5	30005	2000	asshalion	mulmille	Sec. Sec.
-E		the second	enteringen	axdeaxde	comyes
.01	Engineeria 2 154	-	A 1764 -	man and a	85
ð.	3. Bfraf:	÷.	ίΩ	resk.	100
19	2 28	-	×M 84.	and	-52
ça	RA		Girogf.	NUS	55
9	X = St ious air	-	1607.00 2	942	2
64	ন্য ৩৪ জ্য		141	2	01
Q8	631627665		8	NIOS	6
ee.	8: Q	1			to
ga .	Franker	3	00000	Trange .	S.C.
900 B	Count 2 4		PUSAR	res S	Bare
004	3-157-5631		pero 8	0.18	- Sak
ي د	J. oglan stant	1944		wy S	6 5-7
0Ç#	3 edul and	90	Le .	1. C2	175
oge -	SAMON EARS	-	41687 8	Sec.	2000

S 12 197	Ξ.	342.0
Jure Corrent Industry Unitedygမြင့်တို့နယ် ကျွံကိုးရေးမြို့နယ်၊ ကော့မနေအတွေ	ရာအနီးခွင်အကောင်ထည့်ခေါ်ဆောင်ရွက်ရည် ဘီလင်ခြေစ	ຊຸມ3ຊີດາອູບັດແລະຊົວບັດກຸລົງດີກາງອຸບັດຊີດ
ကိုအမ်ဘောဆက်စပ်စီခဲ့ကိန်များအတွက်ကနဦးပတ်ဝန်းကုန်အန်းစစ်	ရှိခ်ီး(britial Environmental Examination-IEE) နေဒိုရောင်နှင့်ပ	န်နောက္ခတ်ကတ်တစ်ခြင်း နှင့်
အများပြည်သူနှင့်စဆွာစနှတ်ခြင်း (Put	#ic Consultation) ຂອຍອິຄລາຊວະວຽດວາກົນສຸດເກົາຕາວຊະລູສະຫະ	ifa .

იაინცინ	රිද්ශකර්දානා	ခုနှစ်လိစ်က	15485	කදෙරි	φŝ.
	1208	~~		6 (T658)5	24
57	nuS.	smap 45	09 692370846	Service Six	jı.
MA	105		09 761943540	giament	25
6354	ing is of mid !	som wege	09+20760 234	516061021	÷.
Brown	nob	a-meis	09.7991992959	A Speame	94
TA	the second	4 Sad		ST Che	54
2200	rous	more		1 430' get 1	q¥.
5.201	55	~		in the mention	64
100 cit	9.0	5		a spiriss	Pa -
0562	32	ĸ		n geden	620
the set	96	(mir		63h 27	24
220	14	15		いのちょう	ġ.
1950	in .	LL.		n of where	ę.
00%	NUS	anno Dago	09-710449831	* 210 5 85	91

Initial Environmental Examination

Page 146

δομόσο δήσουμαι καθύμαι Κατρία βριατία βριατία <t< th=""><th>Bylanding Bylanding <thbylanding< th=""> <thbylanding< th=""> <thb< th=""><th>Befo</th><th>အေးခံပြည်သူများ</th><th></th><th></th><th>ရက်ရှိ - ၂၀၀၉ ခု</th><th>နစ်၊ ဇွန်လ (၁၅) ရက်</th></thb<></thbylanding<></thbylanding<></th></t<>	Bylanding Bylanding <thbylanding< th=""> <thbylanding< th=""> <thb< th=""><th>Befo</th><th>အေးခံပြည်သူများ</th><th></th><th></th><th>ရက်ရှိ - ၂၀၀၉ ခု</th><th>နစ်၊ ဇွန်လ (၁၅) ရက်</th></thb<></thbylanding<></thbylanding<>	Be fo	အေးခံပြည်သူများ			ရက်ရှိ - ၂၀၀၉ ခု	နစ်၊ ဇွန်လ (၁၅) ရက်
第二、 「「」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」 「」」」<	Вани (Приниски) Приниски (Приниски) Приниски) Приниски (Приниски) Прински (Приниски) Прински (Приниски) Прински (Приниски) Прин	β	బంద్ర	ARTER .	იგიგიმნთ	მწილმდილ	ითებით
3 3	No. B-8 - - Ref from the second state of the second sta	-	Reco	-	a get man and	port -	604
 ・ 「見、「かってのる」 ・ 「し、かんしので、「し、かんしので、「し、かりとうり・アドレー」 ・ 「うかでかんの「うかいので、「し、かいしので、「し、かりまた」」 ・ 「うかでかんの「し、かいしので、「し、かいしので、「うかでかんの」 ・ 「し、かいしので、「し、かいしので、「し、かいしので、「うかでかんの」 ・ 「し、かしので、「し、かいしので、「し、かいしので、「し、かいしので、「し、うべい」 ・ 「し、かいしので、「し、かいしので、「し、かいしので、「し、い、し、い、し、い、し、い、し、い、し、い、し、い、し、い、し、い、し、	Від Продокций Проводи Сонсказарна со 2000 2000 года Проводи Сонсказарна со 2000 2000 года <t< td=""><td>j¢ .</td><td>-my nor</td><td>-</td><td></td><td>5-8</td><td>X</td></t<>	j¢ .	-my nor	-		5-8	X
 ・ アン・ハン・ベース はんしんがいたい しょういう ちょうり シーク 「うんしかい」 「しんかい」 「うんしかい」 「しんかいかいしかい」 「しんしかい」 「しんしかいしかいしんしかいしかいしんしかいしかいしかいしんしかいしかいっかいっかいいっんしかいいっしんしかいっしんしかいっしんしかいいっし	φ Φ - </td <td>ę.</td> <td>=3[22]</td> <td>÷</td> <td>1</td> <td>-FSP- "</td> <td>×</td>	ę.	=3[22]	÷	1	-FSP- "	×
μ μ	φ Φ	ça	Sec. 30	44 - 39 24 8Kige	encored alon	State Frenche 2871	-A'
ληθ	θe	9	E-wash	24-4252996tz	AL.	Garroso 184	-17+
μομ μομ <td>φ </td> <td>6.</td> <td></td> <td></td> <td></td> <td></td> <td>1</td>	φ	6.					1
es a a a a B a a a a a S a a a a a B a a a a a B a a a a a S a b a a b B a b a a b B a b a a b B a b a b a B a b a b a B a b a b a B a b a b a B a b a b b B a b a b a B a b a a b B a b a a b B a b a a b B a b a b a B a b a b a B a b a<	a a a a B a a a a B a a a a B a a a a B a a a a B a a a a B a b a a B a a a a B a a a a B a a a a B a a a a B b a a a B a b a a B a a a a B a a a a B a a a a B a a a a B a a a a B a a a a B a a a a B a a a a B a a a a B a a a <t< td=""><td>qe .</td><td></td><td></td><td></td><td></td><td></td></t<>	qe .					
B B </td <td>λομλου λομλου λομλου</td> <td>69</td> <td></td> <td></td> <td></td> <td></td> <td></td>	λομλου	69					
λομ	α 33 34 35 36 37 37 38 39 30 30 31 31 31 31 32 32 32 32 32 32 32 32 32 32 32 32 32 32 32 32 33 34 34 34 34 34 34 34 34 34 34 34 34 34 34	E*					
April 10g 3000 adjute jung 2000 k 1 April 10g 3000 adjut jung 2000 k 1	100 100 </td <td>0.08</td> <td></td> <td></td> <td></td> <td></td> <td></td>	0.08					
10 10 10	μ μ μ μ μ μ μ μ μ μ μ μ μ μ μ μ μ μ μ μ μ μ μ	228					
202 202 </td <td>22 23 32 32 32 32 32 32 32 32 32 32 32 32 32 32 33 32 34 32 34 32 35 32 34 32 35 32 34 32 34 32 34 32 34 32 34 32 34 32 34 32 34 32 34 34 34 34 34 34 34 34 34 34 34 34 34 34 34 34 34 34 34 34 35 34 34 34 35 34 34 34 35 34 34 34 34 34 35 34 34 34 34 34 34 34 34</td> <td>*U⁶</td> <td></td> <td></td> <td></td> <td></td> <td></td>	22 23 32 32 32 32 32 32 32 32 32 32 32 32 32 32 33 32 34 32 34 32 35 32 34 32 35 32 34 32 34 32 34 32 34 32 34 32 34 32 34 32 34 32 34 34 34 34 34 34 34 34 34 34 34 34 34 34 34 34 34 34 34 34 35 34 34 34 35 34 34 34 35 34 34 34 34 34 35 34 34 34 34 34 34 34 34	*U ⁶					
ແລະ ເຊັ່ງ ເຊິ່ງ ເຊ	ຊຸດ ຊາດ	199					
3.4 ຮັບຄາດຮູ້ອາດອຸດັດອອີດເຮັດອອີດເຮັດເຮັດອອີດເຮັດແຜ່ອອດອາດອາດອາດອາດອາດອາດອາດອາດອາດອາດອາດອາດອ	ມີຈຸດຊີເລີດແຜ່, ລະບານເຮັດເຮັດແຜ່, ແລະ	-pe					
රූ ප්රීම් ප්රත කරන්න ක කරන්න කරන්න කරන් කරන්න කරන්න කරන් කරන්න කරන්න ක කරන්න කරන්න කරන්න කරන්න කරන්න කරන් කරන්න කරන්න කරන් කරන්න කරන්න කරන කරන්න කරන්න කරන්න කරන්න කරන්න කරන් කරන්න කරන්න කරන්න කරන්න කරන්න කරන්න කරන්න කරන්න කරන්න කරන්න ක කරන්න කරන්න ක කරන්න කරන්න කරන්න කරන්න	රූ පවුදුරුවෙන්තුන්තුරුවන්න (2)						
el souti de la constante la con	and a strandymer and a strain a	ne O	entern: Instantry Linetecty	စရာမြို့နယ် စက္ကာစနာတျေးခွာအနီက္နင့်အမေ	, గారయిప్రజరంజారంభారంభారం	ulaBerhkozzászotijárovác I remo	jeanigriijiaji
a filement - amount will beginne I figheant - amount -	a Aleme - anon Nes exert I Palement - amal	ne O	ment Industry Limiteskyຊ່ອີດູລົມລະດາຊິກາດ ເດີຍແດ້ອວການປາຍໃຫ້ປາກັນອາດາຊາ ແຜ່ຊາຍີດູລົງ ສອງວຣີດີດີລົງຊາຍງານ	ိန စရာမြို့နယ်၊ စကားဖနောကျေးမွာအနီးလွှင်အမေ စီကနာ့ဦးတေီကန်းတွင်အနီးစစ်ဖြင်(Drobat Envir နန်ခိုင်ရွေးနွေးကိုင်ပင်ခြင်း (Public Consultation	"៖ ກາວັດນະລິຍະອັດຍາວດີຫຼາກິດຜູ້ຊີ ເຮັດ ermental Ecenteration=183) ຜູ້ນີ້) ເວຍຍິຍະນະຈູດກະກິດອຸດກຳບາວຈ	ပင်ရန် - ၂၃၁၃ နေနဲ အလိုးရန်ကျောင်လေးကြောင် ကိုလို - ၁၉၃၄ - ၁၉၃၄ ကိုလို - ၁၉၃၄ - ၁၉၃၄ ကိုလို - ၁၉၃၄ - ၁၉၃၄ - ၁၉၃၄ - ၁၉၃၄ - ၁၉၃၄ - ၁၉၃၄ - ၁၉၃၄ - ၁၉၃၄ - ၁၉၃၄ - ၁၉၃၄ - ၁၉၃၄ - ၁၉၃၄	န်းဆာင်ရွက်နိုင်ရန် နှင့် စန့်နိုင်င (၁၅) ရက်
3 2 sport - amal	- amile -	ne O ŝeĵŝe	ment 3400119 Limiteskyyຊີດີຜູ້ນັ້ງແມ້ວ່າ ດັ່ງກັດ ເດີຍເມື່ອວາມແຕກັດໃຫ້ໃຫ້ກ່ຽວການສູງ ແມ່ງດັ່ງຜູ້ນຶ່ງ ເຮສວວຍີຜູ້ຊີວິດູນຢູກ ສອບຊີວິ	ုန စရာရှိနယ်၊ ကော့ဖနောကျေမွှာအနီးလွှင်အမေ ကေနာ့်ဖြားတိုင်နိုက်ရောက်နောက်ကြီး(Dread Envir နိုင်ငံနောက်ပြင်နိုင် နိုင်ငံနောက်	် ကာင်ထည့်ဖော်စဆောင်ရွက်မည့် အံဂ emental Exernicalen-1657 ဆိုင် (အမမိအေနားသို့ထက်ရောက်လာဒ စနေရင်ဇဝိဇ်စာ	ပင်မြားကိုတင့်သောင်ခြင်းလုပ်ငံ ရာလုပ်ငန်းနားစွင်းလင်ထာင်ခြင်းရ ရာလုပ်ငန်း စိုက်ဆို ၂၀၁၉ ရမှ စိုက်ဆက်ရှိန် ဆက္ခပ်ဆက်ရှိ	န်ဆောင်ရွက်နိုင်ရန် နှစ် စနေနိုင်လ (၁၅) ရက် လက်မှတ်
		ne O စီရစ်ခ ချ	າກອາກ ໂກປະກາງ Linkeskyຊູຊີດີລູລິມລີ ເຊິ່ງກໍ ເດີຍເຮືອລະກະນະກໍ່ອີດີໃຫ້ເກີຊະຫຼາກອຽງ ແຫຼງສີດີລູດ ອອດຊີລິ ອອດຊີລິ ີ ຊີ ເພິ່າ ກາ ຄື	ို စရာရှိနဲ့မှသီ ဘော့စနောကျေးမွာအနီးထွစ်သမာ စံကနှိုင်တွေနေ့ကိုစိပ်ခြင်း (Pusic Consultation မှုနိုင်ရောနေ့ကိုစိပ်ခြင်း (Pusic Consultation မှုနိုင်နဲ့ ဇြတ် – လိ	් තාර්ගාුලිගේගොරදුක්සැල් න්ග emerical Examination-1657) ශ්රී () මෙමනෙදාගමුනාත්තොත්තොත් () මෙමනෙදාගමුනාත්තොත්තොත් () මෙමෙනෙදාගමුනාත් () කාල්ලාන් ()	ისიწიილნითინცნოვანი ფივსაწყოვნითნინ[წრი ფინჭ - კთვდ ფას გინჭ - კთვდ ფას აკა აკა ი აკა აკა	මුදු කරන්න කරන කරන කරන කරන කරන කරන කරන කරන කරන කර

eğ	කළේ	462.55	လမိဂိဂိန်မှာ	යදේශයේදි	လက်မှတ်
31	- Rewel		dem Ubyn	NIS	85,04
Ĵ.	7 spare	12	0~~1P	59 - C	-
ęł –	Robert Comp & mark	2	soing		mp
φ	graph acres	<u>2</u>	14	59	Train
9	6 16	2		nus	8
51	ay Big to al	cav -	ત્તીમ બ્લાન ન જાવેલિઝારુ	inort mails	6. 35-00
ų:					
es.					
8					
201					
101					
ų.					
uşu.					
190					

0	· · · · · · · · · · · · · · · · · · ·	(7)	24
	June Camari, Industry Umbedyayရှိပြည်နယ်၊ ကိုလ်မလေ့ရှိသည်။ ampicasocrayag လိုအစီအဘာဆက်ဆင်ခံရဲကိုန်းရားတွေက်ကန်ဆီများအတွက်ကနေနိုင်မည်ဆန်အနေအနိုင် အချေးရည်တွေနှင့်ဆွေစနေဖြင့်နိုင်ငံခြင်၊ (Public	ວະຊີແດງດ້ອຍອາການໂດຍງູກ້ອະກຳອາການໂຊກຳມູດູ້ງ ເກີດເບີຍຜູ້ອຸດກໍຊຸດກູມູລິແດນດີຊີດີ (Initial Environmental Examination IEE) ເຊັ່ງມີອຸດການໂດຊີແດງດີແດນດີແດດ້ Comultation) ເຮຍອົມສະຍຸກແຕ່ງດາກຳລອກກຳແດນລຸມຸມສະນຸລູດີ:	ოγδα μουσ οδησδηδηδ 1958: 48
	စုပ်မိရပ်စအသခဲပြည်သူများ	ရက်ရှိ - ၂၀၁	က ဗနစ် ခွန်လ (၁၅) ရက်

αĝ	အမည်	WEAR.	ခနုနော်လိပ်တ	အလုဒ်အကိုစ်	იიინყინ
≂ŧ	fran ge .	* <u>~</u>	marter	G	CF.
J	3-up		n - 21	·· ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	MP AS
91	erryn	-	ant mig	part	X
58	8.85	~	**** 96S	~	-22
<u>9</u> t	starry	-	out of	28	areas
84	estron ust		ч	R	63
9	altanzan	22 C	w.	~	X
C8	-9751-31	(m)	× .	~~	*
Вł	gla-als	. e	roveran.	Such	at
364	Arap and	8	warneft.	RA	25
901	Finison	7-796024872	oursequ.	P	m
ъў.	30-258	07731193575	mainte	G	EN
əpi	300 8-1-21	09425269861	5-0530.	not -	2121
991	Zantan	-	an sol	mangan	5928

(A)		2
June Centent Industry Linekosygiji ເຊິ່າລໂລດວາຍວາດົຍໂຮ້ຜ	ည်မှလ်၊ ကျိုက်မရာမြို့မှလ်၊ ကော့ပနောဘေခူးရှာအနီးဆွင်အဘောင်းဆု ကိန်မှအအတွေးက်အနှင့်အတိုသိုးကျင်ဆန်အင်ဖြင်း[Initial Environment အများဖြည့်သူနှင့်တွေးနွေးတိုင်ငံခြင်း (Public Consultation) အခါအ	ည်ဖော်ဆောင်ရွက်မည့် ဘီလပ်မြောက်ရုံတည်ဆောင်ဖြင်းပုင်ငန်းဆောင်ရွက်နိုင်ရန် tal Examination (EE) ဆိုင်ရာကုပ်ငန်းနားရှင်လင်ဆင်ပြန်ငြင်း နှင့် အနောက်ခွဲအက်ရောက်လာသူများတရင်၊

go	азыдб	phillippe -	ခေရခ်လိမ်က	အကုစ်အကိုစ်	იაიწყინ
ar	M 8-05	0.8560	30000	muss	mp
J	gue Vol	Paprae age- 400	son si	Benderen	(B)
2 8	2002		Section of	mot	i mut
9	Promist	09-25955299	อนสิทธุ์	Groß	a
9P	Popl cont		Susa P	rauSepS	
6x	grontostg.	69 MR 262947	machuom	#mpGam	GA
18	Suss (mus		බොහළ	ingina.	Abé
61	ostanen		คอร์เคล	egoli	63.60
81	A ST R		aren sa	Ro mising	12
209	PALEONE		Gensen	(m. Sup S	100
208	g. come		erro g	exan 5	28.62
3	Sunray		amo si	raph and	1758
iqe i	8 15		100 3E	100522 8	En
191	Seat of		unton R	nut . E	20

Initial Environmental Examination

9.i	e Cement Industry Limitedမှုနှစ်ပြည်နယ်၊ ကိုက်မာတွေ	န်နယ်၊ ကော့ပနေးကျေးရွာအနီးတွင်အကောင်ထည့်ခော်ဆောင်ရွက်မည့်	တီလမ်မြောက်ရဲ့တည်ထောင်ခြင်းလုပ်ငန်းဆောင်ခွက်နိုင်ရန်
	ကိုအပ်သောဆက်စပ်စိပ်ကိန်သူားသတွက်ကန	ຊິດແຕ້ດຊື່ແຈງຮັດກຊັດອອີໄດຣີລ(Initial Environmental Examination-SEE)	ဆိုင်ရာလှင်ငန်းများရှင်းလင်းတစ်ခြခြင်း နှင့်
	ารณามีกรีการสอง	consurable EES: (Public Consultation) makeness Perchaserede	งการและอางก็ร

ęŚ	ఇంద్ర	plificiti	နေရစ်ကိစ်စာ	රිද්ශකර්දාන	confiyab
-94 -	allen .	25	605008	1968.95	63
ЗF.	estora.		44	P.C.	05:
5H	esten of		with	Paras pas	ISA_
91	effen		unanto	Parias vals	5-
9	e \$100 { 008			mehro S	1000
Gi .	19982-		Geologia	0.0	a
9"	contre all ca		omis	1000	06-09
.01	ist a set		witten	20	<)
61	arrig.		60500	500	. m
008	3. B. Spartine	+4768699807	Emisery on	mal	Hr
0.00	Prof.		60203	recebergia	-
٩,٥					
0.56					
0.99					

6845000	လမံပြည်သူများ			ရက်ခွဲ - ၂၀၁၉ -	ခုနစ် စွန်လ (၁၅) ရ
ę	ෂංත්	in the second se	aqabe85es	δήσαυζητατ	იაინყინ
06	ethorger	-	with d.	nays-	OE
3	aras	· · · ·	445mg).	528	×
9 4	3-72 -2	-	- W	~ H15	254-
çı	20th mars	9771196412	Marga -	-175-	GLE-
94	Strathers.	Section of the sectio	an - G	P. Con	5MM
64	Bonsen			Arres.	Par
98	Erastonens		11	NUM	
64	estou	09 75 2235272	4	and a	No
Ex.	Eronows	-	e-sq	per l'	02
193	Bajimo	-	with g	min	april
2034	6787 53m			\$51	2600
2.)1	=Prograph	-	6.	4	24
100	Jan 2/0-	-	eren ung		000
alla -	325 me	-	rurand	-	2558

Initial Environmental Examination



APPENDIX 6 - Company Registration

009 ထောင်စုသမ္မတမြန်မာနိုင်ငံတော်အစိုးရ 009630 ဘူးစီမံကိန်းနှင့် စီးပွားရေးဖွံ့ဖြီးတိုးတက်မှုဝန်ကြီးဌာန သက်တမ်းတိုး ക്കുറ്റപ്ല....../ പറാട് – പറാപ မြန်မာနိုင်ငံ ကုမ္ပဏီများ အက်ဥပစေအရ . ဇွန် ဘိလပ်မြေ စက်မှုလက်မှုနှင့် ထုတ်လုပ်မှု လီမိတက် ကုမ္ပဏီအဖြစ် .၂၀၁၁ နှစ်၊ ... ေပြီ.....လ၊ ရက်နေ့တွင် မှတ်ပုံတင်ထားခြင်းအား ၂၀၁၃ နှစ်၊ နိုဝင်ဘာ လ၊ ၂၉ ရက်နေ့မှစ၍ သက်တမ်းတိုး ခွင့်ပြုလိုက်သည်။ ညွှန်ကြားရေးမှူးချပ် (ကိုယ်စား) (နန်းရီရီသန်း ၊ ညွှန်ကြားရေးမှူး) မှုဝ်နံမှုနှင့်တုမ္ပဏီများညွှန်ကြားမှု THE GOVERNMENT OF THE REPUBLIC OF THE UNION OF MYANMAR MINISTRY OF NATIONAL PLANNING AND ECONOMIC DEVELOPMENT **CERTIFICATE OF INCORPORATION** I hereby certify that the tenure of _____JUNE CEMENT INDUSTRY LIMITEDincorporated under the Myanmar Companies Act on <u>1* APRIL 2011</u> For Director General (Nang Yi Yi Than, Director) Directorate of Investment and Company Administration



APPENDIX 7 - Using farmland by other means permit



မွန်ပြည်နယ် ၊ တို့က်မရောမြို့နယ် ၊ ကော့ပနောကူးရွာအုပ်စု နှင့် မယ်ကရိုကျေးရွာ ၊ ကွင်းအမှတ် (၄၀၆ + ၄၀၇-က + ၄၀၈) ၊ ဦးပိုင်ပေါင်း (၁၇၂)ခု ၊ မြေဧရိယာ (၇၁၃- ၅၇) ဧကရှိ လယ်မြေအား ဒေါက်တာနုန္ဝင်း ၊ ၁၀/မလမ (နိုင်) ၁၄ခု၂၄၀ ၊ (ကုမ္ပဏီ ၊ မန်နေးဂျင်းဒါရိုက်တာ) အမှတ်(၈၀) ဆရာစံလမ်း သွယ် ၊ ဗဟန်းမြို့နယ် ၊ ရန်ကုန်တိုင်းဒေသကြီးတွင် နေထိုင်သူမှ ဘီလဝ်မြေစက်ရံ့ဆောက်လုပ်ရန်မြေအဖြစ် အသုံးပြုခွင့် ရရှိရေးအတွက် အမှုတွဲဖွင့်လှစ် တည်ဆောက်၍ မြို့နယ်/ ခရိုင်/ ပြည်နယ်လယ်ယာမြေ စီမံခန့်ခွဲမှုအဖွဲ့အဆင့်ဆင့် အစည်းအဝေး ဆုံးဖြတ်ချက်သဘောထား တို့နှင့်အတူ လယ်မြေအားအခြားနည်း အသုံးပြုခွင့် လယ်ယာမြေ ဥပဒေပုဒ်မ ၃ဝ(က) ရရှိရေးအတွက် ရည်ညွှန်းချက်ပါစာဖြင့် တင်ပြလာခြင်းနှင့် စင်လျဉ်း၍ (၄ - ၂-၂ဝ၁၆) ရက်နေ့၊ မွန်ပြည်နယ်အစိုးရအဖွဲ့ အစည်းအဝေး (၄ / ၂ဝ၁၆) ၊ဆုံးဖြတ်ချက် အပိုဒ်(၆၉)အရ လုဝ်ထုံးလုပ်နည်းနှင့်အညီ တင်ပြဆောင်ရွက်သွားရန် အကြောင်းကြားပါသည်။ ပူးတွဲ ၊ အမှုတွဲအမှတ် ၊ ၅ /၂ဝ၁၅-၂ဝ၁၆

ဝန်ကြီးချပ်(ကိုယ်စား) (ဇော်လင်းထွန်း ၊ အတွင်းရေးမှုႏ)

မိတ္ထုကို

ဝန်ကြီး ၊ စိုက်ပျိုးရေး နှင့် မွေးမြူရေးဝန်ကြီးဌာန ၊ မွန်ပြည်နယ် အုပ်ချပ်ရေးမျှး ၊ မြို့နယ်အထွေထွေအုပ်ချပ်ရေးဦးစီးဌာန၊ ကိျက်မရောမြို့ /ဒေါက်တာနန္ဝဝင်း ၊ (ကုမ္ပဏီ ၊ မန်နေးဂျင်းဒါရိုက်တာ)အမှတ်(၈၀)၊ ဆရာစံလမ်းသွယ် ၊ တာန်းမြို့နယ် ၊ ရန်ကုန်တိုင်းဒေသကြီး ရုံးလက်ခံစာတွဲ / မျှောစာတွဲ။

AAAA-4 25



ပုံစံ - ၁၅

ဗဟိုလယ်ယာမြေစီမံခန့်ခွဲမှုအဖွဲ့ လယ်မြေအား အခြားနည်းဖြင့်အသုံးပြုရန် ခွင့်ပြုမိန့်

မွန် တိုင်းဒေသကြီး/ ပြည်နယ်၊ <u>မော်လမြိုင်</u> ခရိုင်၊ <u>ကိျက်မရော</u>မြို့နယ်၊ <u>(မယ်ကရို၊</u> <u>ကော့ပနော)</u> ရပ်ကွက်/ ကျေးရွာအုပ်စုနေ ဦ<u>း မင်းသိန်း</u>၏ သား/ သမီး ဦး/ ဒေါ်/ အဖွဲ့ အစည်း <u>နုနုဝင်း</u>နိုင်ငံသား/ အမျိုးသားစိစစ်ရေးကတ်အမှတ်<u>၁၀/ မလမ (နိုင်) ၁၄၃၂၄၀</u> အား လယ်ယာမြေ ဥပဒေပုဒ်မ ၂၉ နှင့် ၃၀ တို့အရ အောက်ဗော်ပြပါ လယ်မြေကို သတ်မှတ်ထားသည့် စည်းကမ်းချက် များနှင့်အညီ အခြားနည်းဖြင့် အသုံးပြုခွင့်ပြုလိုက်သည်။

အခြားနည်းအသုံးပြုခွင့်ပြုသည့် လယ်မြေအကြောင်းအရာ _မွန်_တိုင်းဒေသကြီး/ပြည်နယ်၊ <u>မော်လမြိုင်</u> ခရိုင်၊ <u>ကျိုက်မရော မြို</u>့နယ်

n 5	ရပ်ကွက်/	တွင်း/ အကွက်	ဦးဝိုင်	-G.S.	ခွင့်ပြ ဧရိ	ျသည့် ယာ	ခွင့်ပြုသည့်	မှတ်
*E	အုပ်စု	အမှတ်နှင့် အမည်	အမှတ်	બલતી	നേ	ဒဿမ	နည်းလမ်း	ချက်
э	J	2	9	ງ	G	2	ຄ	C
	မယ်ကရို၊ ကော့ပနော	(၄၀၆၊ ၄၀၇-က၊ ၄ဂ၈)၊ ကော့လစပ်၊ ယေကရိအရှေ့၊ ပျားတောင်	ဦးဝိုင်ပေါင်း (၁၇၂) ခု	నిట్	၇၁၃	୭୧	ဘိလဝ်မြေစက်ရုံ လုပ်ငန်းသုံး မြေနေရာ	-
		မြောက်ကွင်း			၇၁၃	9?		
		12						

သက်သေခံမြေပုံပူးတွဲထားပါသည်။

ဗဟိုလယ်ယာမြေစီမံခန့်ခွဲမှုအဖွဲ့၏ (၁၉-၁ဝ-၂ဝ၁၆) ရက်နေ့ အစည်းအဝေးအမှတ်စဉ် (၃/၂ဝ၁၆) ဆုံးဖြတ်ချက်အမှတ် <u>၁(ဈ)</u> အရ လက်မှတ်ရေးထိုးထုတ်ပေးခြင်းဖြစ်သည်။

အတွင်းရေးမှူး ဗဟိုလယ်ယာမြေစီမံခန့်ခွဲမှုအဖွဲ့ နေပြည်တော်

ရီးတံဆိပ် pop

စာအမှတ်၊ ၁၅/လယ-၃ဝ (ဝဝ၁ /၂ဝ၁၆) ရက်စွဲ၊ ၂ဝ၁၆ ခုနှစ်၊ နိုဝင်ဘာလ (၂୯)ရက်



APPENDIX 8 – Plot numbers for Clay soil production

60

သို့

မြို့နယ်မြေစာရင်းဦးစီးဌာနမှူး

မြို့နယ်မြေစာရင်းဦးစီးဌာန

ကိုုက်မရောမြို့။

ရက်စွဲ၊ ၂၀၁၅ ခုနှစ်၊ ဧပြီလ (၈) ရက်

1

SI	လျှောက်ထားသူအမည်	-	ဒေါက်တာနုနုဝင်း	
ال	အဘအမည်	-	ခေါက်တာမင်းသိမ်း	
91	နိုင်ငံသားစီစစ်ရေးကတ်အမှတ်	-	၁၀/မလမ (နိန်) ၁၄၃၂၄၀	
GI	အလုပ်အကိုင်	-	မန်နေဂျင်းဒါရိုက်တာ	
31	အမြဲနေထိုင်သည့်နေရပ်လိဝ်စာ		အမှတ် (၈၀)၊ ဆရာစံလမ်းသွယ်၊ ဆရာစံမြောက်/	
~			အနောက်ရပ်ကွက်၊ ဗဟန်းမြို့နယ်၊ ရန်ကုန်တိုင်းဒေသကြီး။	

၆။ လျှောက်ထားသည့်မြေ၏ အကြောင်းအရာ

စဉ်	ကျေးရွာအုပ်စု/ ကျေးရွာ	ကွင်း/ဓာကွက် ဓာမှတ် နှင့်အမည်	39%	မြေမျိုး/ အတန်း	ဧရိယာ ကေ	မှတ်ချက်
С	မယ်ကရို	၄၀၆/ကော့လစပ်	o	నింద	کې ا	
J	မယ်ကရို	၄၀၆/ကော့လစစ်	9/0+J	నియ	6.09	
	မယ်ကရို	၄၀၆/ကော့လစပ်	g/0 m	လယ်	9.00	
9	မယ်ကရို	၄၀၆/ကော့လစပ်	9/00	လယ်	J. 02	
2	မယ်ကရို	၄၀၆/ကော့လစစ်	3/J	രയ	2.09	
6	မယ်ကရို	၄၀၆/ကော့လစပ်	9+9 \C	လယ်	6. 06	
2	မယ်ကရို	၄၀၆/ကော့လစစ်	G	లులు	9.12	
Ð	မယ်ကရို	၄၀၆/ကော့လစစ်	2	လယ်	n. p6	
e	မယ်ကရို	၄၀၆/ကော့လစပ်	0	സധ്	9. nG	
oc	မယ်ကရို	၄၀၆/ကော့လစပ်	00	സധ്	00.00	
00	မယ်ကရို	၄၀၆/ကော့လစပ်	ာ၂	నులక	1. 26	
oj	မယ်ကရို	၄၀၆/ကော့လစပ်	90	నింద	2.20	
90	မယ်ကရို	၄၀၆/ကော့လစပ်	09	యి	Gn. 00	
99	မယ်ကရို	၄၀၆/ကော့လစပ်	၁၅	యిట్	20.00	
ວງ	မယ်ကရို	၄၀၆/ကော့လစပ်	JJ/J	లు	ال 00	
3c	မယ်ကရို	၄၀၆/ကော့လစပ်	11/2	యిట్	2.00	



-			-
		,	
	-		

¢	ကျေးရွာအုပ်စု/ ကျေးရွာ	ကွင်း/အကွက် အမှတ် နှင့်အမည်	ද්ංරි	်မြေမျိုး/ အတန်း	ရေိယာ ကေ	မှတ်ချက်
20	မယ်ကရို	၄၀၆/ကော့လစစ်	9L	രാഹ്	9. JC	
ວຄ	မယ်ကရို	၄၀၆/ကော့လစပ်	J9	నుయ	9.60	
୍ଚତ	မယ်ကရို	၄၀၆/ကော့လစပ်	jG	രാധ്	9.00	
jo	မယ်ကရို	၄၀၆/ကော့လစပ်	၂၈/ ວ	രയ്	٥٥ ر	
q	မယ်ကရို	၄၀၆/ကော့လစပ်	99/0	లయ	ວ. ຄວ	
IJ	မယ်ကရို	၄၀၆/ကော့လစပ်	99/5	నియ	9.00	
9L	မယ်ကရို	၄၀၆/ကော့လစပ်	ენ	నియ	2. 90	
J9	မယ်ကရို	၄၀၆/ကော့လစပ်	3 2	లు	p. 0p	
JD	မယ်ကရို	၄၀၆/ကော့လစပ်	DC	<u></u> ని సార్	0.98	
ß	မယ်ကရို	၄၀၆/ကော့လစပ်	N 2	నియ	ი. ეი	
J2	မယ်ကရို	၄၀၆/ကော့လစပ်	N 65	లయ	J. 99	
Jo	မယ်ကရို	၄၀၆/ကော့လစပ်	N 68	నియ	9.00	
R	မယ်ကရို	၄၀၆/ကော့လစစ်	N 79	లు	0.00	
90	မယ်ကရို	၄၀၆/ကော့လစစ်	N 82	యి	0.00	
cq	မယ်ကရို	၄၀၆/ကော့လစစ်	N 6	నియ	J. 00	
					၁ 6၈. ၃၁	



			- 9 -			
දේ	ကျေးရွာအုပ်စု/ ကျေးရွာ	ကွင်း/အကွက် အမှတ် နှင့်အမည်	දීංදිර්	မြေမျိုး/ အဘန်း	ဧရိယာ ဧက	မှတ်ချက်
э	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	0/0	నింద	2. 29	
J	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	o/J	രാഹ്	· 60	
9	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	J/o	నులు	6.00	
9	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	9	యి	9.00	
2	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	9	నియ	p. 00	
G	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	g/0	నియ	J. 67	
2	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	ე/ით	నియ	0.00	
Ð	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	3/J	నియ	n. 09	
e	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	9/2	నులు	6. 92	
00	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	6/0	నుయ్	9.00	
00	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	6/1	యి	g. 00	
ວງ	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	2/J	లు	2.00	
90	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	ຄ	నుయ	g. 00	81 C
99	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	e/0	లులు	5. JJ	
აე	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	ഭ/ ൃന	രാഹ്	J. 96	
96	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	e/.jə	లులు	J. 95	
Sc	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	e/9	లులు	ე. კი	
ວດ	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	00	లుయ	g. 62	
90	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	00/0	యి	P. 98	
ю	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	00/1	లులు	9.98	
p	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	oj	నుట్	9.98	
IJ	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	သင်သ	രാഗ്	p. 0J	
9L	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	6 90	లు	6. 65	
J9	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	ဝခုယ	నులు	9.00	
IJ	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	op c	സധ്	J. 32	
ß	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	အ ၄၀	నుయ	J. 90	
22	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	0 90	నులు	9.00	
jn	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	29/0	രാധ്	P. 22	
e	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	o6/om	സധ്	9.00	
20	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	o6/00	నింద	G. ,9	



စဉ်	ကျေးရွာအုပ်စု/ ကျေးရွာ	ကွင်း/အကွက် အမှတ် နှင့်အရည်	දිඃදිදි	မြေမိုး/ အတန်း	ရေိယာ ကေ	မှတ်ချက်
69	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	o€/J	ంట్	99 بل	
LA	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	ം(/ിം	ంట్	ol .9	
99	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	02/0	లు	o. 60	
99	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	02/J	രാഹ്	0.62	
C9	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	02/2	నియ	p. 00	
Øg	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	22/9	လယ်	9. PJ	
55	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	ວຄ/ວ	లు	ي. 69	
ခု၈	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	ວຄ/ງ	నింగ	კ. ე ი	
98	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	on/2	లు	J. 06	
90	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	o[/90	యి	p. 09	
90	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	0e/J	లులు	p. 09	
9J	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	0@/P	నుయ	p. 09	
99	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	08/9	నుయ	2.09	
99	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	jo	నుయ	२. ७२	
90	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	j0/0	నుయ	9.02	
, 6	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	JP/J	నులు	p. 20	
72	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	Ju/o	లులు	00 بل	
<u>20</u>	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	JJ/J	నుయ	ەە بل	
7C	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	9/LL	లులు	ره در	
90	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ	SL.	లులు	2.90	
jo l	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	J0/0	లులు	9. Co	
ม	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	Jo	లులు	9.99	
90	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	Je/J	లుల్	9.00	
09	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	99	యి	00.00	
00	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	62	ວບເວັ	9.89	
ß	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	26/0	యి	9.09	
20	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	26/1	ంట్	6. 65	
ງຄ	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	22/00	లులు	اگە بر	
90	မယ်ကရို	၄၀၇ က/မယ်ကရိအရှေ	272/0	లులు	1.00	
io	ယ်ေကရိ	၄၀၇ က/မယ်ကရိအရေ	202/1	လယ်	6 20	



- ၅ -

¢	ကျေးရွာအုပ်စု/ ကျေးရွာ	ကွင်း/အကွက် အမှတ် နှင့်အမည်	ဦးဝိုင်	မြေမျိုး/ အတန်း	ဧရိယာ ဧက	မှတ်ချက်
60	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	929/9	నియ	٥٥ ر	
61	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	pe	నిల	9.00	
Gp	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	No	്രയ	o. 69	
69	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	NP	నించ	9.00	
69	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	Ng	నిల	o. 60	
GG	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	No	నియ	ი. ეი	
62	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	No	నిల	9.90	
Gn	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	N oo	ంట్	p. 00	
60	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	N oo	ంయ	٥٥ ا	
ço	မယ်ကရို	၄၀၇ က/မယ်ကရိုအရှေ့	N 99	నిల	0.99	
					J&J. 2J	



APPENDIX 9 - Corporate Social Responsibility











(၃၁.၁၀.၂၀၁၈)

ဘုန်းတော်ကြီးကျောင်းများအတွက် ကထိန်းသင်္ဃန်းလှူဒါန်းခြင်း။ (၂,၄၅၀,၀၀၀ိ/-)





(၁၉-၇-၂၀၁၆)





ဘုန်းတော်ကြီးကျောင်းများအတွက် ဝါဆိုသင်္ကန်းလှုုဒါန်းခြင်း (၁,၂၀၀,၀၀၀/-)





(20. 2. 100%)





ကိုုက်မရောမြို့နယ် အခမဲ့ကုသိုလ်ဖြစ် ဆေးကုခန်း လစဉ်အလှူငွေနှင့် မျက်စိခွဲစိတ်ခြင်း အလှူငွေ (၂,၉၀၀,၀၀၀ိ/-)









ကော့ပနော၊ ကော့ဒွန်း၊ ဝဲငဲ့ကျေးရွာများရှိ သက်ကြီးပုဂ္ဂိုလ် (၉၀)ဦးအတွက် အလျှငွေ (၁,၈၀၀,၀၀၀ိ/-)











ကိုက်မရောမြို့နယ် မယ်ကရိုကျေးရွာ ရေဘေးအတွက် လှူဒါန်းခြင်း ရေသန့် (၂၀၉)ဗူး၊ ဆန် (၁၀) အိတ် (၄၄၉,၄၄၀/-)









ကိျက်မရောမြို့နယ်၊ မယ်ကရိုကျေးရွာ ရေဘေးအတွက် လျှဒါန်းခြင်း ရေသန့် (၁၈၂၅)ဘူး ၊ ခေါက်ဆွဲခြောက် (၁၆၂၀) ထုပ်၊ ဆန် (၃) အိတ်၊ ဆီ (၃) ဘူး (၇၄၁,၂၀၀ိ/-)



APPENDIX 10 - Consultant Registration Certificate



The Ministry of Natural Resources and Environmental Conservation, hereby, issues this certificate to the organization under Environmental Impact Assessment Procedure, Notification No. 616/2015.

(ပတ်ဝန်းကျင် ထိခိုက်မှုဆန်းစစ်ခြင်းဆိုင်ရာ လုပ်ထုံးလုပ်နည်း၊ အဓိန့်ကြော်ငြာစာအမှတ်၊ ၅၁၆/၂၀၁၅ အရ သယံဓာတနှင့် သဘာဝပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဝန်ကြီးဌာနသည် ဤအထောက်အထားလက်မှတ်ကို အဖွဲ့အစည်းအား ထုတ်ပေးလိုက်သည်။)

- (a) Name of Organization (ශවූ ශාවේ: ශාවේ)
 (b) Name of the representative in the
- (b) Plance of the representative in the organization (အဖွဲ့အစည်းကိုယ်စားလှယ်၏ အမည်)
- (c) Citizenship of the representative in the organization
 (အဖွဲ့အစည်းကိုယ်စားလှယ်၏ နိုင်ငံသား)
- (d) Identity Card /Passport Number of the representative person in the organization (အဖွဲ့ အစည်းကိုယ်စားလှယ်၏ မှတ်ပုံတင်/ နိုင်ငံကူးလက်မှတ် အမှတ်)
- (e) Address of organization (ဆက်သွယ်ရန်လိပ်စာ)
- (f) Type of Consultancy (အကြံပေးလုပ်ကိုင်မှုအမျိုးအစား)
- (g) Duration of validity (သက်တမ်းကုန်ဆုံးရက်)

E Guard Environmental Services Co., Ltd.

U Aye Thiha

Myanmar

12/ MRK (Naing) 069784

No. 99, Mya Kan Thar Lane, Nyein Chan Yay Street, 10 Miles, Pyay Road, Saw Bwar Gyi Gone, Insein Township, Yangon. info@eguardservices.com, 09448001676 Organization

31 March 2018

EXTENSIO to (11.3.2010)

Director General Department Environmental Conservation Department Ministry of Natural Resources and Environmental Conservation





The Ministry of Natural Resources and Environmental Conservation, hereby, issues this certificate to the person under Environmental Impact Assessment Procedure, Notification No. 616/2015.

(ပတ်ဝန်းကျင် ထိနိုက်မှုဆန်းစစ်ခြင်းဆိုင်ရာလုပ်ထုံးလုပ်နည်း၊ အမိန့်ကြော်ငြာစာအမှတ်၊ ၅၁၆/၂၀၁၅ အရ သယံစာတနှင့် သဘာဝပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဝန်ကြီးဌာနသည် ဤအထောက်အထားလက်မှတ်ကို လူပုဂ္ဂိုလ်အားထုတ်ပေးလိုက်သည်။)

(a) Name of Consultant (အကြံပေးပုဂ္ဂိုလ်အမည်) U Tin Aung Moe

- (b) Citizenship (နိုင်ငံသား)
- (c) Identity Card / Passport Number
 (မှတ်ပုံတင်/ နိုင်ငံကူးလက်မှတ် အမှတ်)
- (d) Address (ဆက်သွယ်ရန်လိပ်စာ)
- (e) Organization (အဖွဲ့အစည်း)
- (f) Type of Consultancy (အကြံပေးလုပ်ကိုင်မှုအမျိုးအစား)
- (g) Duration of validity (သက်တမ်းကုန်ဆုံးရက်)

Myanmar

12/ Ma Ga Ta (Naing) 028014

99, Mya Kan Thar Lane, Nyein Chan Yay Street, 10 Mile, Pyay Road, Saw Bwar Gyi Kone Ward, Insein Township, Yangon Northern District, Yangon.

tinaungmoe@eguardservices.com , tinaungmoel@gmail.com , 09 49321511 , 09 420330417 E Guard Environmental Services Co., Ltd.

Person

31 March 2018

2.000

Director General Environmental Conservation Department Ministry of Natural Resources and Environmental Conservation


63

Areas of Expertise Permitted (စွင့်ပြုသည် ကျွမ်းကျင်မှုနယ်ပယ်များ)

1

a let

1. Facilitation of Meeting

2. Land Use

ş

.

3. Risk Assessment and Hazard Management

4. RS & GIS

63





The Ministry of Natural Resources and Environmental Conservation, hereby, issues this certificate to the person under Environmental Impact Assessment Procedure, Notification No. 616/2015.

(ပတ်ဝန်းကျင် ထိခိုက်မှုဆန်းစစ်ခြင်းဆိုင်ရာလုပ်ထုံးလုပ်နည်း၊ အမိန့်ကြော်ငြာစာအမှတ်၊ ၅၁၆/၂၀၁၅ အရ သယံဓာတနှင့် သဘာဝပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဝန်ကြီးဌာနသည် ဤအထောက်အထားလက်မှတ်ကို လူပုဂ္ဂိုလ်အားထုတ်ပေးလိုက်သည်။)

Myanmar

 (a) Name of Consultant (ශාරිගෙදාර්ලිල්කාන්ත්) U Aung Myint Myat

9/ Ka Pa Ta (Naing) 214545

Township, Mandalay Region.

09 797005168 , 09 794555989

Mudita lane, Loklatyae Quarter, Kyaukpadaung

aungmyintmyat@eguardservices.com ,

E Guard Environmental Services Co., Ltd.

- (b) Citizenship (ຊີຣ໌ຮ່ວນາ:)
- (c) Identity Card / Passport Number
 (မှတ်ပုံတင်/ နိုင်ငံကူးလက်မှတ် အမှတ်)
- (d) Address (ဆက်သွယ်ရန်လိပ်စာ)
- (e) Organization (ශල්ශාවෝ:)
- (f) Type of Consultancy (အကြံပေးလုပ်ကိုင်မှုအမျိုးအစား)
- (g) Duration of validity (သက်တမ်းကုန်ဆုံးရက်)

EXTENSION autorosite (Got The VALIDITY of this certificate is extended for one year from (1.4.2018) to (31.3.2019) officerbuctures (e-e-sole) approxy (co.p. sole) approxy and cobsecutive of (got co.p. sole) approxy and cobsecutive of (got co.p. sole) approxy approxy (co.p. sole) Person

31 March 2018

in losa

Director General Environmental Conservation Department Ministry of Natural Resources and Environmental Conservation



Areas of Expertise Permitted (ခွင့်ပြုသည့် ကျွမ်းကျင်မှုနယ်ပယ်များ)

1. Forestry





THE REPUBLIC OF THE UNION OF MYANMAR

Ministry of Natural Resources and Environmental Conservation



Environmental Conservation Department

CERTIFICATE FOR TRANSITIONAL CONSULTANT REGISTRATION

(ကြားကာလအကြံပေးလုပ်ကိုင်သူမှတ်ပုံတင်ခြင်းအထောက်အထားလက်မှတ်)

No.	10223	Date	2 4 MAY 2019
		1000 C	

The Ministry of Natural Resources and Environmental Conservation, hereby, issues this certificate to the person under Environmental Impact Assessment Procedure, Notification No. 616/2015.

(ပတ်ဝန်းကျင်ထိခိုက်မှုဆန်းစစ်ခြင်းဆိုင်ရာလုပ်ထုံးလုပ်နည်း၊ အမိန့်ကြော်ငြာစာအမှတ်၊ ၆၁၆/၂၀၁၅ အရ သယံစာတနှင့် သဘာဝပတ်ဝန်းကျင်ထိန်းသိမ်းရေးဝန်ကြီးဌာနသည် ဤအထောက်အထားလက်မှတ်ကို ထုတ်ပေးလိုက်သည်။)

(a)	Name of Consultant	U Si Thu Min Naing	
	(အကြံပေးပုဂ္ဂိုလ်အမည်)		
(b)	Citizenship	Myanmar	
	(နိုင်ငံသား)		
(c)	Identity Card / Passport Number	9/AhMaZa (Naing) 032489	
	(မှတ်ပုံတင်/ နိုင်ငံကူးလက်မှတ် အမှတ်)		
(d)	Address	No. 11, Airport Avenue Road, Yangon Airport Road,	

(ဆက်သွယ်ရန်လိပ်စာ)

Saw Bwar Gyi Gone Quarter, Insein Township, Yangon, Myanmar, Mobile phone: 09 797005217, 09 43096583,

E mail: sithuminnaing@eguardserveses.com E Guard Environmental Services Co., Ltd.

Organization (e) (အဖွဲ့ အစည်း)

(f) Type of Consultancy (အကြံပေးလုပ်ကိုင်မှုအမျိုးအစား)

Duration of validity (g) (သက်တမ်းကုန်ဆုံးရက်)

Person



Director General Environmental Conservation Department Ministry of Natural Resources and Environmental Conservation